




# Austria








#### **Bidirectional Austrian Czech Interconnection (BACI, formerly LBL project)** TRA-N-133 Non-FID

# **Pipeline including CS**


# **SPONSORS**

# GENERAL INFORMATION

# FINANCING



Promoter	NET40	GAS, s.r.o.
Operator	NET40	GAS, s.r.o.
TEN-E Project ?	Project of Co	ommon Interest
Interested by PCI ?		Yes
IGAs	N	lone
Web Link		
TEN-E Requests	Date of Request 27/02/12	Year Funding Granted Not yet



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2019
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+58,00
Total Compressor Power (MW)	+24,00
Maximum Capacity (GWh/d)	+254,00
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Reinthal - Bidirectional Austrian-Czech Interconnector	Yes	exit	254,00	Hub Czech Republic	Hub Austria
	Yes	entry	254,00	Hub Austria	Hub Czech Republic
DESCRIPTION OF THE PROJECT					
The BACI will be a new infrastructure directly connecting the Austrian and Cze	ech market. I	t will be conr	nected to the existing Cze	ch transmission system via C	S Břeclav (NET4GAS, s.r.o.) and to the Austrian transmission system via
Baumgarten (GAS CONNECT AUSTRIA GmbH). The BACI will enable capacity tra countries like Hungary, Poland, Germany, Italy, France, Slovenia, Croatia and Slov	nsmission for	the first time	e between these two men	nber states and it will facilitate	te better market integration and security of gas supply also for adjacent
system by diversification of gas supply routes and by connecting UGS in the Czech			i additional transportation	opportunities. The project wi	il also increase the overall hexibility of the Czech, Austrian and also Polish
EXPECTED BENEFITS					
Security of Supply, Market integration (CEE Region), Reverse Flows, Diversification	n of sources, I	Diversification	of routes, N-1 National (C	Z, AT), N-1 Regional (CEE Regional	on), Back-up for renewables, Power-to-gas, Biogas
CONMACNITY A DOLLT THE DROUGT FINANCING					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




#### **Bidirectional Austrian-Czech Interconnector (BACI, formerly LBL project)** TRA-N-021 Non-FID

# **Pipeline including CS**


# **SPONSORS**

# GENERAL INFORMATION

# FINANCING



Promoter	Gas Connect	Austria GmbH
Operator	Gas Connect	Austria GmbH
TEN-E Project ?	Project of Cor	mmon Interest
Interested by PCI ?	Y	es
IGAs	No	one
Web Link		
TEN-E Requests	Date of Request 27/02/12	Year Funding Granted Not yet



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2019
Last completed Phase :	Planned


TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	2
Total Pipeline Length (km)	+58,00
Total Compressor Power (MW)	+24,00
Maximum Capacity (GWh/d)	+255,13
Expected Load Factor	



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Reinthal - Bidirectional Austrian-Czech Interconnector	Yes	exit	255,13	Hub Austria	Hub Czech Republic
	Yes	entry	255,13	Hub Czech Republic	Hub Austria
DESCRIPTION OF THE PROJECT					
The first pipeline connecting the Austrian and the Czech Markets					
EVOLUTED DEVICE CO.					
EXPECTED BENEFITS					
Security of Supply, Market integration (Austrian Market, Czech Market), Reverse of Russian gas to the West,	Flows, Divers	ification of so	ources, Diversification of rou	utes, N-1 National (Austria, Cz	ech Republic), N-1 Regional (CEE Region), Extension of transport capacity
Integration of Nord Stream off- and on-Shore in the European gas infrastructure					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing

PROJECTED CAPACITY INCREASES

# Belgium









TRA-F-205	Alveringem-Maldegem	FID

**SPONSORS** 

# GENERAL INFORMATION



Promoter	Fluxys Belgium
Operator	Fluxys Belgium
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	www.fluxys.com/nl- BE/services/transmission_1/openseasons/~/media/files/services/transmission/openseasonfrancebelgium/bindingphase/informationmemorandum%20pdf.ashx



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	Not relevant
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2014 Q3
FID	2012 Q2
Construction	2015 Q1
Commissioning	2015 Q4
Last completed Phase :	

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+74,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+270,00
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
New IP FR-BE (FR) / Alveringem-Maldegem (BE)	Yes	entry	270,00	Hub France(PEG North)	Hub Belgium
DESCRIPTION OF THE PROJECT					
A new interconnection point between GRTgaz and Fluxys near Veurne (Alveringe the IPs of the zone of Zeebrugge (IZT/HUB, ZPT and LNG terminal) and the North-				gas from France to Belgium. Tha	nks to this new connection, the terminal of Dunkirk will be linked with
EXPECTED BENEFITS					
Security of Supply, Market integration (This project gives a connection from the LNG terminal of Dunkirk and the PEG-Nord to Belgium and the international markets of North-West Europe.) Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (Belgium), N-1 Regional (NW Europe), Back-up for renewables					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing		M	ultilateral financing




TRA-N-270	Zeebrugge Compression Project	Non-FID

# **SPONSORS**

# GENERAL INFORMATION



Promoter	Fluxys Belgium
Operator	Fluxys Belgium
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	2014 Q1
Construction	2014 Q3
Commissioning	2016 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	
Total Compressor Power (MW)	+30,00
Maximum Capacity (GWh/d)	+540,00
Expected Load Factor	



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Zeebrugge ZPT	Yes	entry	55,00	Supplier Norway	Hub Belgium
DESCRIPTION OF THE PROJECT					
A compressor station downstream of the ZPT terminal to compress the gas from t	the Zeepipe. 1	his will allow	to reduce the outlet pressu	re of the ZPT terminal, thus in	ncreasing the Zeepipe capacity.
EXPECTED BENEFITS					
Security of Supply					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing


PROJECTED CAPACITY INCREASES




TRA-N-206	Luxembourg Pipeline	Non-FID

SPONSORS

# GENERAL INFORMATION



Promoter	Fluxys Belgium / Creos
Operator	Fluxys Belgium
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2016
Last completed Phase :	

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+50,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+10,85
Expected Load Factor	



PROJECTED CAPACITY INCREASES						
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone	
DESCRIPTION OF THE PROJECT						
Pipeline upgrade to increase capacity from Belgium to Luxembourg by reinforcin from Fluxys network.	g the current	: DN300 secti	on from Bras to Petange	by DN500. It results in a capac	ity increase of 10.85 GWh/d on Creos side due to higher delivery pressi	ıre
EXPECTED BENEFITS						
County of County Market has been also (DE / LDV). Discussification of county	:6:+:6	N. 4 N+	:\			
Security of Supply, Market integration (BE/LUX), Diversification of sources, Divers	ification of ro	utes, N-1 Nat	ionai (Luxembourg), Back	-up for renewables		
COMMENTS ABOUT THE PROJECT FINANCING						
Public financing	Private fina	ncing			Multilateral financing	




TRA-N-056	Zeebrugge Compression Project	Non-FID	
Pipeline including CS			

GENERAL INFORMATION

SPONSORS

Gassco (100%)

# Promoter Gassco AS Operator Gassco AS TEN-E Project ? Not part of TEN-E Interested by PCI ? IGAs None Web Link



THIRD-PARTY ACCESS REGIME		SCHEDULE		TECHNICAL INFORMATION	
Considered TPA Regime		End of permitting phase		# of Pipelines, nodes, CS	
Considered Tariff Regime		FID	2014 Q1	Total Pipeline Length (km)	
Applied for Exemption ?		Construction		Total Compressor Power (MW)	
Exemption granted ?		Commissioning	2016 Q4	Maximum Capacity (GWh/d)	
% Exemption in entry direction	0%	Last completed Phase :	Planned	Expected Load Factor	
% Exemption in exit direction	0%				



Interconnection	Modelled	Direction	Capacity (	(GWh/d)	From Zone	To Zone
Zeebrugge ZPT	Yes	exit		52,80	Supplier Norway	Hub Belgium
DESCRIPTION OF THE PROJECT						
Main scope in installation of a new compressor at the Zeebrugge Terminal to incr	ease exit capa	city from Ga	ssled .			
EXPECTED BENEFITS						
Security of Supply, Extension of transport capacity of Russian gas to the West, Int	egration of No	ord Stream of	ff- and on-Sh	hore in the Euro	pean gas infrastructure	
COMMENTS ABOUT THE PROJECT FINANCING						
Public financing	Private fina	ncing				Multilateral financing

PROJECTED CAPACITY INCREASES




# LNG-N-229 LNG Terminal Zeebrugge - Capacity Extension & 2nd Jetty Non-FID


**LNG Terminal** 

**SPONSORS** 

# GENERAL INFORMATION



Promoter	Fluxys LNG
Operator	Fluxys LNG
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME		S
Considered TPA Regime	Regulated	E
Considered Tariff Regime	Regulated	F
Applied for Exemption ?	No	С
Exemption granted ?	No	C
% Exemption in entry direction	0%	L
% Exemption in exit direction	0%	

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2017
Last completed Phase :	

TECHNICAL INFORMATION	
Regasification facility	LNG Terminal Zeebrugge
Expected volume (bcm/y)	+3,00
Storage capacity (m3)	+180.000,00
Send-out (mcm/d)	+10,80
Ship size (m3)	
Reloading ability ?	Yes



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Zeebrugge LNG	Yes	exit	118,80	LNG Terminals Belgium	Hub Belgium
DESCRIPTION OF THE PROJECT					
construction or a second jetty for pertning of ting ships with a capacity from appr	roximateiv 35	OO M" LING UE	) to 217000 m² Ling.		
,	, , , , , ,				
Construction of an additional storage tank with a capacity of 180000 m <sup>3</sup> LNG.					
Construction of additional cond-out canacity of 450000 m³(n)/h					
EXPECTED BENEFITS					
EXPECTED BENEFITS					
Security of Supply, Market integration (The increase of capacity will contribute					
capacity.), Diversification of sources, Diversification of routes, N-1 National (Belgi	um), N-1 Keg	ionai (NVV Eur	rope), Back-up for renewab	es, Higher Flexibility for the m	arket due to ennanced reloading capacity
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing

PROJECTED CAPACITY INCREASES

# **Bosnia Herzegovina**









TRA-N-224	Gaspipeline Zenica - Brod	Non-FID
	· · · · · · · · · · · · · · · · · · ·	

# **SPONSORS**

# GENERAL INFORMATION



Promoter	BH Gas d.o.o.
Operator	BH Gas d.o.o.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME				
Considered TPA Regime	Negotiated (e.g. Exemption)			
Considered Tariff Regime	Negotiated (e.g. Exemption)			
Applied for Exemption ?	No			
Exemption granted ?	No			
% Exemption in entry direction	0%			
% Exemption in exit direction	0%			

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2022*
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+130,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+0,02
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
The starting point of the Bosanski Brod – Zenica gas pipeline is in close vicinity Republic of Croatia. Point of interconnection between Croatian and BiH natural g	of Bosanski E as transmissic	Brod where it n network is I	should be connected to th Bosanski Brod/Slavonski Bro	ne high-pressure gas pipeline od.	e leading from Zagreb via Kutina to Slavonski Brod (TSO – Plinacro) in the
EXPECTED BENEFITS					
Security of Supply, Market integration, Reverse Flows, Diversification of sources,	Diversification	n of routes, N-	1 Regional, Power-to-gas		
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing

# Bulgaria








# TRA-N-137 Interconnection Bulgaria - Serbia Non-FID


# **Pipeline including CS**

# SPONSORS

# GENERAL INFORMATION



Promoter	Bulgarian Ministry of Economy, energy and tourism		
Operator	Bulgartransgaz EAD		
TEN-E Project ?	Not part of TEN-E		
Interested by PCI ?	Yes		
IGAs	2		
Web Link	www.bulgartransgaz.bg		



THIRD-PARTY ACCESS REGIME				
Considered TPA Regime	Regulated			
Considered Tariff Regime	Regulated			
Applied for Exemption ?	No			
Exemption granted ?	No			
% Exemption in entry direction	0%			
% Exemption in exit direction	0%			

SCHEDULE	
End of permitting phase	
FID	
Construction	2015
Commissioning	2015
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	2
Total Pipeline Length (km)	+155,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+51,00
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Interconnector BG RS	Yes	entry	51,00	Hub Serbia	Hub Bulgaria
	Yes	exit	51,00	Hub Bulgaria	Hub Serbia

DESCRIPTION OF THE PROJECT				
This is the first interconnection between the gas transmission systems of Serbia and Bulgaria. The project establishes a connection between the Bulgarian and Serbian gas markets that currently are not connected.				
EXPECTED BENEFITS				
Security of Supply, Market integration, Reverse Flows, Diversification of sources, Diversification of routes, N-1 National, N-1 Regional, The projects listed above should enhance the system flexibility and contribute to the security of supply within the region (increased interconnection between Bulgaria and Serbia)				
COMMENTS ABOUT THE PROJECT FINANCING				
Public financing	Private financing	Multilateral financing		




# TRA-N-145 Black Sea CNG Non-FID


# **Pipeline including CS**

# SPONSORS

# **GENERAL INFORMATION**



Promoter	Bulgartransgaz EAD
Operator	Bulgartransgaz EAD
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	2
Web Link	www.bulgartransgaz.bg/



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	Not relevant
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2015
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	
Total Pipeline Length (km)	
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
nterconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
Project for delivery of compressed natural gas (CNG) through Black Sea. The realize	ation of the p	project depen	nds on the progress of the S	outhern Gas Corridor project	S.
EXPECTED BENEFITS					
Security of Supply, Diversification of sources, Diversification of routes, N-1 National Free CNG project is a direct connection of the EU with the gas sources of the Caucathe SEE Region (gas-to-gas competition) and will promote the real liberalisation of supply for Bulgaria and the SEE region.	asus and Cas	pian regions			
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing



# Construction of new gas storage facility on the territory of Bulgaria UGS-N-141 Non-FID **Storage Facility**


SPONSORS



Bulgartransgaz EAD (100%)

# GENERAL INFORMATION

Promoter	Bulgartransgaz EAD
Operator	Bulgartransgaz EAD
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	www.bulgartransgaz.bg/index.php



THIRD-PARTY ACCESS REGIME		SCHEDULE		TECHNICAL INFORMATION	
Considered TPA Regime	Regulated	End of permitting phase		Storage facility	new gas storage facility on the territory
Considered Tariff Regime	Regulated	FID		Working volume (mcm)	
Applied for Exemption ?	No	Construction	2020	Injectability (mcm/d)	
Exemption granted ?	No	Commissioning	2020	Deliverability (mcm/d)	
% Exemption in entry direction	0%	Last completed Phase :	Planned		
% Exemption in exit direction	0%				



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
Under considerations are several option for construction of new gas storage facil	lity on the terr	itory of Bulga	ria – depleted gas field (or	nshore or offshore), salt caverr	n or aquifer.
The new gas storage facility will be interconnected with the existing gas transmis	sion system o	n the territory	y of Bulgaria.		
Construction of new gas storage facility on the territory of Bulgaria is very impor-	tant in order t	o enhance the	e level of the security of ga	s supply and to fulfil the requi	irements of Regulation 994/2010.
EXPECTED BENEFITS					
Security of Supply, N-1 National, N-1 Regional					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-F-143

# Enabling permanent bi-directional capacity in the existing interconnection point between Bulgaria and Greece

FID

# **Pipeline including CS**


# **SPONSORS**



# GENERAL INFORMATION

Promoter	Bulgartransgaz EAD
Operator	Bulgartransgaz EAD
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	www.bulgartransgaz.bg/





THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2013
Last completed Phase :	Market test

TECHNICAL INFORMATION
# of Pipelines, nodes, CS
Total Pipeline Length (km)
iotai ripeille Lengtii (kiii)
Total Compressor Power (MW)
· · ·
Maximum Capacity (GWh/d)
Maximum capacity (GVIII) a)
Expected Load Factor



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Kula (BG) / Sidirokastron (GR)	Yes	entry	38,50	Hub Greece	Hub Bulgaria
DESCRIPTION OF THE PROJECT					
In line with the provisions of Regulation (EC) 994/2010 to enable permanent bion the interconnection point with Greece: Kula/Sirirokastro amounting to 3.5 mcm					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing



TRA-F-144


# Enabling permanent bi-directional capacity in the interconnection points between Bulgaria and Romania – Negru Voda 1, 2 and 3

FID


# **Pipeline including CS**

**SPONSORS** 

GENERAL INFORMATION



Promoter	Bulgartransgaz EAD
Operator	Bulgartransgaz EAD
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	www.bulgartransgaz.bg/



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2013
Last completed Phase :	Market test

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	
Total Pipeline Length (km)	
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Negru Voda I	Yes	exit	132,00	Hub Bulgaria	Interconnector Trans-Balkan Pipeline
DESCRIPTION OF THE PROJECT					
In line with the provisions of Regulation (EC) 994/2010 to enable permanent bi- Bulgaria to Romania in the interconnection points – Negru Voda 1, 2 and 3. The ca					
bulgaria to Nomania in the interconnection points – Negra voda 1, 2 and 3. The ca	pacity figures	maicatea m	tilis project are provisionar	and may be subject to change	solice a final agreement with the Normanian 130 is reached.
EXPECTED BENEFITS					
EAFECTED BENEFITS					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing
					_




TRA-F-057	Interconnection Bulgaria-Romania	FID
altinational colling CC		

SPONSORS

GENERAL INFORMATION



Promoter	Bulgartransgaz EAD
Operator	Bulgartransgaz EAD
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	www.bulgartransgaz.bg



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2011 Q4
FID	2010 Q4
Construction	2013 Q2
Commissioning	2013 Q2
Last completed Phase :	Supply contract

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	3
Total Pipeline Length (km)	+25,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+42,40
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Interconnector Bulgaria-Romania (IBR)	Yes	entry	42,40	Hub Romania	Hub Bulgaria
	Yes	exit	42,40	Hub Bulgaria	Hub Romania
DESCRIPTION OF THE PROJECT					
The reverse interconnection Bulgaria–Romania aims at connecting the national between Member States like Bulgaria having a limited number of sources and rou			s of Bulgaria and Romania.	The implementation of the	project is in line with the EU policy aimed at providing interconnections
The gas pipeline is being designed to function in a reverse mode, which will creat	e conditions fo	or the mitigat	ion of potential supply crise	es on Bulgarian and Romaniar	territory.
The implementation of the project will result in increasing the degree of interconnectivity between the gas transmission systems of Bulgaria and Romania. The project will offer additional transmission capacity.					
EXPECTED BENEFITS					
Security of Supply, Market integration, Reverse Flows, Diversification of sources,	Diversification	of routes N-	1 National N-1 Regional		
Security of Supply, Market integration, neverse riows, Diversification of Sources,	Diversification	rorroutes, iv-	ri National, N-1 Neglonal		
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-N-140	Interconnection Turkey-Bulgaria	Non-FID

# **SPONSORS**

# **GENERAL INFORMATION**



Promoter	Bulgartransgaz EAD
Operator	Bulgartransgaz EAD
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	2
Web Link	www.bulgartransgaz.bg/index.php



THIRD-PARTY ACCESS REGIME			
Considered TPA Regime	Regulated		
Considered Tariff Regime	Regulated		
Applied for Exemption ?	No		
Exemption granted ?	No		
% Exemption in entry direction	0%		
% Exemption in exit direction	0%		

SCHEDULE	
End of permitting phase	
FID	
Construction	2014
Commissioning	2014
Last completed Phase :	Planned

TECHNICAL INFORMATION		
# of Pipelines, nodes, CS	1	
Total Pipeline Length (km)	+200,00	
Total Compressor Power (MW)		
Maximum Capacity (GWh/d)	+85,00	
Expected Load Factor		



PROJECTED CAPACITY INCREASES						
Interconnection	Modelled	Direction	Capacity	(GWh/d)	From Zone	To Zone
Interconnector ITB (Turkey - Bulgaria)	Yes	entry		85,00	Hub Turkey	Hub Bulgaria
	Yes	exit		85,00	Hub Bulgaria	Hub Turkey
DESCRIPTION OF THE PROJECT						
The interconnection Turkey-Bulgaria is a key project whose realization shall lead to the increase of the security of supply and the opportunity for diversification of gas supply not only to Bulgaria, but to the Central and South-Eastern Europe region as well. The interconnection is expected to be constructed as a development of the existing interconnection of the systems of Bulgartransgaz EAD and Botaş S.A Turkey, through the creation of technical capability for provision of capacity for simultaneous bi-directional physical natural gas flow between the two systems.						
EXPECTED BENEFITS						
Security of Supply, Market integration, Reverse Flows, Diversification of sources, Diversification of routes, N-1 National, N-1 Regional						
COMMENTS ABOUT THE PROJECT FINANCING						
Public financing	Private fina	ncing				Multilateral financing




UGS-N-138	UGS Chiren Expansion	Non-FID
	en de la companya de	


**Storage Facility** 

**SPONSORS** 

# GENERAL INFORMATION



Promoter	Bulgartransgaz EAD
Operator	Bulgartransgaz EAD
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	www.bulgartransgaz.bg



THIRD-PARTY ACCESS REGIME			
Considered TPA Regime	Regulated		
Considered Tariff Regime	Regulated		
Applied for Exemption ?	No		
Exemption granted ?	No		
% Exemption in entry direction	0%		
% Exemption in exit direction	0%		

SCHEDULE	
End of permitting phase	
FID	2020
Construction	
Commissioning	2016
Last completed Phase :	Planned

TECHNICAL INFORMATION	
Storage facility	UGS Chiren
Working volume (mcm)	
Injectability (mcm/d)	+6,00
Deliverability (mcm/d)	+6,00



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
UGS - BG - Bulgartransgaz	Yes	entry	60,53	Hub Bulgaria	Storage Bulgaria
	Yes	exit	60,53	Storage Bulgaria	Hub Bulgaria
DESCRIPTION OF THE PROJECT					
UGS Chiren is the only underground storage in the country. It covers mainly sea				and ensures supply security. T	he expansion of the UGS is very important for the implementation of the
Infrastructure Standard N-1. The project will contribute to the increase of storage	e capacity in B	ulgaria and in	the region.		
EXPECTED BENEFITS					
Security of Supply, N-1 National, N-1 Regional					
2014151154 120115 115 22015 23111					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing

## Croatia







#### TRA-N-066 Interconnection Croatia/Bosnia and Herzegovina (Slobodnica- Bosanski Brod-Zenica)

Non-FID

#### **Pipeline including CS**


#### **SPONSORS**

# Croatia, SlobodnicaBosanski Brod (border), Plinacro (100%)

#### GENERAL INFORMATION

Promoter	Plinacro Ltd
Operator	Plinacro Ltd
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	2
Web Link	www.plinacro.hr





THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	0
Considered Tariff Regime	0
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	2013
Construction	
Commissioning	2015
Last completed Phase :	Construction

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+6,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+44,00
Expected Load Factor	90,00%



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Slobodnica- Bosanski Brod-Zenica	Yes	exit	44,00	Hub Croatia	Hub Bosnia Herzegovina
DESCRIPTION OF THE PROJECT					
The pipeline covers the countries Croatia and Bosnia and Herzegovina and it will and Herzegovina with furter extension to Zenica.	be the part o	of Energy Com	munity Ring. The pipeline	goes from Slavonski Brod (Slol	oodnica) in Croatia, it will cross the Sava river to Bosanski Brod in Bosnia
EXPECTED BENEFITS					
Market integration, Reverse Flows, N-1 Regional (For Bosnia and Herzegovina), Ba	ack-up for ren	ewables, It wi	ll be new entry point and t	ransmission route for the need	Is of B&H
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing



TRA-N-070 Interconnection Croatia/Serbia Slobdnica - Sotin (Croatia) - Bačko Novo Selo (Serbia)

Non-FID

#### **Pipeline including CS**


#### **SPONSORS**

# Croatian section, Plinacro (100%) Serbian section, Srbijagas (100%)

#### GENERAL INFORMATION

Promoter	Plinacro Ltd			
Operator	Plinacro Ltd			
TEN-E Project ?	Not part of TEN-E			
Interested by PCI ?	Not defined yet			
IGAs	None			
Web Link	www.plinacro.hr			





THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	0
Considered Tariff Regime	0
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	2015
Construction	
Commissioning	2022*
Last completed Phase :	Construction

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	2
Total Pipeline Length (km)	+100,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+176,00
Expected Load Factor	90,00%



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Sotin- Bačko Novo Selo	No	exit	176,00	Hub Croatia	Hub Serbia
DESCRIPTION OF THE PROJECT					
Covering Croatia and Serbia, connecting the Croatian gas transmission system to	the Serbian g	as transmissio	on system Slobodnica - Sotir	n (Croatia) - Bačko Novo Selo (S	erbia)
, ,	J		•	, ,	,
EXPECTED BENEFITS					
Market integration, Reverse Flows, Diversification of routes, N-1 Regional (For Serbia), Back-up for renewables, It will be new entry point and transmission route for the needs of B&H					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing

PROJECTED CAPACITY INCREASES




TRA-N-086 Interconnection Croatia/Slovenia (Bosiljevo - Karlovac - Lučko - Zabok - Rogatec) Non-FID


**Pipeline including CS** 

**SPONSORS** 

#### GENERAL INFORMATION



Promoter	Plinacro Ltd
Operator	Plinacro Ltd
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	www.plinacro.hr



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	0
Considered Tariff Regime	0
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	2014
Construction	
Commissioning	2022*
Last completed Phase :	Construction

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+150,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+165,00
Expected Load Factor	90,00%



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Rogatec	No	exit	165,00	Hub Croatia	Hub Slovenia
DESCRIPTION OF THE PROJECT					
Covering Croatia and Slovenia, from the gas node Bosiljevo via Karlovac, Lučko an	d Zabok in Cro	patia to the C	roatian / Slovenian border	(to be connected to the gas no	de Rogatec on the Slovenian side)
EXPECTED BENEFITS					
Security of Supply, Market integration (croatian market and the markets in CEE will be significantly increase the capacity of the interconnection of the Croatian a market.					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




### TRA-N-083 International Pipeline Omišalj - Casal Borsetti Non-FID


#### Pipeline including CS

#### SPONSORS

#### GENERAL INFORMATION



Promoter	Plinacro Ltd
Operator	Plinacro Ltd
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	www.plinacro.hr



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	0
Considered Tariff Regime	0
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2018
Last completed Phase :	Construction

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	2
Total Pipeline Length (km)	+220,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+506,00
Expected Load Factor	90,00%



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Casalborsetti	Yes	exit	506,00	Hub Croatia	Hub Italia
DESCRIPTION OF THE PROJECT					
Covering the therritory from the gas node Omišalj on the island of Krk (Croatian C	Gas Transmiss	ion System) vi	ia Adriatic Sea to Casal Bors	setti (Italian Gas Transmission	System)
EXPECTED BENEFITS					
Security of Supply, Market integration, Reverse Flows, Diversification of sources,	Diversification	of routes N	-1 National (For Croatia) N	-1 Regional Back-up for renev	wahlas It will he new cross harder transmission hetween Croatia and Italy.
fits in the idea of Adriatic Gas Ring	Diversification	rorroutes, iv	-1 National (For Croatia), N	-1 Negional, back-up for reflex	wables, it will be new closs border transmission between croatia and italy,
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing


PROJECTED CAPACITY INCREASES



#### TRA-N-068 Ionian Adriatic Pipeline Non-FID


#### **Pipeline including CS**

#### SPONSORS



#### GENERAL INFORMATION

Promoter	Plinacro Ltd
Operator	Plinacro Ltd
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	2
Web Link	www.plinacro.hr



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	0
Considered Tariff Regime	0
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	2014
Construction	
Commissioning	2018
Last completed Phase :	Construction

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	3
Total Pipeline Length (km)	+540,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+75,34
Expected Load Factor	90,00%



#### PROJECTED CAPACITY INCREASES Modelled Direction Capacity (GWh/d) To Zone Interconnection From Zone interconnector ionic-Adriatic Ionic-Adriatic Pipeline - IAP / Split - HR Yes 75,00 **Hub Croatia** entry Priterionnector ronic-Adriatic Ionic-Adriatic Pipeline - IAP / BH exit 30,00 **Hub Bosnia Herzegovina** Yes Piterionnector ionic-Auriatic Ionic-Adriatic Pipeline - IAP / ME Yes exit 15,00 **Hub Montenegro** Pitelionnector tonic-Adriatic Ionic-Adriatic Pipeline - IAP / AB **Hub Albania** Yes exit 30,00 Pitelionnector trans-Auriatic Trans-Adriatic Pipeline - TAP / Ionic-Adriatic Pipeline - IAP Yes entry 150.00 Interconnector Ionic-Adriatic Pipeline **DESCRIPTION OF THE PROJECT** The pipeline will cross the territory along the Adriatic coast from Fieri in Albania via Montenegro to Split in Croatia and will be linked to the existing Croatian gas transmission system (main direction Bosiljevo – Split). The Ionian-Adriatic Pipeline is considered a part of the Energy Community Gas Ring, which is the concept of gasification for the entire region, proposed by the WB Study and accepted by the Gas Fora of the Energy Community. **EXPECTED BENEFITS** Security of Supply, Market integration (Market Integration benefits for Croatia and the region (Albania, Montenegro, Bosnia and Herzegovina and neighbouring countries), Reverse Flows, Diversification of sources, Diversification of routes, N-1 National, N-1 Regional (Balkan region), Back-up for renewables COMMENTS ABOUT THE PROJECT FINANCING **Public financing Private financing Multilateral financing**




#### TRA-N-090 LNG evacuation pipeline Omišalj - Zlobin (Croatia) - Rupa (Slovenia)

Non-FID


#### **Pipeline including CS**

#### **SPONSORS**

### GENERAL INFORMATION



Promoter	Plinacro Ltd
Operator	Plinacro Ltd
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	1
Web Link	www.plinacro.hr



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	0
Considered Tariff Regime	0
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	2013
Construction	
Commissioning	2015
Last completed Phase :	Construction

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+55,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+506,00
Expected Load Factor	90,00%



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Zlobin (Croatia) - Rupa (Slovenia)	Yes	exit	506,00	Hub Croatia	Hub Slovenia
DESCRIPTION OF THE PROJECT					
The pipeline will cross the territory from the LNG solution in Omišalj on the island	of Krk to Rup	a in Slovenia	and will be linked to the Slo	ovenian gas transmission syste	m.
EXPECTED BENEFITS					
Security of Supply, Market integration (croatian market, slovenian market and the markets in CEE region and Italy), Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (for Croatia and Slovenia), N-1 Regional, Back-up for renewables, It will be significantly increase the capacity of the interconnection of the Croatian and Slovenian gas transmission systems in this direction. It will increase the capacity along the route, provide enhanced access to					
Baumgarten and Italien gas market. The project will significantly increase the flexibillity of the system for Croatia.					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing



TRA-N-075


#### LNG main gas transit pipeline (Part of North-South Gas Corridor) Zlobin-Bosiljevo-Sisak-Kozarac-Slobodnica

Non-FID


**Pipeline including CS** 

SPONSORS

#### GENERAL INFORMATION



Promoter	Plinacro Ltd
Operator	Plinacro Ltd
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	www.plinacro.hr



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	0
Considered Tariff Regime	0
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	2015
Construction	
Commissioning	2022*
Last completed Phase :	Construction

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+308,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+330,00
Expected Load Factor	90,00%



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone

#### **DESCRIPTION OF THE PROJECT**

The pipeline will be construted on the territory of Croatia from the gas node Zlobin via Bosiljevo, Sisak, the gas node Kozarac to Slobodnica

#### **EXPECTED BENEFITS**

Security of Supply, Market integration (Croatia, Hungary, Bosnia and Herzegovina, Serbia), Reverse Flows, Diversification of routes, N-1 National (for Croatia), Back-up for renewables, This main transit gas pipeline is the future strategic gas transmission connector of great significance and is an integral part of the North – South European Corridor designated the North-South (Baltic – Adriatic) Gas Connection. Its purpose is linking the Polish and Croatian LNG (Liquefied Natural Gas) solutions under the umbrella of the European Commission (EC). This project is foreseen under the Gas Forum administered by the Energy Community Secretariat, and although in Croatia, is regionally significant. The main transit gas pipeline Zlobin-Bosiljevo-Sisak-Kozarac-Slobodnica:

- is a continuation of the existing Hungarian Croatian interconnection (gas pipeline Varosföld-Dravaszerdahely-Donji Miholjac-Slobodnica)
- will be connected to the future Ionian Adriatic Pipeline (IAP)
- will be connected to the future LNG solution in Omišalj.

#### COMMENTS ABOUT THE PROJECT FINANCING

Public financing	Private financing	Multilateral financing




LNG-N-082	LNGRV	Non-FID

#### **LNG Terminal**


#### SPONSORS

#### GENERAL INFORMATION

#### **FINANCING**



Promoter	Plinacro Ltd
Operator	Plinacro Ltd
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	www.plinacro.hr



THIRD-PARTY ACCESS REGIME		SCHEDULE
Considered TPA Regime	0	End of permitting phase
Considered Tariff Regime	0	FID
Applied for Exemption ?	No	Construction
Exemption granted ?	No	Commissioning
% Exemption in entry direction	0%	Last completed Phase :
% Exemption in exit direction	0%	

TECHNICAL INFORMATION				
Regasification facility	LNG RV Croatia			
Expected volume (bcm/y)	+2,00			
Storage capacity (m3)				
Send-out (mcm/d)	+5,50			
Ship size (m3)				
Reloading ability ?	No			


2013

2015 Construction



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
LNG RV (Regasification Vessel) to Croatia	Yes	entry	60,50	LNG Terminals Croatia	Hub Croatia
DESCRIPTION OF THE PROJECT					
The LNG RV will be situated in Omišalj on the island of Krk, Republic of Croatia.					
It is considered a part of the Energy Community Gas Ring, which is the concept of	gasification f	or the entire	region, proposed by the W	B Study and accepted by the Ga	as Fora of the Energy Community.
EXPECTED BENEFITS					
	- /a				W 20 10 20 10 10 10 10 10 10 10 10 10 10 10 10 10
Security of Supply, Market integration (Croatia, markets of Central and Western Europe (Austria, Slovenia, Hungary, Slovakia, Check Republic) as well as the Balkan countries (Serbia, B&H, Montenegro)), Diversification of sources, Diversification of routes, N-1 National (for Croatia), N-1 Regional, Back-up for renewables					alkan countries (Serbia, B&H, Montenegro)), Diversification of sources,
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing










#### POW-N-073 Internal Gas Pipeline Network Non-FID


#### Interconnection with a gas-fired power plant

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	Ministry of Cyprus
Operator	Cygas
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	2
Web Link	



THIRD-PARTY ACCESS REGIME				
Considered TPA Regime	Regulated			
Considered Tariff Regime	Regulated			
Applied for Exemption ?	No			
Exemption granted ?	Not relevant			
% Exemption in entry direction	0%			
% Exemption in exit direction	0%			

SCHEDULE	
End of permitting phase	2013 Q2
FID	2013 Q2
Construction	2014 Q4
Commissioning	2015 Q1
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	3
Total Pipeline Length (km)	+77,50
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+85,15
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
Development of a gas pipeline network that will, initially, supply natural gas to thother power producers as well as industrial, commercial and domestic potential cu		er stations op	erated by the Electricity Au	ithority of Cyprus. It is expec	ted that in the future the gas network will be further developed to supply
EXPECTED BENEFITS					
Security of Supply, Diversification of sources, Biogas					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private finar	ncing			Multilateral financing
					EEPR Funds




#### UGS-N-067 Mediterranean Gas Storage Non-FID


#### **Storage Facility**

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	Ministry of Cyprus			
Operator	Future Cypriot Producer			
TEN-E Project ?	Not part of TEN-E			
Interested by PCI ?	Yes			
IGAs	None			
Web Link				



THIRD-PARTY ACCESS REGIME					
Considered TPA Regime	Regulated				
Considered Tariff Regime	Regulated				
Applied for Exemption ?	No				
Exemption granted ?	Not relevant				
% Exemption in entry direction	0%				
% Exemption in exit direction	0%				

SCHEDULE	
End of permitting phase	2015 Q1
FID	2015 Q1
Construction	2018 Q4
Commissioning	2019 Q1
Last completed Phase :	Market test

TECHNICAL INFORMATION	
Storage facility	Cyprus Onshore LNG storage
Working volume (mcm)	+109,62
Injectability (mcm/d)	+18,10
Deliverability (mcm/d)	+18,10



#### PROJECTED CAPACITY INCREASES

Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Mediterranean Gas Storage (CY)	Yes	exit	199,10		LNG Terminals Cyprus
	Yes	entry	199,10	LNG Terminals Cyprus	

#### **DESCRIPTION OF THE PROJECT**

LING Storage and export facilities located in Cyprus, to transport gas from the Levantine basin to LING Regastification Terminals located in the infediterranean Sea (i.e. in Greece, France, Italy, Spain).

Gas could then be further transmitted through the national gas transmission system of those countries (using existing or new/upgraded transmission networks/pipelines) to the Central Eastern and South Eastern Europe (not part of current project).

The proposed gas storage and export facilities comprise of initially one LNG storage tank (in total three LNG tanks will gradually be built) and related export facilities, which will be capable of exporting 5mtpa of LNG (the exporting capacity will gradually be expanded to 15mtpa).

#### **EXPECTED BENEFITS**

Security of Supply, Diversification of sources, Diversification of routes, N-1 Regional (Mediterranean), Biogas, With the implementation of this project additional capacity will become available (offering additional flexibility, through an additional route, source and counterpart), and gas could be transported where necessary and when necessary (provided there is an LNG Receiving and Regasification Terminal at the destination), thus able to also cover daily peak demand.

Additional available capacity could also cover part of the annual demand.

#### COMMENTS ABOUT THE PROJECT FINANCING

Public financing	Private financing	Multilateral financing
Project Financing structure not yet finalized	Project Financing structure not yet finalized	Project Financing structure not yet finalized




PRD-N-055	Mediterranean LNG Export Terminal	Non-FID


#### **Production Facility**

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	Ministry of Cyprus
Operator	Future Cypriot Producer
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2015 Q1
FID	2015 Q1
Construction	2018 Q4
Commissioning	2019 Q1
Last completed Phase :	Market test

TECHNICAL INFORMATION	
Production facility	Vasilikos LNG Plant
Expected volume (bcm/y)	+6,60
Technical Capacity (bcm/y)	+7,59



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Vasilikos LNG Plant (CY)	Yes	exit	211,00		LNG Terminals Cyprus
DESCRIPTION OF THE PROJECT					
LNG Export Terminal for the liquefaction of natural gas produced in upstream fields, which will be capable of producing 5mtpa of LNG (the exporting capacity will gradually be expanded to 15mtpa).					
EXPECTED BENEFITS					
Security of Supply, Diversification of sources, Diversification of routes, N-1 Regional (Mediterranean), Biogas					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing
Project Financing structure not yet finalized	Project Fina	ncing structu	re not yet finalized		Project Financing structure not yet finalized




#### TRA-N-054 Trans-Mediterranean Gas Pipeline Non-FID


#### **Pipeline including CS**

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	Ministry of Cyprus
Operator	Cygas
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	2
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2015 Q1
FID	2015 Q1
Construction	2018 Q1
Commissioning	2018 Q2
Last completed Phase :	Market test

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+1.400,00
Total Compressor Power (MW)	+111,00
Maximum Capacity (GWh/d)	+254,27
Expected Load Factor	90,00%



#### PROJECTED CAPACITY INCREASES

Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Interconnector CY-GR (Trans-Med)	Yes	entry	47,68	Hub Greece	Hub Cyprus
	Yes	exit	222,49	Hub Cyprus	Hub Greece

#### **DESCRIPTION OF THE PROJECT**

Transmission pipeline for the transport of natural gas from the Levantine Basin into Greece's National Gas Transmission System, through Cyprus.

Gas could be then transported, using existing or new/upgraded transmission networks/pipelines, through mainland Greece to the Central Eastern and South Eastern Europe (not part of current project).

The proposed gas transmission pipeline will have a total length of around 1,400km and could allow for reverse flow. Other relevant project infrastructure (facilities) includes three compressor stations – one located onshore Cyprus, the second onshore Crete (Greece) and the third onshore mainland Greece.

#### **EXPECTED BENEFITS**

Security of Supply, Market integration (Mediterranean and South-Eastern Europe), Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (Cyprus), N-1 Regional (South-Eastern Europe), Biogas, Project has significant impact on cross-border transmission capacity between Greece and Cyprus.


Project establishes a new connection and contributes to the interconnection of Cyprus with the European Grid, through Greece, thus also eliminating the isolation of Cyprus from the Internal Energy Market (by allowing for reverse flow). Project provides for additional capacity able to cover peak demand and daily demand, as well as for reverse flow.

Enhanced flexibility is also offered since the project involves gas transmission through an additional route, source and counterpart.

#### COMMENTS ABOUT THE PROJECT FINANCING

Public financing	Private financing	Multilateral financing
Project Financing structure not yet finalized	Project Financing structure not yet finalized	Project Financing structure not yet finalized

# Czech Republic








#### **Bidirectional Austrian Czech Interconnection (BACI, formerly LBL project)** TRA-N-133 Non-FID

#### **Pipeline including CS**


#### **SPONSORS**

#### GENERAL INFORMATION

#### FINANCING



Promoter	NET40	GAS, s.r.o.
Operator	NET40	GAS, s.r.o.
TEN-E Project ?	Project of Co	ommon Interest
Interested by PCI ?		Yes
IGAs	N	lone
Web Link		
TEN-E Requests	Date of Request 27/02/12	Year Funding Granted Not yet



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2019
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+58,00
Total Compressor Power (MW)	+24,00
Maximum Capacity (GWh/d)	+254,00
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Reinthal - Bidirectional Austrian-Czech Interconnector	Yes Yes	exit entry	254,00 254,00	Hub Czech Republic	Hub Austria Hub Czech Republic
DESCRIPTION OF THE PROJECT					
The BACI will be a new infrastructure directly connecting the Austrian and Czech market. It will be connected to the existing Czech transmission system via CS Břeclav (NET4GAS, s.r.o.) and to the Austrian transmission system via Baumgarten (GAS CONNECT AUSTRIA GmbH). The BACI will enable capacity transmission for the first time between these two member states and it will facilitate better market integration and security of gas supply also for adjacent countries like Hungary, Poland, Germany, Italy, France, Slovenia, Croatia and Slovakia due to the creation of additional transportation opportunities. The project will also increase the overall flexibility of the Czech, Austrian and also Polish system by diversification of gas supply routes and by connecting UGS in the Czech Republic and Austria.					
EXPECTED BENEFITS					
Security of Supply, Market integration (CEE Region), Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (CZ, AT), N-1 Regional (CEE Region), Back-up for renewables, Power-to-gas, Biogas					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




#### TRA-N-135 Connection to Oberkappel Non-FID


#### **Pipeline including CS**

#### SPONSORS

#### GENERAL INFORMATION



Promoter	NET4GAS, s.r.o.	
Operator	NET4GAS, s.r.o.	
TEN-E Project ?	Not part of TEN-E	
Interested by PCI ?	Yes	
IGAs	None	
Web Link	www.tauerngasleitung.at/5GL	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2022
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+110,00
Total Compressor Power (MW)	+2,00
Maximum Capacity (GWh/d)	+55,00
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
	No	exit	55,00	Hub Czech Republic	Hub Austria
	No	entry	55,00	Hub Austria	Hub Czech Republic
DESCRIPTION OF THE PROJECT					
DESCRIPTION OF THE PROJECT					
The project will interconnect the existing transmission pipelines in the Czech R pipeline (AT) and to the Southern branch of the N4G transmission system (CZ). C					
and NET4GAS, s.r.o. (CZ). As part of the 5GL Project the Oberkappel project wo					
Haiming/Burghausen.					
EXPECTED BENEFITS					
Security of Supply, Market integration (CEE Region), Reverse Flows, Diversification	n of sources,	Diversification	n of routes, N-1 National (C	Z, AT), N-1 Regional (CEE Regional	on), Back-up for renewables, Power-to-gas, Biogas
COLUMNITIES ADOLLT THE PROJECT THANKS HE					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-F-134	GAZELLE project	FID


#### **Pipeline including CS**

#### SPONSORS

#### GENERAL INFORMATION



Promoter	NET4GAS, s.r.o.
Operator	NET4GAS, s.r.o.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	www.net4gas.cz/en/projekt-gazela/



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	Yes
Exemption granted ?	Yes
% Exemption in entry direction	100%
% Exemption in exit direction	0%


SCHEDULE	
End of permitting phase	2012
FID	
Construction	2012
Commissioning	2013
Last completed Phase :	Permitting

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+158,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+218,00
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Opal (DE)/Brandov (CZ)	Yes	entry	960,00	Interconnector OPAL	
DESCRIPTION OF THE PROJECT					
The project creates together with the projects Nord Stream and OPAL the so calle	ed Northern R	oute for Russi	ian gas supplies to Europe a	and it has important influence o	on increasing security of supply through the diversification of gas routes.
EXPECTED BENEFITS					
Security of Supply, Market integration (CEE Region), Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (the Czech Republic), N-1 Regional (CEE Region), Back-up for renewables, Power-to-gas, Biogas					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing






#### Poland-Czech Republic Interconnection within the North-South Corridor (STORK II)

Non-FID


#### **Pipeline including CS**

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	NET4G/	AS, s.r.o.
Operator	NET4G/	AS, s.r.o.
TEN-E Project ?	Project of Cor	mmon Interest
Interested by PCI ?	Y	es
IGAs	No	one
Web Link		
TEN-E Requests	Date of Request 1/02/11	Year Funding Granted Not yet



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2017
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+107,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+218,00
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Interconnector CZ-PL	Yes	entry	153,40	Hub Poland	Hub Czech Republic
	Yes	exit	220,50	Hub Czech Republic	Hub Poland
DESCRIPTION OF THE PROJECT					
The STORK II interconnector pipeline will be part of the Czech and Polish transmission system and will increase cross-border capacity between these two countries by establishing a large transportation corridor that will allow flexible					
transport of gas in Central Europe in direction North-South. The development of the physical interconnection between Poland and Czech Republic will contribute to reinforcement of the effective operation of the gas transmission systems, efficient gas exchange between the markets, as well as increase of the security of supply not only for Poland and Czech Republic, but also for the CEE region by enabling the supply link with the European gas market (NCG, CEGH					
Baumgarten, Gas Pool) and global LNG market via the Terminal in Świnoujście.					
EXPECTED BENEFITS					
County of County Market interaction (CCC Design (see in the CCC DIV) Design (see in the CCC DIV) N. 4 Design (CCC Design) Design (see in the CCC DIV) N. 4 Design (CCC Design) Design (see in the CCC DIV) N. 4 Design (see in the CCC					
Security of Supply, Market integration (CEE Region (mainly CZ, PL)), Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (CZ, PL), N-1 Regional (CEE Region), Back-up for renewables, Power-to-gas, Biogas					
COMMENTS ABOUT THE PROJECT FINANCING					
	Duinete fine				Multilatoral financina
Public financing	Private fina	ncing			Multilateral financing




UGS-N-074	Expansion of the virtual storage operated by RWE Gas Storage	Non-FID


**Storage Facility** 

**SPONSORS** 

#### GENERAL INFORMATION



Promoter	RWE Gas Storage, s.r.o.			
Operator	RWE Gas Storage, s.r.o.			
TEN-E Project ?	Not part of TEN-E			
Interested by PCI ?	Not defined yet			
IGAs	None			
Web Link	www.rwe-gasstorage.cz/en/capacity-development/			



THIRD-PARTY ACCESS REGIME				
Considered TPA Regime	Negotiated (e.g. Exemption)			
Considered Tariff Regime	Negotiated (e.g. Exemption)			
Applied for Exemption ?	No			
Exemption granted ?	Not relevant			
% Exemption in entry direction	0%			
% Exemption in exit direction	0%			

SCHEDULE	
End of permitting phase	2015
FID	2013
Construction	2016
Commissioning	2022*
Last completed Phase :	Planned

TECHNICAL INFORMATION	
Storage facility	RWE Gas Storage Virtual Storage
Working volume (mcm)	+587,40
Injectability (mcm/d)	+9,50
Deliverability (mcm/d)	+16,10



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
UGS - CZ - Net4Gas/RWE Gas Storage	Yes	exit	177,10	Storage Czech Republic	Hub Czech Republic
	Yes	entry	104,50	Hub Czech Republic	Storage Czech Republic
DESCRIPTION OF THE PROJECT					
RWE Gas Storage operates its six UGS facilities as virtual storage. The project invo	llves expansic	on of a numbe	r of facilities.		
EXPECTED BENEFITS					
Market integration, Back-up for renewables, Project will increase security of supp The new gas storage capacity will both increase the ratio between storage capa flexibility.					oute to the gas market liberalisation by providing an additional source of
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing

# Denmark








TRA-F-015 Ellund-Egtved FID
-----------------------------


#### **Pipeline including CS**

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	<b>Energinet.dk</b>			
Operator	<b>Energinet.dk</b>			
TEN-E Project ?	Project of Common Interest			
Interested by PCI ?	Not defined yet			
IGAs	None			
Web Link	energinet.dk/EN/ANLAEG-OG-PROJEKTER/Anlaegsprojektergas/Ellund-Egtved/Sider/Ellund-Egtved.aspx			



THIRD-PARTY ACCESS REGIME			
Considered TPA Regime	Regulated		
Considered Tariff Regime	Regulated		
Applied for Exemption ?	Not relevant		
Exemption granted ?	Not relevant		
% Exemption in entry direction	0%		
% Exemption in exit direction	0%		

SCHEDULE	
End of permitting phase	2011
FID	2010 Q2
Construction	2013
Commissioning	2013 Q4
Last completed Phase :	FID

ECHNICAL INFORMATION	
of Pipelines, nodes, CS	1
otal Pipeline Length (km)	+94,00
otal Compressor Power (MW)	+20,00
Maximum Capacity (GWh/d)	+184,80
xpected Load Factor	55,00%



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Ellund	Yes	entry	184,80	Hub Germany	Hub Denmark
Dragør	Yes	exit	13,20	Hub Denmark	Hub Sweden
Ellund	Yes	exit	44,00	Hub Denmark	

#### **DESCRIPTION OF THE PROJECT**

Pipeline looping Ellund-Egtved. Four unit Compressor Station in Egtved. Increases capacity in Ellund and Dragør Interconnection Points.

#### **EXPECTED BENEFITS**

Security of Supply, Market integration, Reverse Flows, Diversification of sources, Diversification of routes, N-1 National, N-1 Regional, Back-up for renewables, Biogas, The project will ensure supply of gas to the Danish and Swedish markets when the gas production from the Danish North Sea is declining. The project also ensures integration with the gas market in Germany. Furthermore, the project will enhance security of supply also in emergency situations by providing diversification of sources and routes.

#### COMMENTS ABOUT THE PROJECT FINANCING

Public financing	Private financing	Multilateral financing
50% European Economic Recovery Programme – expected co-financing of 100 million EUR.	50% Financed by Energinet.dk	




TRA-N-218

Tie-in of Norwegian off-shore natural gas transmission system to Danish off-shore natural gas
infrastructure


Pipeline including CS

SPONSORS

#### GENERAL INFORMATION



Promoter	Maersk Oil and Gas A/S
Operator	Maersk Oil and Gas A/S
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	2013
Commissioning	2014 Q4
Last completed Phase :	FEED

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+175,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+100,00
Expected Load Factor	80,00%



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Statpipe - NO / Harald platform - DK	Yes	entry	100,00	Supplier Norway	NP Send-out Denmark
DESCRIPTION OF THE PROJECT					
To connect the Norwegian off shore natural gas infrastructure (Statpipe) with the	Danish off-sh	ore natural g	as infrastructure		
(Harald platform).					
EXPECTED BENEFITS					
Security of Supply, Market integration (Norwegian off shore system and Danish/S	wedish/Germ	an market) D	Diversification of sources D	iversification of routes N-1 N	ational (Denmark) Back-un for renewables
Security of Supply, market integration (Not wegan on Shore System and Burnshy S	wealsh, derm	arr markety, D	orversimention or sources, b	iversification of routes, iv 110	adolar (Selmany, Sack up to Tenewasies
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing










# LNG-N-079 Paldiski LNG Terminal Non-FID


#### **LNG Terminal**

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	Balti Gaas plc
Operator	Balti Gaas plc
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	www.baltigaas.eu



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not Relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2012 Q4
FID	2013 Q1
Construction	2015 Q2
Commissioning	2015 Q3
Last completed Phase :	Planned

TECHNICAL INFORMATION	
Regasification facility	Paldiski LNG Terminal
Expected volume (bcm/y)	+2,60
Storage capacity (m3)	+180.000,00
Send-out (mcm/d)	+25,00
Ship size (m3)	160.000,00
Reloading ability ?	Yes



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Paldiski LNG	Yes	exit	275,00	LNG Terminals Estonia	Hub Estonia
DESCRIPTION OF THE PROJECT					
LNG regasification terminal for regional use on the Pakri peninsula on the Easern	coast of the D	altic Soa			
tivo regasilication terminarior regional use on the rakin permisula on the casem	Loast of the b	aitic Sea			
EXPECTED BENEFITS					
Security of Supply, Market integration (Estonia, Latvia, Finland with Balticconnect	or), Diversific	ation of sour	ces, N-1 National (Estonia),	N-1 Regional (Baltics and Finle	and with Balticconnector), Back-up for renewables
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




### LNG-N-146 Tallinn LNG Terminal Non-FID


#### **LNG Terminal**

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	Elering
Operator	Vopak / Elering
TEN-E Project ?	Project of Common Interest
Interested by PCI ?	Yes
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2015 Q2
FID	2015 Q2
Construction	2017 Q3
Commissioning	2017 Q4
Last completed Phase :	Permitting

TECHNICAL INFORMATION	
Regasification facility	Tallinn LNG terminal
Expected volume (bcm/y)	+2,90
Storage capacity (m3)	+90.000,00
Send-out (mcm/d)	+8,00
Ship size (m3)	75.000,00
Reloading ability ?	Yes



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Tallinn LNG	Yes	exit	88,00	LNG Terminals Estonia	Hub Estonia
DESCRIPTION OF THE PROJECT					
Conventional LNG import terminal for improving Baltic as well as Finnish security	of sypply nad	serving comn	mercial customers.		
		J			
EXPECTED BENEFITS					
Security of Supply, Market integration, Reverse Flows, Diversification of source includes facilities for bunkering, it contributes for ECA regulation implementation		ion of routes	s, N-1 National (Estonia), N	I-1 Regional (Baltic + Finland),	Back-up for renewables, Power-to-gas, Biogas, As Tallinn LNG terminal
includes facilities for bunkering, it contributes for ECA regulation implementation					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




# TRA-N-072 Balticconnector (Including CS) Non-FID


#### **Pipeline including CS**

#### SPONSORS

#### GENERAL INFORMATION



Promoter	Vörguteenus
Operator	Vörguteenus
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME				
Considered TPA Regime	Regulated			
Considered Tariff Regime	Regulated			
Applied for Exemption ?	No			
Exemption granted ?	No			
% Exemption in entry direction	0%			
% Exemption in exit direction	0%			

SCHEDULE	
End of permitting phase	2013 Q4
FID	2014 Q1
Construction	2014 Q3
Commissioning	2016 Q1
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	2
Total Pipeline Length (km)	+127,00
Total Compressor Power (MW)	+35,00
Maximum Capacity (GWh/d)	+79,80
Expected Load Factor	70,00%



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Inkoo (FI) / Undetermined (EE) - Balticconnector	Yes	entry	79,80	Hub Finland	Hub Estonia
	Yes	exit	79,80	Hub Estonia	Hub Finland
DESCRIPTION OF THE PROJECT					
The project will establish the first interconnection between Finland and Establish					
The project will establish the first interconnection between Finland and Estonia.					
EXPECTED BENEFITS					
En Lores Sent 113					
Security of Supply, Market integration (Estonia, Finland), Reverse Flows, Diversification of sources, N-1 National (Estonia, Finland), Market integration through connecting the Estonian and Finnish market					

COMMENTS ABOUT THE PROJECT FINANCING

Public financing

Multilateral financing

Private financing




TRA-N-084	Karksi GMS	Non-FID


#### **Pipeline including CS**

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	Vörguteenus
Operator	Vörguteenus
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME			
Considered TPA Regime	Regulated		
Considered Tariff Regime	Regulated		
Applied for Exemption ?	No		
Exemption granted ?	No		
% Exemption in entry direction	0%		
% Exemption in exit direction	0%		

SCHEDULE	
End of permitting phase	2014 Q1
FID	2014 Q1
Construction	2014 Q3
Commissioning	2015 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	
Total Compressor Power (MW)	+35,00
Maximum Capacity (GWh/d)	+94,00
Expected Load Factor	70,00%



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Karksi	Yes	exit	94,00	Hub Estonia	Hub Latvia
	Yes	entry	94,00	Hub Latvia	Hub Estonia

DESCRIPTION OF THE PROJECT					
Uppgrade of interconnection pipeline by installation of compressor station and new metering equipment					
EXPECTED BENEFITS					
Security of Supply, Market integration (Estonia, Finland, Latvia), Reverse Flows, Diversification of sources, N-1 National (Estonia, Latvia)					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private financing	Multilateral financing			










TRA-N-023	Balticconnector (FI-EE)	Non-FID
Pipeline including CS		


Pipeline including Co

SPONSORS

#### **GENERAL INFORMATION**



Promoter	Gasum Oy
Operator	Gasum Oy
TEN-E Project ?	Priority Project
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	www.gasum.com



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	2014
Construction	
Commissioning	2016 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+80,00
Total Compressor Power (MW)	+20,00
Maximum Capacity (GWh/d)	
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Inkoo (FI) / Undetermined (EE) - Balticconnector	Yes	exit	79,80	Hub Finland	Hub Estonia
	Yes	entry	79,80	Hub Estonia	Hub Finland

DESCRIPTION OF THE PROJECT				
EXPECTED BENEFITS				
Security of Supply, Market integration, Reverse Flows, Diversification of sources, Diversification of routes, N-1 National, N-1 Regional, Back-up for renewables, Biogas Balticconnector is a project targeted to interconnect markets around the northern Baltic Sea. It will enable two-way gas flows between Finland and Estonia and provide more gas supply capacity and flexibility for the whole region. Together with Finngulf LNG terminal, it improves the security of gas supply of Finland and Baltic Countries.  Together with Balticconnector, Finngulf LNG terminal makes it possible to diversify the gas sourcing from international LNG markets and thus improve the security of gas supply of Finland and Baltic Countries.				
COMMENTS ABOUT THE PROJECT FINANCING				
Public financing	Private financing	Multilateral financing		
Balticconnector 50%	Balticconnector 50%			




LNG-N-024	Finngulf	Non-FID


#### **LNG Terminal**

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	Gasum Oy
Operator	Gasum Oy
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	www.gasum.com



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	2014
Construction	
Commissioning	2018 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
Regasification facility	
Expected volume (bcm/y)	+1,00
Storage capacity (m3)	+300.000,00
Send-out (mcm/d)	+19,20
Ship size (m3)	150.000,00
Reloading ability ?	No



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Finngulf LNG	Yes	entry	211,20	LNG Terminals Finland	Hub Finland
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Market integration, Reverse Flows, Diversification of sources, Div	Diversification	of routes, N-	·1 National, N-1 Regional, B	ack-up for renewables, Bioga	S
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing
Finngulf LNG 50%	Finngulf LNC	G 50%			




LNG-N-277	Pansio LNG	Non-FID


#### **LNG Terminal**

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	Gasum Oy
Operator	Gasum Oy
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	www.gasum.com



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	2013 Q4
Construction	
Commissioning	2015 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
Regasification facility	
Expected volume (bcm/y)	+0,11
Storage capacity (m3)	+30.000,00
Send-out (mcm/d)	
Ship size (m3)	15.000,00
Reloading ability ?	No




Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
	No	exit	0,00	LNG Terminals Finland	
DESCRIPTION OF THE PROJECT					
Business orientation: Marine use and small facilities outside natural gas network	(Terminal is n	ot connected	to natural gas network)		
EXPECTED BENEFITS					
Security of Supply, Reverse Flows, Diversification of sources, Diversification of ro	utes, N-1 Regi	onal, Back-up	for renewables, Biogas		
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing



# LNG-N-194 Tornio ManGa LNG Terminal project Non-FID

#### **LNG Terminal**


#### **SPONSORS**



#### GENERAL INFORMATION

Promoter	OutoKompu Oyj
Operator	OutoKompu Oyj
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	





THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	Not yet
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2013 Q2
FID	2013 Q3
Construction	2014 Q1
Commissioning	2016 Q1
Last completed Phase :	FEED

TECHNICAL INFORMATION	
Regasification facility	
Expected volume (bcm/y)	
Storage capacity (m3)	+140.000,00
Send-out (mcm/d)	+0,00
Ship size (m3)	45.000,00
Reloading ability ?	No



terconnection	Modelled	Direction	Capacity (GWh/d)	From Zone
	Yes	exit	0,03	LNG Terminals Finland(Nortl

#### **DESCRIPTION OF THE PROJECT**

The Manga Ltd LNG terminal will supply natural gas into market areas and industrial companies which currently do not have access to gas via pipeline networks i.e. Northern and Central parts of Finland and Sweden. The terminal is located in Tornio, at the border of Finland and Sweden. Several Finnish and Sweden are interested in the project among them Outokumpu, which plans to use LNG in its production processes both in Sweden and in Finland.

#### **EXPECTED BENEFITS**

Security of Supply, Market integration (Northern Scandinavia, Sweden, Finland and Norway), Diversification of sources, Diversification of routes, Back-up for renewables,

- Increases the competitiveness of the Northern EU and its industry and securing Nordic raw materials for the manufacturing of industrial and consumer goods in NW and Continental
- Europe at economical prices (incl. metals, chemical and pulp & paper).


Improves the security of supply within the Northern EU – no energy islands.

- Reduces environmental pollution and CO2/NOx –emissions (replaces LPG, oil, peat and coal).
- Supports EU transportation policies, TEN-T, and Motorways of the Sea programme and SECA regulations within the Baltic Sea.
- Enhances the use of LNG in maritime transport in the region provides ship vessel bunkering availability.
- Satisfies energy needs and demands both in Sweden and in Finland 100% alignment with the Northern dimension of the EU.

#### COMMENTS ABOUT THE PROJECT FINANCING

Public financing	Private financing	Multilateral financing










## LNG-F-210 Dunkerque LNG Terminal FID


#### **LNG Terminal**

#### SPONSORS



#### GENERAL INFORMATION

Promoter	EdF
Operator	Dunkerque LNG
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	Yes
Exemption granted ?	Yes
% Exemption in entry direction	100%
% Exemption in exit direction	100%

SCHEDULE	
End of permitting phase	2010 Q2
FID	2011 Q2
Construction	2011 Q3
Commissioning	2015 Q4
Last completed Phase :	FID

TECHNICAL INFORMATION	
Regasification facility	Dunkerque LNG
Expected volume (bcm/y)	+13,00
Storage capacity (m3)	+570.000,00
Send-out (mcm/d)	+45,60
Ship size (m3)	267.000,00
Reloading ability ?	Yes



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Dunkerque LNG / FRn	Yes	exit	519,00	LNG Terminals France(PEG North)	LNG Terminals France(PEG North)
Dunkerque LNG / Avringem - BE	Yes	exit	270,00	LNG Terminals France(PEG North)	Hub Belgium
Dunkerque LNG	Yes	exit	501,60	LNG Terminals France(PEG North)	Hub France(PEG North)

DESCRIPTION OF THE PROJECT		
LNG regasification Facility located in Dunkirk		
EXPECTED BENEFITS		
COMMENTS ABOUT THE PROJECT FINANCING		
Public financing	Private financing	Multilateral financing




UGS-N-204 Salins des Landes Non-FID


**Storage Facility** 

SPONSORS

#### GENERAL INFORMATION



Promoter	EdF
Operator	EDF
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	Not yet
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	2016 Q2
Construction	2016 Q3
Commissioning	2021 Q1
Last completed Phase :	Planned

TECHNICAL INFORMATION	
Storage facility	Salins des Landes
Working volume (mcm)	+600,00
Injectability (mcm/d)	+10,42
Deliverability (mcm/d)	+20,16



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Salins des Landes	Yes	entry	114,62	Hub France(TIGF)	Storage France(TIGF)
	Yes	exit	221,76	Storage France(TIGF)	Hub France(TIGF)

DESCRIPTION OF THE PROJECT					
Salins des Landes is a fast-cylce storage project in salt cavern located in South-West France					
EXPECTED BENEFITS					
Security of Supply, Market integration (France and Spain), N-1 National (In case of supply disruption, Salins des Landes will provide short-term deliverability to ensure demand is met), N-1 Regional (North-South West priority corridor), Back up for renewables, Power-to-gas					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private financing	Multilateral financing			




LNG-N-227	Fos Cavaou LNG Terminal Expansion	Non-FID
-----------	-----------------------------------	---------


**LNG Terminal** 

**SPONSORS** 

#### GENERAL INFORMATION



Promoter	Elengy
Operator	Fosmax LNG
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	www.fosmax-lng.com



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2015 Q4
FID	2015 Q4
Construction	2016 Q2
Commissioning	2020 Q2
Last completed Phase :	Planned

TECHNICAL INFORMATION	
Regasification facility	Fos Cavaou LNG Terminal
Expected volume (bcm/y)	+8,25
Storage capacity (m3)	+220.000,00
Send-out (mcm/d)	+28,00
Ship size (m3)	270.000,00
Reloading ability ?	Yes



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Fos Cavaou	Yes	exit	308.00	LNG Terminals France(PEG South)	Hub France(PEG South)

#### **DESCRIPTION OF THE PROJECT**

The project aims to expand the LNG terminal capacity from 8.25 to 16.5 bcm/a through the construction of regasification units and storage tanks.

#### **EXPECTED BENEFITS**

Security of Supply, Market integration, Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (France), N-1 Regional (France, Germany, Switzerland, Italy (Northern)), Back-up for renewables
Thanks to its location, Fos Cavaou LNG terminal is an excellent entry gate in Western Europe for LNG coming from the Mediterranean basin and the Middle East (which represent more than 45% of the world LNG production), toward the core of the European gas market in particular France, Germany as well as Switzerland and Northern Italy (through Switzerland). Indeed, LNG has the tremendous advantage of being able to be efficiently delivered at the nearest of the gas consumption areas, by optimizing pipeline and sea transportation. Moreover, the recent development of reloading services has significantly increased the fonctionalities of the LNG terminals, enabling them to offer possibilities equivalent to reverse flows, in addition to the classical uses.

From the Market Integration point of view, the project will strongly contribute to linking Northern and Southern European markets, through the hubs to which it give access in the North (France, Germany, Switzerland, Northern Italy), and through "flexible floating pipeline", ie ship tranfers, from and to the South (Spain, Italy, Greece, Malta in the future). In addition, the project will also enable to free up significant part of the already existing / under construction pipeline interconnection capacity between Spain and France, so that this capacity can be first and foremost utilized for short term trading.

The project will also contribute to:

- an increase of the competition,
- the development of shortsea LNG trading,
- the development of ECA (Emission Controlled Area) zones in the Northern part of the Mediterranean sea

#### COMMENTS ABOUT THE PROJECT FINANCING

Public financing	Private financing	Multilateral financing




TRA-N-255	Fos Tonkin LNG expansion	Non-FID


#### **Pipeline including CS**

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	GRTgaz		
Operator	GRTgaz		
TEN-E Project ?	Not part of TEN-E		
Interested by PCI ?	no		
IGAs	None		
Web Link	www.grtgaz.com/en/home/major-projects/plan-decennal/10-year-development/		



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2019
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
	Yes		80,00		outh) Hub France(PEG South)
Fos	ies	entry	80,00	LNO TETTIMIAS FIAILE(FEG SC	nub riance(red South)
DESCRIPTION OF THE PROJECT					
Only core system developments are needed for this expansion : they will depend	on the other	entry capacity	vincreases in the South zon	e	
EXPECTED BENEFITS					
Security of Supply, Market integration, Diversification of sources, Diversification of	of routes, Bacl	<-up for renew	vables		
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




LNG-N-225	Montoir LNG Terminal Expansion	Non-FID
	· ·	


#### **LNG Terminal**

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	Elengy		
Operator	Elengy		
TEN-E Project ?	Not part of TEN-E		
Interested by PCI ?	Yes		
IGAs	None		
Web Link	www.elengy.com/en/projects/montoir-extension.html		



THIRD-PARTY ACCESS REGIME				
Considered TPA Regime	Regulated			
Considered Tariff Regime	Regulated			
Applied for Exemption ?	No			
Exemption granted ?	Not relevant			
% Exemption in entry direction	0%			
% Exemption in exit direction	0%			

SCHEDULE	
End of permitting phase	2015 Q1
FID	2015 Q1
Construction	2015 Q2
Commissioning	2018 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
Regasification facility	Montoir LNG Terminal
Expected volume (bcm/y)	+6,50
Storage capacity (m3)	+190.000,00
Send-out (mcm/d)	+20,00
Ship size (m3)	265.000,00
Reloading ability ?	Yes



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Montoir de Bretagne	Yes	exit	220,00	LNG Terminals France(PEG North)	Hub France(PEG North)

#### **DESCRIPTION OF THE PROJECT**

The project aims to expand the LNG terminal capacity from 10 to 16.5 bcm/y through the construction of regasification units and storage tanks.

#### **EXPECTED BENEFITS**

Security of Supply, Market integration, Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (France), N-1 Regional (France, Germany, Benelux countries, Switzerland, Italy (Northern)), Back-up for renewables, Thanks to its location, Montoir LNG terminal is, from every points of view, one of the best entry gate in Western Europe for LNG coming from all over the world toward the core of the European gas market in particular France, Germany as well as Switzerland and Northern Italy (through Switzerland). In particular, the project is very well located to receive LNG from North America where LNG liquefaction should develop rapidly. Indeed, LNG has the tremendous advantage of being able to be efficiently delivered at the nearest of the gas consumption areas, by optimizing pipeline and sea transportation.

Moreover, the recent development of reloading services has significantly increased the fonctionalities of the LNG terminals, enabling them to offer possibilities equivalent to reverse flows, in addition to the classical uses. The project will strongly contribute to linking Northern and Southern European markets, through the hubs to which it give access in the North (France, Germany, Benelux countries, Switzerland, Northern Italy), and through "flexible floating pipeline", ie ship transfers, from and to the South (in particular Spain and Portugal). The project will also enable to free up significant part of the already existing / under construction pipeline interconnection capacity between Spain and France, so that this capacity can be first and foremost utilized for short term trading.

In addition to the above, the project will also contribute to (see below):

- the reinforcement of the competition,
- the development of shortsea LNG trading,
- the development of ECA (Emission Controlled Area) zones on the Western Atlantic coast

#### COMMENTS ABOUT THE PROJECT FINANCING


Public financing	Private financing	Multilateral financing



# LNG-N-223 Fos Faster LNG Terminal Non-FID

# **LNG Terminal**


#### **SPONSORS**



# GENERAL INFORMATION

Promoter	Fos Faster LNG
Operator	Faster
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	www.fosfaster.com





THIRD-PARTY ACCESS REGIME				
Considered TPA Regime	Negotiated (e.g. Exemption)			
Considered Tariff Regime	Negotiated (e.g. Exemption)			
Applied for Exemption ?	Not yet			
Exemption granted ?	Not yet			
% Exemption in entry direction	0%			
% Exemption in exit direction	0%			

SCHEDULE	
End of permitting phase	2019
FID	2015
Construction	2019
Commissioning	2019
Last completed Phase :	Market test

TECHNICAL INFORMATION	
Regasification facility	Fos Faster
Expected volume (bcm/y)	+8,00
Storage capacity (m3)	+360.000,00
Send-out (mcm/d)	+24,00
Ship size (m3)	270.000,00
Reloading ability ?	Yes




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Fos Faster	Yes	exit	264,00	LNG Terminals France(PEG Sout	h) Hub France(PEG South)
DESCRIPTION OF THE PROJECT					
The project aims to build a new LNG terminal at Fos-sur-Mer near Marseille in Fra Our projected terminal is dedicated to be an independent, opened and multi-cust					
EXPECTED BENEFITS					
Security of Supply, Market integration (South Of France), Reverse Flows, Diversif the South of France, to open an independent and multi customers terminal and t					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing		Mu	Itilateral financing




TRA-F-036	Arc de Dierrey	FID

#### SPONSORS

#### GENERAL INFORMATION



Promoter	GRTgaz
Operator	GRTgaz
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	www.grtgaz.com/en/home/major-projects/plan-decennal/10- year-development/



THIRD-PARTY ACCESS REGIME			
Considered TPA Regime	Regulated		
Considered Tariff Regime	Regulated		
Applied for Exemption ?	Not relevant		
Exemption granted ?	Not relevant		
% Exemption in entry direction	0%		
% Exemption in exit direction	0%		

SCHEDULE			
End of permitting phase			
FID	2011 Q4		
Construction	2015		
Commissioning	2015 Q4		
Last completed Phase :	FID		

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+308,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
DESCRIPTION OF THE PROJECT					
This core system development is necessary for several projects in the North (Duni	keraue I NG te	erminal Mero	zer of the North and South	zones Exit canacity increase :	at Oltingue Reverse canacity at Obergailbach, etc.)
This core system development is necessary for several projects in the North (Bull	kerque Eno te	initial, were	ser of the Horth and Journ	zones, zwe capacity mercuse i	at Oldingue, here is a capacity at Oberguinacei, etc.,
EXPECTED BENEFITS					
EXPECTED DENEFITS					
	ot				
Security of Supply, Market integration, Reverse Flows, Diversification of sources,	Diversification	of routes			
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-N-048 Developments for Montoir LNG terminal expansion at 12,5bcm - 1 Non-FID


**Pipeline including CS** 

SPONSORS

# GENERAL INFORMATION



Promoter	GRTgaz
Operator	GRTgaz
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	www.grtgaz.com/en/home/major-projects/plan-decennal/10-year-development/



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	Not relevant
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2018
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+63,00
Total Compressor Power (MW)	+10,00
Maximum Capacity (GWh/d)	
Expected Load Factor	



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Montoir de Bretagne	Yes	entry	55,00	LNG Terminals France(PEG No	rth) Hub France(PEG North)
DESCRIPTION OF THE PROJECT					
This entry capacity increase at Montoir only needs specific developments.					
EXPECTED BENEFITS					
	_				
Security of Supply, Market integration, Diversification of sources, Diversification of	f routes				
COLUMN AT A TOTAL OF THE PROPERTY FILL AND INC.					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing		N	Aultilateral financing




TRA-N-258 Developments for Montoir LNG terminal expansion at 16,5bcm - 2 Non-FID


**Pipeline including CS** 

SPONSORS

# GENERAL INFORMATION



Promoter	GRTgaz
Operator	GRTgaz
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	www.grtgaz.com/en/home/major-projects/plan-decennal/10- year-development/



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	Not relevant
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2021
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+200,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	




Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Montoir de Bretagne	Yes	entry	125,00	LNG Terminals France(PEG North	th) Hub France(PEG North)
DESCRIPTION OF THE PROJECT					
This entry capacity increase at Montoir needs specific developments and core sys	tem developr	nents (New li	ne between Chemery and D	Dierrev).	
	·	,	,	,,	
EXPECTED BENEFITS					
Security of Supply, Market integration, Diversification of sources, Diversification of	f routes				
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing		M	ultilateral financing




TRA-F-038	Developments for the Dunkerque LNG new terminal	FID

SPONSORS

#### GENERAL INFORMATION



Promoter	GRTgaz
Operator	GRTgaz
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	www.grtgaz.com/en/home/major-projects/plan-decennal/10-year-development/



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	2011 Q4
Construction	2015
Commissioning	2015 Q4
Last completed Phase :	FEED

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	2
Total Pipeline Length (km)	+142,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	




Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Dunkerque LNG / FRn	Yes	entry	250,00	Fork France(Dunkerque LN	G) Hub France(PEG North)
DESCRIPTION OF THE PROJECT					
The connection of the terminal needs spécific transmission system developement	and core sys	tem develope	ements (Arc de Dierrey)		
EXPECTED BENEFITS					
Security of Supply, Market integration, Diversification of sources, Diversification of	of routes				
security of supply, warket integration, siversineation of sources, siversineation	n routes				
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncina			Multilateral financing
runic infancing	riivate iina	neng			iniditulateral ililalitulig




TRA-N-254	Developments for the Fos faster LNG new terminal	Non-FID

**SPONSORS** 

#### GENERAL INFORMATION



Promoter	GRTgaz
Operator	GRTgaz
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	www.grtgaz.com/en/home/major-projects/plan-decennal/10-year-development/



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2019
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+30,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	




Interconnection	Modelled	Direction	Capacity	/ (GWh/d)	From Zone	To Zone	
Fos	Yes	entry		255,00	LNG Terminals France(PEG	outh) Hub France(PE	G South)
	No	entry		383,00	LNG Terminals France(PEG	outh) Hub France(PE	G South)
DESCRIPTION OF THE PROJECT							
In addition to this specific connection, the reinforcement of the core transmission	n system is als	o needed (ER	IDAN, East	Lyonnais pipelin	e,Bourgogne and/or compres	ons depending on the	developments already realized)
EXPECTED BENEFITS							
Security of Supply, Market integration, Diversification of sources, Diversification of	of routes, Bac	k-up for renev	vables				
COMMENTS ABOUT THE PROJECT FINANCING							
Public financing	Private fina	ncing				Multilateral financing	
,		J					




TRA-N-043	Developments to merge GRTgaz North and South zones	Non-FID

#### **SPONSORS**

# GENERAL INFORMATION



Promoter	GRTgaz
Operator	GRTgaz
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	www.grtgaz.com/en/home/major-projects/plan-decennal/10-year-development/



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	Not relevant
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2018
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+190,00
Total Compressor Power (MW)	+9,00
Maximum Capacity (GWh/d)	
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Liaison Nord Sud	Yes	entry	999,00	Hub France(PEG North)	Hub France(PEG South)
	Yes	exit	999,00	Hub France(PEG North)	Hub France(PEG South)

DESCRIPTION OF THE PROJECT	DESCRIPTION OF THE PROJECT				
In addition to the core transmission system reinforcement projects, Arc de Dierrey in the North and ERIDAN in the South, this merger needs the looping of the Bourgogne pipeline (between Etrez and Voisines)					
EXPECTED BENEFITS					
Security of Supply, Market integration					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private financing	Multilateral financing			




TRA-F-037	Entry capacity increase from Belgium to France	FID
Pipeline including CS		

**GENERAL INFORMATION** 



**SPONSORS** 

# Promoter GRTgaz Operator GRTgaz TEN-E Project ? Not part of TEN-E Interested by PCI ? No IGAs None Web Link www.grtgaz.com/en/home/major-projects/plan-decennal/10-year-development/



THIRD-PARTY ACCESS REGIME		SCHEDULE		TECHNICAL INFORMATION	
Considered TPA Regime	Regulated	End of permitting phase	2012	# of Pipelines, nodes, CS	1
Considered Tariff Regime	Regulated	FID	2010 Q2	Total Pipeline Length (km)	+51,00
Applied for Exemption ?	No	Construction	2013	Total Compressor Power (MW)	+8,00
Exemption granted ?	Not relevant	Commissioning	2013 Q4	Maximum Capacity (GWh/d)	
% Exemption in entry direction	0%	Last completed Phase :	Permitting	Expected Load Factor	
% Exemption in exit direction	0%				




Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Blarégnies (BE) / Taisnières (H) (FR)	Yes	entry	50,00	Hub Belgium	Hub France(PEG North)
DESCRIPTION OF THE PROJECT					
Transmission systems development(s) in FR (and BE) to increase entry capacity in	FR at Taisnièr	es (from 590	to 640 GWh/d) - OS in 2009	9/2010	
		·			
EXPECTED BENEFITS					
Security of Supply, Market integration					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-F-041	Eridan	Non-FID

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	GRTgaz
Operator	GRTgaz
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	www.grtgaz.com/en/home/major-projects/plan-decennal/10 year-development/



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	Not relevant
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	2011
Construction	2016
Commissioning	2016
Last completed Phase :	FID

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+220,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
This development of the core transmission system, Saint Martin de Crau - Saint A	vit pipeline, is	necessary fo	or entry/exit capacity incre	eases in the South zone and to	merge the North an South zones.
EXPECTED BENEFITS					
Security of Supply, Market integration, Diversification of sources, Diversification of	of routes, Bac	k-up for rene	wables		
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing
EEPR					




TRA-N-253	Est Lyonnais pipeline	Non-FID

#### **SPONSORS**

#### **GENERAL INFORMATION**



Promoter	GRTgaz
Operator	GRTgaz
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	www.grtgaz.com/en/home/major-projects/plan-decennal/10- year-development/



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2019
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+170,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	




Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Fos	No	entry	0,00	LNG Terminals France(PEG Sout	h) Hub France(PEG South)
DESCRIPTION OF THE PROJECT					
This development of the core transmision system is necessary to develop entry c	apacity in the	South (Fos Pr	ojects, IP with spain, storag	es) and contribute to the South-N	orth corridor in Western Europe
EXPECTED BENEFITS					
Security of Supply, Market integration, Diversification of sources, Diversification of routes, Back-up for renewables					
COMMENTS ABOUT THE PROJECT FINANCING	Bulanta C				dilatan fire a de-
Public financing	Private fina	incing		Mu	ultilateral financing




TRA-N-046	Exit capacity increase to CH at Oltingue	Non-FID
Pineline including CS		

SPONSORS

#### GENERAL INFORMATION



Promoter	GRTgaz
Operator	GRTgaz
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	www.grtgaz.com/en/home/major-projects/plan-decennal/10-year-development/



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2019
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	2
Total Pipeline Length (km)	
Total Compressor Power (MW)	+30,00
Maximum Capacity (GWh/d)	
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Oltingue (FR) / Rodersdorf (CH)	Yes	exit	100,00	Hub France(PEG North)	Hub Switzerland
	No	exit	40,00	Hub France(PEG North)	Hub Switzerland


DESCRIPTION OF THE PROJECT					
Specific transmission system develpements to increase exit capacity to CH (design to confirm according to the market demand)					
EXPECTED BENEFITS					
Security of Supply, Market integration					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private financing	Multilateral financing			




TRA-N-255	Fos Tonkin LNG expansion	Non-FID

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	GRTgaz
Operator	GRTgaz
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	no
IGAs	None
Web Link	www.grtgaz.com/en/home/major-projects/plan-decennal/10-year-development/



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2019
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	




Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
	Yes		80,00		outh) Hub France(PEG South)
Fos	ies	entry	80,00	LNO TETTIMIAS FIAILE(FEG SC	nub riance(red South)
DESCRIPTION OF THE PROJECT					
Only core system developments are needed for this expansion : they will depend	on the other	entry capacity	vincreases in the South zon	e	
EXPECTED BENEFITS					
Security of Supply, Market integration, Diversification of sources, Diversification of	of routes, Bacl	<-up for renew	vables		
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-N-269	Fosmax (Cavaou) LNG expansion	Non-FID
-----------	-------------------------------	---------

SPONSORS

#### GENERAL INFORMATION



Promoter	GRTgaz
Operator	GRTgaz
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	no
IGAs	None
Web Link	www.grtgaz.com/en/home/major-projects/plan-decennal/10- year-development/



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2020
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	



nterconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
ios	Yes	entry	327,00	LNG Terminals France(PEG Sou	uth) Hub France(PEG South)
DESCRIPTION OF THE PROJECT					
Only core system developments are needed for this expansion : they will depend	d on the other	entry capacity	/ increases in the South z	one	
EXPECTED BENEFITS					
security of Supply, Market integration, Diversification of sources, Diversification	of routes, Back	-up for renev	vables		
OMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing		N	Aultilateral financing
COMMENTS ABOUT THE PROJECT FINANCING Public financing	Private fina	ncing		N	Aultilateral financing



TRA-N-256


Iberian-French corridor: Eastern Axis-Midcat Project (CS Montpellier and CS Saint Martin de Crau)

Non-FID


# **Pipeline including CS**

#### **SPONSORS**

# GENERAL INFORMATION



Promoter	GRTgaz
Operator	GRTgaz
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	yes
IGAs	None
Web Link	www.grtgaz.com



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2020
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	
Total Compressor Power (MW)	+30,00
Maximum Capacity (GWh/d)	
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
PIR MIDI	Yes	entry	230,00	Hub France(TIGF)	Hub France(PEG South)
	Yes	exit	80,00	Hub France(PEG South)	Hub France(TIGF)
DESCRIPTION OF THE PROJECT					
GRTgaz contribution to develop a new FR-ES IP on the Eastern axis -MidCat. In ad compressions depending on the developments already realized)	dition to the	se specific dev	velopments, the reinforcem	nent of the core transmission	system is also needed (ERIDAN, East Lyonnais pipeline, Bourgogne and/or
compressions depending on the developments an eady realized)					
EXPECTED BENEFITS					
Security of Supply, Market integration, Diversification of sources, Diversification o	froutes Back	c-un for renew	vahles		
Security of Supply, Market integration, Diversincation of Sources, Diversincation of	rroutes, buci	Cup for reflex	vables		
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-F-039	Iberian-French corridor: Western Axis (CS Chazelles)	FID

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	GRTgaz
Operator	GRTgaz
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	www.grtgaz.com#http://www.grtgaz.com#



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2012
FID	2010 Q1
Construction	2013
Commissioning	2013 Q1
Last completed Phase :	Permitting

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	
Total Compressor Power (MW)	+36,00
Maximum Capacity (GWh/d)	
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
PIR MIDI	Yes	entry	175,00	Hub France(TIGF)	Hub France(PEG South)
	Yes	exit	70,00	Hub France(PEG South)	Hub France(TIGF)

DESCRIPTION OF THE PROJECT		
GRTgaz contribution to the transmission systems developments to develop FR-ES IP at Larrau and Biriatou, OS in 2009/2010		
EXPECTED BENEFITS		
Security of Supply, Market integration, Diversification of sources, Diversification of routes, Back-up for renewables		
COMMENTS ABOUT THE PROJECT FINANCING		
Public financing	Private financing	Multilateral financing




TRA-N-042	New interconnection IT-FR to connect Corsica	Non-FID
Pipeline including CS		


ripellile illelading e

SPONSORS



#### GENERAL INFORMATION





**FINANCING** 

THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	Not relevant
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

French section, GRTgaz (100%)

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2018
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	2
Total Pipeline Length (km)	+320,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	




Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Porto-Vecchio	Yes	entry	20,00	Interconnector GALSI	Hub France(Corsica)
DESCRIPTION OF THE PROJECT					
This project is linked to the GALSI project and includes an offshore pipeline from S	Sardinia to Co	rsica and ons	hore pipelines in Corsica		
EXPECTED BENEFITS					
Security of Supply, Market integration, Back-up for renewables, Access to Natural	gas for Corsi	са			
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing
Expected					




TRA-N-044	New interconnection to Luxembourg	Non-FID
Pineline including CS		

SPONSORS

#### GENERAL INFORMATION



Promoter	GRTgaz
Operator	GRTgaz
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	www.grtgaz.com/en/home/major-projects/plan-decennal/10- year-development/



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	2013
Construction	
Commissioning	2018
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	2
Total Pipeline Length (km)	+71,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
New IP France/Luxemburg	Yes	exit	40,00	Hub France(PEG North)	Hub Luxemburg
	Yes	exit	9,00	Hub France(PEG North)	Hub Luxemburg


DESCRIPTION OF THE PROJECT				
Project design to finalised according to the OS				
EXPECTED BENEFITS				
Security of Supply, Market integration, Diversification of sources, Diversification of routes, Back-up for renewables				
COMMENTS ABOUT THE PROJECT FINANCING				
Public financing	Private financing	Multilateral financing		




TRA-N-257	New line Between Chemery and Dierrey	Non-FID

SPONSORS

# GENERAL INFORMATION



Promoter	GRTgaz			
Operator	GRTgaz			
TEN-E Project ?	Not part of TEN-E			
Interested by PCI ?	No			
IGAs	None			
Web Link	www.grtgaz.com/en/home/major-projects/plan-decennal/2 year-development/			



THIRD-PARTY ACCESS REGIME			
Considered TPA Regime	Regulated		
Considered Tariff Regime	Regulated		
Applied for Exemption ?	Not relevant		
Exemption granted ?	Not relevant		
% Exemption in entry direction	0%		
% Exemption in exit direction	0%		

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2021
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+210,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
This core system development develop West-East capacity transit necessary for N	∕lontoir LNG t	erminal expai	nsion2 and firm reverse flo	w to Germany	
EXPECTED BENEFITS					
Security of Supply, Market integration, Diversification of sources, Diversification of	of routes, Bac	k-up for renev	wables		
COMMENTS ABOUT THE PROJECT FINANCING					
	Duivete fine				Baubilaharal financing
Public financing	Private fina	ncing			Multilateral financing




TRA-N-045	Reverse capacity from CH to FR at Oltingue	Non-FID

SPONSORS

# GENERAL INFORMATION



Promoter	GRTgaz
Operator	GRTgaz
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	www.grtgaz.com#http://www.grtgaz.com#



THIRD-PARTY ACCESS REGIME		SCHEDULE		TECHNICAL INFORMATION	
Considered TPA Regime	Regulated	End of permitting phase		# of Pipelines, nodes, CS	1
Considered Tariff Regime	Regulated	FID		Total Pipeline Length (km)	+87,00
Applied for Exemption ?	Not relevant	Construction		Total Compressor Power (MW)	
Exemption granted ?	Not relevant	Commissioning	2018	Maximum Capacity (GWh/d)	
% Exemption in entry direction	0%	Last completed Phase :	Planned	Expected Load Factor	
% Exemption in exit direction	0%				




Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Oltingue (FR) / Rodersdorf (CH)	Yes	entry	100,00	<b>Hub Switzerland</b>	Hub France(PEG North)
DESCRIPTION OF THE PROJECT					
Developements needed to create this reverse capacity					
Developements needed to create this reverse capacity					
EXPECTED BENEFITS					
Security of Supply, Market integration, Reverse Flows, Diversification of sources,	Diversification	n of routes			
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	incing			Multilateral financing




TRA-F-040	Reverse capacity from France to Belgium at Veurne	FID

### **SPONSORS**

### GENERAL INFORMATION



Promoter	GRTgaz
Operator	GRTgaz
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	www.grtgaz.com/en/home/major-projects/plan-decennal/10- year-development/



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	2012 Q2
Construction	2015
Commissioning	2015 Q4
Last completed Phase :	FID

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+26,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	




Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
New IP FR-BE (FR) / Alveringem-Maldegem (BE)	Yes	exit	270,00	Hub France(PEG North)	Hub Belgium
DESCRIPTION OF THE PROJECT					
DESCRIPTION OF THE PROJECT					
New IP near Veurne between GRTgaz and Fluxys with capacity from FR to BE					
EXPECTED BENEFITS					
Security of Supply, Market integration, Reverse Flows					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-N-047	Reverse capacity from France to Germany at Obergailbach	Non-FID

**SPONSORS** 

### GENERAL INFORMATION



Promoter	GRTgaz
Operator	GRTgaz
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	www.grtgaz.com/en/home/major-projects/plan-decennal/10- year-development/



THIRD-PARTY ACCESS REGIME				
Considered TPA Regime	Regulated			
Considered Tariff Regime	Regulated			
Applied for Exemption ?	No			
Exemption granted ?	Not relevant			
% Exemption in entry direction	0%			
% Exemption in exit direction	0%			

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2018
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+60,00
Total Compressor Power (MW)	+42,00
Maximum Capacity (GWh/d)	
Expected Load Factor	



Interconnection	Modelled	Direction	Capacity	(GWh/d)	From Zone	To Zone
Medelsheim (DE) / Obergailbach (FR)	Yes	exit		100,00	Hub France(PEG North)	Hub Germany(NCG)
	No	exit		250,00	Hub France(PEG North)	Hub Germany
Medelsheim (DE) / Obergailbach (FR)	No	exit		180,00	Hub France(PEG North)	Hub Germany(NCG)
DESCRIPTION OF THE PROJECT						
This project includes pipelines (including compression) and changes in the odorisa	tion system (	replacing odo	oristaion st	ations at the enti	ry of the transmission system	n by odorisation stations at the entry of the regional networks)
EXPECTED BENEFITS						
Security of Supply, Market integration, Reverse Flows, Diversification of sources, Diversification of routes						
COMMENTS ABOUT THE PROJECT FINANCING						
Public financing	Private fina	ncing				Multilateral financing




UGS-N-003	Etrez / Manosque	Non-FID
000 N 000		11011 1 22


**Storage Facility** 

SPONSORS

### GENERAL INFORMATION



Promoter	Storengy
Operator	Storengy
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2014
Last completed Phase :	Construction

TECHNICAL INFORMATION	
Storage facility	Etrez /Manosque Gas Storage
Working volume (mcm)	+120,00
Injectability (mcm/d)	+2,00
Deliverability (mcm/d)	+7,00



To Zone

Multilateral financing

Etrez/Manosque	Yes	exit	77,00	Storage France(PEG South)	Hub France(PEG South)
	Yes	entry	22,00	Hub France(PEG South)	Storage France(PEG South)
DESCRIPTION OF THE PROJECT					
Extension of the exisiting salt cavity storage facilities.					
EXPECTED BENEFITS					
Market Integration (Increase of competition) The project will contribute to the increase of storage capacity in France, which will enhance security of supply and provide more flexibility to the market thus facilitating competition					

From Zone

Modelled Direction Capacity (GWh/d)

Private financing

PROJECTED CAPACITY INCREASES

COMMENTS ABOUT THE PROJECT FINANCING

**Public financing** 

Interconnection




UGS-N-264 Etrez / Manosque - Stage 2 Non-FID


**Storage Facility** 

SPONSORS

### GENERAL INFORMATION



Promoter	Storengy
Operator	Storengy
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2022
Last completed Phase :	Construction

TECHNICAL INFORMATION	
Storage facility	Etrez /Manosque Gas Storage
Working volume (mcm)	+480,00
Injectability (mcm/d)	+9,00
Deliverability (mcm/d)	+28,00



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Etrez/Manosque	Yes	exit	308,00	Storage France(PEG South)	Hub France(PEG South)
	Yes	entry	99,00	Hub France(PEG South)	Storage France(PEG South)

DESCRIPTION OF THE PROJECT				
Extension of the exisiting salt cavity storage facilities.				
EXPECTED BENEFITS				
Market Integration (Increase of competition) The project will contribute to the increase of storage capacity in France, which will enhance security of supply and provide more flexibility to the market thus facilitating competition				
COMMENTS ABOUT THE PROJECT FINANCING				
Public financing	Private financing	Multilateral financing		




### **Storage Facility**

### **SPONSORS**


### GENERAL INFORMATION

### FINANCING



Promoter		Storengy	
Operator		Storengy	
TEN-E Project ?	Pi	riority Project	
Interested by PCI ?		No	
IGAs		None	
Web Link			
TEN-E Requests	Date of Request	Year Funding Granted	

Year Funding Granted Date of Request 2002



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2015 Q1
Last completed Phase :	Construction

TECHNICAL INFORMATION	
Storage facility	Hauterives
Working volume (mcm)	+40,00
Injectability (mcm/d)	+0,80
Deliverability (mcm/d)	+3,20



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Hauterives	Yes	entry	8,80	Hub France(PEG South)	Storage France(PEG South)
	Yes	exit	35,20	Storage France(PEG South)	Hub France(PEG South)

DESCRIPTION OF THE PROJECT		
Development of a new salt cavity storage.		
EXPECTED BENEFITS		
Security of Supply, Market integration		
COMMENTS ABOUT THE PROJECT FINANCING		
Public financing	Private financing	Multilateral financing



UGS-F-004	Hauterives Storage Project - Stage 1	FID
Storage Eacility		


Storage Facility

SPONSORS

### GENERAL INFORMATION

### **FINANCING**

2002



Promoter		Storengy		
Operator		Storengy		
TEN-E Project ?	P	Priority Project		
Interested by PCI ?		No		
IGAs		None		
Web Link				
TEN-E Requests	Date of Request	Year Funding Granted		

Undefined (100,00%)

THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2014 Q1
Last completed Phase :	Construction

TECHNICAL INFORMATION	
Storage facility	Hauterives
Working volume (mcm)	+60,00
Injectability (mcm/d)	+1,20
Deliverability (mcm/d)	+4,80



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Hauterives	Yes	entry	13,20	Hub France(PEG South)	Storage France(PEG South)
	Yes	exit	52,80	Storage France(PEG South)	Hub France(PEG South)

DESCRIPTION OF THE PROJECT		
Development of a new salt cavity storage.		
EXPECTED BENEFITS		
Security of Supply, Market integration		
COMMENTS ABOUT THE PROJECT FINANCING		
Public financing	Private financing	Multilateral financing




TRA-F-250	Artère de Guyenne (Phase B Girland Project)	FID
Pipeline including CS		


ripellile ilicidulilg C.

SPONSORS

### GENERAL INFORMATION



Promoter	TIGF
Operator	TIGF
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	www.tigf.fr



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	2010
Construction	
Commissioning	2013
Last completed Phase :	FEED

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+58,00
Total Compressor Power (MW)	+5,50
Maximum Capacity (GWh/d)	
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
PIR MIDI	No	entry	185,00	Hub France(PEG South)	Hub France(TIGF)
	No	exit	180,00	Hub France(TIGF)	Hub France(PEG South)
PIR MIDI	Yes	exit	175,00	Hub France(TIGF)	Hub France(PEG South)
	Yes	entry	70,00	Hub France(PEG South)	Hub France(TIGF)


DESCRIPTION OF THE PROJECT		
It's a DN 900 and 58 km long pipeline that conects the UGS of Lussagnet with Captieux with an additional compression at Sauveterre (that's not decided yet)		
EXPECTED BENEFITS		
Security of Supply		
COMMENTS ABOUT THE PROJECT FINANCING		
Public financing	Private financing	Multilateral financing




TRA-F-251	Artère de l'Adour (former Euskadour) (FR-ES interconnection)	FID

**SPONSORS** 

### GENERAL INFORMATION



Promoter	TIGF	
Operator	TIGF	
TEN-E Project ?	Not part of TEN-E	
Interested by PCI ?	Not defined yet	
IGAs	None	
Web Link	www.artere-adour-tigf.fr	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2015 Q4
Last completed Phase :	FEED

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+95,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	




Interconnection	Modelled	Direction	Capacity	(GWh/d)	From Zone	To Zone
Biriatou (FR) / Irun (ES)	Yes	entry		55,00	Hub Spain	Hub France(TIGF)
	Yes	exit		60,00	Hub France(TIGF)	Hub Spain
DESCRIPTION OF THE PROJECT						
It's a 24" and 95 km long pipeline between Arcangues and Coudures that will allo	w to conect (ι	ising the exist	ting infrastr	ructure) the UGS	of Lussagnet with the Spanis	h frontier.
EXPECTED BENEFITS						
Security of Supply						
This project will create the bidirectional gas flow between France and Spain by in	creasing the t	ransport capa	city			
COMMENTS ABOUT THE PROJECT FINANCING						
Public financing	Private fina	ncing				Multilateral financing




TRA-N-252	Iberian-French corridor: Eastern Axis-Midcat Project	Non-FID
TRA-N-252	Iberian-French corridor: Eastern Axis-Midcat Project	Non-FID

### **SPONSORS**

### GENERAL INFORMATION



Promoter	TIGF
Operator	TIGF
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	www.tigf.fr



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%


SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2020
Last completed Phase :	

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	2
Total Pipeline Length (km)	+148,00
Total Compressor Power (MW)	+10,00
Maximum Capacity (GWh/d)	
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Le Perthus	Yes	entry	230,00	Hub Spain	Hub France(TIGF)
	Yes	exit	80,00	Hub France(TIGF)	Hub Spain
DESCRIPTION OF THE PROJECT					
In the French side, it's composed by a 120 km long pipeline between the frontier Baran (Artère du Gascogne).	r (near Le Per	thus) and the	CS of Barbaira, the instala	tion of an aditional compression	on of 10 MW at Barbaira, and a 28 km long pipeline between Lupiac and
EXPECTED BENEFITS					
Security of Supply, Market integration, Reverse Flows, Diversification of sources, Diversification of routes, N-1 National, N-1 Regional, Back-up for renewables					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing

# Germany








# TRA-N-241 MONACO section phase I (Burghausen-Finsing) Non-FID


Pipeline including CS

SPONSORS

### GENERAL INFORMATION



Promoter	bayernets GmbH
Operator	bayernets GmbH
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	1
Web Link	www.bayernets.de/start_netzinformation_en.aspx?int_nam e=_73792



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	Not yet
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2014 Q4
FID	
Construction	2017 Q4
Commissioning	2017 Q4
Last completed Phase :	FEED

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+90,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Tauerngasleitung / Austria	No	exit	0,00		Interconnector Tauerngas Leitung
Penta-West /Überackern	No	exit	0,00		Hub Austria
SÜDAL / Burghausen	No	exit	0,00		
Storage Haiming	No	exit	0,00		Hub Austria
Storage 7Fields	No	exit	0,00		
DESCRIPTION OF THE PROJECT					
Pipeline project					
EXPECTED BENEFITS					
Security of Supply, Market integration, The MONACO project is divided in two phases: 1. Burghausen-Finsing and 2. Finsing-Amerdingen. The new pipeline is targeted to link areas of high demand in Germany and further westwards with liquid gas sources in and through Austria (Überackern/Burghausen at the Austrian border, Penta-West, WAG, MEGAL, Hub CEGH Baumgarten) and of Italy (via TGL pipeline, planned to deliver mainly LNG gas northwards). The project increases physical flow capacity between these market areas and therefore contributes to market integration, as well as accelerating competition through the increased diversification of sources and diversification of routes.  The project will also provide better access of large Austrian gas reservoirs Haidach and 7 UGS to Germany and further westwards. It thus enhances the resilience of the gas network, shows positive impact on the remaining flexibility of the system and therefore contributes to Security of Supply in Europe.					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




# TRA-N-240 MONACO section phase II (Finsing-Amerdingen) Non-FID


Pipeline including CS

SPONSORS

### GENERAL INFORMATION



Promoter	bayernets GmbH
Operator	bayernets GmbH
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	1
Web Link	www.bayernets.de/start_netzinformation_en.aspx?int_nam e=_73792



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	Not yet
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2016 Q4
FID	
Construction	2018 Q4
Commissioning	2018 Q4
Last completed Phase :	Market test

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+130,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Penta-West /Überackern	No	exit	0,00		Hub Austria
Tauerngasleitung / Austria	No	exit	0,00		Interconnector Tauerngas Leitung
SÜDAL / Burghausen	No	exit	0,00		
Storage 7Fields	No	exit	0,00		
Storage Haiming	No	exit	0,00		Hub Austria
DESCRIPTION OF THE PROJECT					
Pipeline project					
EXPECTED BENEFITS					
Security of Supply, Market integration, The MONACO project is divided in two phases: 1. Burghausen-Finsing and 2. Finsing-Amerdingen. The new pipeline is targeted to link areas of high demand in Germany and further westwards with liquid gas sources in and through Austria (Überackern/Burghausen at the Austrian border, Penta-West, WAG, MEGAL, Hub CEGH Baumgarten) and of Italy (via TGL pipeline, planned to deliver mainly LNG gas northwards). The project increases physical flow capacity between these market areas and therefore contributes to market integration, as well as accelerating competition through the increased diversification of sources and diversification of routes.  The project will also provide better access of large Austrian gas reservoirs Haidach and 7 UGS to Germany and further westwards. It thus enhances the resilience of the gas network, shows positive impact on the remaining flexibility of the system and therefore contributes to Security of Supply in Europe.					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-N-207	Bretella	Non-FID

### **SPONSORS**

### GENERAL INFORMATION



Promoter	Fluxys
Operator	Fluxys TENP GmbH
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME			
Considered TPA Regime	Regulated		
Considered Tariff Regime	Regulated		
Applied for Exemption ?	Not relevant		
Exemption granted ?	Not relevant		
% Exemption in entry direction	0%		
% Exemption in exit direction	0%		

SCHEDULE	
End of permitting phase	2014 Q3
FID	2013 Q1
Construction	2014 Q1
Commissioning	2016 Q4
Last completed Phase :	Market test

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+11,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+260,00
Expected Load Factor	




Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Eynatten (BE) // Lichtenbusch / Raeren (DE) (Fluxys TENP)	Yes	entry	260,00	Hub Belgium	Hub Germany(NCG)
	Yes	exit	260,00	Hub Germany(NCG)	Hub Belgium
DESCRIPTION OF THE PROJECT					
Building an additional pipeline between Stolberg and Eynatten to increase bi-dire	ctional flow f	rom the TENP	system to Fluxys Belgium.	This is part of a high case scen	ario of the Reverse Flow project.
EVALUATED DENIFFITO					
EXPECTED BENEFITS					
Security of Supply, Market integration, Reverse Flows, Diversification of sources,	Diversification	n of routes. N-	-1 National. Back-up for rer	newables	
,					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-N-208	Reverse Flow TENP Germany	Non-FID
	· ·	

### **SPONSORS**

### GENERAL INFORMATION



Promoter	Fluxys
Operator	Fluxys TENP GmbH
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME			
Considered TPA Regime	Regulated		
Considered Tariff Regime	Regulated		
Applied for Exemption ?	Not relevant		
Exemption granted ?	Not relevant		
% Exemption in entry direction	0%		
% Exemption in exit direction	0%		

SCHEDULE	
End of permitting phase	2014 Q3
FID	2013 Q1
Construction	2014 Q1
Commissioning	2016 Q4
Last completed Phase :	Market test

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+252,00
Expected Load Factor	



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Wallbach (Fluxys TENP/FluxSwiss)	Yes	entry	252,00	Hub Switzerland	Hub Germany(NCG)
Stolberg	Yes	exit	108,00	<b>Hub Germany(NCG)</b>	Hub Germany(Gaspool)
DESCRIPTION OF THE PROJECT  Reversing the TENP pipeline to be able to source gas from the south (Italy) into the	ne north of Eu	rope. This pro	oject will reverse compresso	or stations and will add comp	ression capacity in Stolberg.
EXPECTED BENEFITS					
Security of Supply, Market integration, Reverse Flows, Diversification of sources, Diversification of routes, N-1 National, Back-up for renewables					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-N-249 Extension of GASCADE grid in the context of the Nord Stream (on-shore) project

Non-FID

### **Pipeline including CS**


### **SPONSORS**



### GENERAL INFORMATION

Promoter	GASCADE Gastransport GmbH
Operator	GASCADE Gastransport GmbH
TEN-E Project ?	Project of European Interest
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	www.gascade.de





THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	0
Considered Tariff Regime	0
Applied for Exemption ?	0
Exemption granted ?	0
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2012 Q4
FID	
Construction	2013 Q4
Commissioning	2014 Q1
Last completed Phase :	Permitting

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+105,00
Total Compressor Power (MW)	+61,00
Maximum Capacity (GWh/d)	
Expected Load Factor	



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Bunde (DE) / Oude Statenziji (H) (NL) (GASCADE)	Yes	exit	285,00	Hub Germany(Gaspool)	Hub Netherlands
Eynatten (BE) // Lichtenbusch / Raeren (DE) (GASCADE)	Yes	exit	100,00	Hub Germany(Gaspool)	Hub Belgium
DESCRIPTION OF THE PROJECT					
Construction of approximately 105 km pipelines (mainly loops) and increase of co	mpressor sta	tions power (a	about 61 MW) to enhance o	capacity of existing pipelines.	
EXPECTED BENEFITS					
Security of Supply, Market integration, Diversification of routes, Extension of transport capacity of Russian gas to the West, Integration of Nord Stream off- and on-Shore in the European gas infrastructure					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing



TRA-F-231


### Extension of existing gas transmission capacity in the direction to Denmark - 1. Step

FID


**Pipeline including CS** 

**SPONSORS** 

### GENERAL INFORMATION



Promoter	Gasunie Deutschland Transport Services GmbH
Operator	Gasunie Deutschland Transport Services GmbH
TEN-E Project ?	Project of Common Interest
Interested by PCI ?	Yes
IGAs	None
Web Link	www.gasunie.de



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	Not relevant
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2014 Q4
Last completed Phase :	Construction

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	
Total Compressor Power (MW)	+15,00
Maximum Capacity (GWh/d)	
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Ellund (GUD)	Yes	exit	50,81	Hub Germany(Gaspool)	Hub Denmark
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Market integration Better connection of the gas hubs (TTF in the Netherlands and market area GASPO	OOL in Germa	any); Compen	isation of the depletion of C	Panish gas fields and better conn	ection of gas hubs; Connection of new storages to the GUD-grid.
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing



TRA-N-232


### Extension of existing gas transmission capacity in the direction to Denmark - 2. Step

Non-FID


### **Pipeline including CS**

**SPONSORS** 

GENERAL INFORMATION



Promoter	Gasunie Deutschland Transport Services GmbH
Onemateu	Casumia Dautachland Transport Saminas Could
Operator	Gasunie Deutschland Transport Services GmbH
TEN-E Project ?	Project of Common Interest
-	
Interested by PCI ?	Yes
IGAs	None
IGAS	Hone
Web Link	www.gasunie.de



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	Not relevant
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2015 Q4
Last completed Phase :	Construction

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	2
Total Pipeline Length (km)	+63,50
Total Compressor Power (MW)	+16,00
Maximum Capacity (GWh/d)	
Expected Load Factor	




PROJECTED CAPACITY INCREASES							
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone		
Ellund (GUD)	Yes	exit	40,56	Hub Germany(Gaspool)	Hub Denmark		
DESCRIPTION OF THE PROJECT							
EXPECTED BENEFITS							
Security of Supply, Market integration  Better connection of the gas hubs (TTF in the Netherlands and market ared GASPOOL in Germany); Compensation of the depletion of Danish gas fields and better connection of gas hubs; Connection of new storages to the GUD-grid.							
Section of the Bas hass ( and the section of the Basin							
COMMENTS ABOUT THE PROJECT FINANCING							
Public financing	Private fina	ncing			Multilateral financing		



### Stepwise change-over to physical H-gas operation of L-gas networks Non-FID TRA-N-244 **Pipeline including CS**


SPONSORS



## GENERAL INFORMATION

Promoter	Open Grid Europe GmbH				
Operator	Open Grid Europe GmbH				
TEN-E Project ?	Not part of TEN-E				
Interested by PCI ?	Not defined yet				
IGAs	None				
Web Link	www.open-grid-europe.com				





THIRD-PARTY ACCESS REGIME		SCHEDULE		TECHNICAL INFORMATION
Considered TPA Regime		End of permitting phase		# of Pipelines, nodes, CS
Considered Tariff Regime		FID	2020	Total Pipeline Length (km)
Applied for Exemption ?		Construction		Total Compressor Power (MW)
Exemption granted ?		Commissioning	2020	Maximum Capacity (GWh/d)
% Exemption in entry direction	0%	Last completed Phase :	Planned	Expected Load Factor
% Exemption in exit direction	0%			



# PROJECTED CAPACITY INCREASES Interconnection Modelled Direction Capacity (GWh/d) From Zone To Zone

# **DESCRIPTION OF THE PROJECT**

Stepwise change-over to physical H-gas operation of L-gas networks (due to decreasing L-gas supply)

# **EXPECTED BENEFITS**

Security of Supply, Market Integration (Increase of competition)

A decline in availability of L-gas necessitates action.

Open Season 2008: The project prioritisation process has been carried out in a non-discriminatory manner based on criteria suggested by BNetzA. It takes into account the factors competition, security of supply, as well as network efficiency. Capacities were allotted to new market entrants. North-south and west-east de-bottlenecking strengthens security of supply.

Future projects: The overall economic benefit of a physical change-over from L (low calorific) to H-gas (high calorific) is higher than permanent conversion. Furthermore, enabling access of storage and gas fired power stations to the network necessitates investments. These measures also serve both market integration and security of supply.

# COMMENTS ABOUT THE PROJECT FINANCING

Public financing	Private financing	Multilateral financing



TRA-N-243

# System enhancements, including the connection of gas-fired power plants, storages and the integration of power to gas facilities


Non-FID

**Pipeline including CS** 


**SPONSORS** 

# GENERAL INFORMATION





Promoter	Open Grid Europe GmbH		
Operator	Open Grid Europe GmbH		
TEN-E Project ?	Not part of TEN-E		
Interested by PCI ?	Not defined yet		
IGAs	None		
Web Link	www.open-grid–europe.com		



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	
Considered Tariff Regime	
Applied for Exemption ?	
Exemption granted ?	
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	2020
Construction	
Commissioning	2020
Last completed Phase :	Planned

TECHNICAL INFORMATION
# of Pipelines, nodes, CS
or repenses, notice, co
Total Pipeline Length (km)
Total Compressor Power (MW)
Maximum Capacity (GWh/d)
Expected Load Factor



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
Extension of the gas grid infrastructure according to the outcomes of the Ge compressor stations and a feasibility study on the integration of power to gas fac				nd forecasts and the optimis	sation of the overall economy, including the expansion and reversion of
EXPECTED BENEFITS					
Security of Supply, Market integration (), Back-up for renewables, Power-to-gas,	Energy turnar	ound: stabilis	ation and better interlinkag	e with power grid, back-up fc	or renewable energies
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




UGS-N-049	Behringen Gas Storage	Non-FID


# **Storage Facility**

# **SPONSORS**

# GENERAL INFORMATION



Promoter	Storengy
Operator	Storengy Deutschland GmbH
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME				
Considered TPA Regime	Negotiated (e.g. Exemption)			
Considered Tariff Regime	Negotiated (e.g. Exemption)			
Applied for Exemption ?	No			
Exemption granted ?	Not relevant			
% Exemption in entry direction	0%			
% Exemption in exit direction	0%			

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2022 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
Storage facility	Behringen Gas Storage
Working volume (mcm)	+1.000,00
Injectability (mcm/d)	+7,00
Deliverability (mcm/d)	+14,00



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Behringen	Yes	exit	154,00	Storage Germany	Hub Germany(Gaspool)
	Yes	entry	77,00	Hub Germany(Gaspool)	Storage Germany

DESCRIPTION OF THE PROJECT			
Development of a new storage facility in a depleted gas field.			
EXPECTED BENEFITS			
COMMENTS ABOUT THE PROJECT FINANCING			
Public financing	Private financing	Multilateral financing	




UGS-N-001	Harsefeld	Non-FID


# **Storage Facility**

# **SPONSORS**

# GENERAL INFORMATION



Promoter	Storengy
Operator	Storengy Deutschland GmbH
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2019 Q2
Last completed Phase :	Planned

TECHNICAL INFORMATION	
Storage facility	Harsefled Gas Storage
Working volume (mcm)	+120,00
Injectability (mcm/d)	+3,60
Deliverability (mcm/d)	+3,60



Interconnection	Modelled	Direction	Capacity (GV	Vh/d)	From Zone		To Zone
Harsefeld	Yes	exit	39	,60	Storage Germany		Hub Germany(Gaspool)
	Yes	entry	39	,60	Hub Germany(Gaspool)		Storage Germany
DESCRIPTION OF THE PROJECT							
Extension of the assisting selt equity atomorp facility in Cormony							
Extension of the existing salt cavity storage facility in Germany							
EXPECTED BENEFITS							
SoS, Market Integration (Increase of competition)  The project will contribute to the increase of storage capacity in France, which wi	II enhance se	curity of supp	ly and provide	more flexibili	ty to the market thus facilita	ting comp	petition
The project will contribute to the increase of storage capacity in France, which will enhance security of supply and provide more flexibility to the market thus facilitating competition.							
COMMENTS ABOUT THE PROJECT FINANCING							
Public financing	Private fina	ncing				Multilat	teral financing

PROJECTED CAPACITY INCREASES




UGS-N-005	Peckensen Gas Storage	Non-FID
003-11-003	reckensen das storage	MOII-I ID


**Storage Facility** 

**SPONSORS** 

# GENERAL INFORMATION



Promoter	Storengy
Operator	Storengy Deutschland GmbH
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2017 Q2
Last completed Phase :	Construction

TECHNICAL INFORMATION	
Storage facility	Peckensen Storage
Working volume (mcm)	+280,00
Injectability (mcm/d)	+3,00
Deliverability (mcm/d)	+10,00



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Peckensen	Yes	entry	33,00	Hub Germany(Gaspool)	Storage Germany
	Yes	exit	110,00	Storage Germany	Hub Germany(Gaspool)
DESCRIPTION OF THE PROJECT					
DESCRIPTION OF THE PROJECT					
Extension of the existing salt cavity gas storage.					
Enterior of the emoting suit to the gas storage.					
EXPECTED BENEFITS					
Security of Supply, Market integration (Western and Central Europe), Diversificati					
will contribute to increased flexibility of the system which will have a positive im			ration and security of supp	oly. Thanks to its location (on	the link between the NGC market area and the Gaspool market area), the
project will have a positive expected influence on price convergence and arbitrage	e opportunitie	es.			
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing

PROJECTED CAPACITY INCREASES




TRA-N-228	Nordschwarzwaldleitung	Non-FID


# **Pipeline including CS**

# **SPONSORS**

# GENERAL INFORMATION



Promoter	terranets bw GmbH
Operator	terranets bw GmbH
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%


SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2016
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+70,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+8,00
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
pipeline between Au am Rhein, coupling to TENP and Leonberg/Stuttgart					
EXPECTED BENEFITS					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing










LNG-N-129	Aegean LNG Import Terminal	Non-FID


# **LNG Terminal**

# **SPONSORS**

# GENERAL INFORMATION



Promoter	DEPA S.A.
Operator	DESFA S.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	Not yet
Exemption granted ?	Not yet
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2014 Q1
FID	2014 Q1
Construction	2016 Q1
Commissioning	2016 Q1
Last completed Phase :	Planned

TECHNICAL INFORMATION	
Regasification facility	Regasification facility is integrated at the FSRII
Expected volume (bcm/y)	+5,00
Storage capacity (m3)	+170.000,00
Send-out (mcm/d)	+14,00
Ship size (m3)	150.000,00
Reloading ability ?	Yes



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Aegean LNG	Yes	entry	154,00	LNG Terminals Greece	Hub Greece
DESCRIPTION OF THE PROJECT					
The LNG import terminal will be a FSRU, located at the North-Eastern (Northern Aegean) area of Greece, with a capacity of 3-5 bcm/y. It will supply LNG directly Greece, Bulgaria and Romania.					
EXPECTED BENEFITS					
Security of Supply, Market integration, Diversification of sources, N-1 National, Back-up for renewables, Power-to-gas  Being located in the North of Greece provides more balanced LNG supply in the country than the existing Revithousa terminal. The upgrading of the pipline network could be facilitated by creating an additional access point in this particular geographical area. Will make available small quantities LNG for industrial/commercial applications and for use it as a transportation fuel for road, rail and marine applications. The availability of LNG in the South-Eastern Balkan area will increase the use of Natural Gas for electricity production and other big industrial applications, reducing substantially the GHG emissions. As a LNG storage facility, the project will respond to daily increases in demand (short term resilience).					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-N-189	East Med	Non-FID


# **Pipeline including CS**

# **SPONSORS**

# GENERAL INFORMATION



Promoter	DEPA S.A.
Operator	Future Greek Trans-Med TSO
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	Not yet
Exemption granted ?	Not yet
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2014 Q3
FID	2014 Q4
Construction	2017 Q3
Commissioning	2017 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	2
Total Pipeline Length (km)	+3.250,00
Total Compressor Power (MW)	+780,00
Maximum Capacity (GWh/d)	+237,00
Expected Load Factor	1,00



## PROJECTED CAPACITY INCREASES

Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Interconnector CY-GR (Trans-Med)	Yes	exit	29,00	Hub Greece	Hub Cyprus
	Yes	entry	237,00	Hub Cyprus	Hub Greece

## **DESCRIPTION OF THE PROJECT**

An offshore natural gas pipeline connecting the offshore natural gas fields in Levantine Basin (Cyprus, Israel) to South Eastern Europe (Bulgaria) or to Italy via Greece

### **EXPECTED BENEFITS**

Security of Supply, Market integration (Cyrpus, Greece, Italy, Bulgaria, Romania, Hungary, FYROM,

Serbia, Albania, BiH, Montenegro), Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (Cyprus, Greece, Italy, Bulgaria), N-1 Regional (South Eastern Europe region), Back-up for renewables

The main objective of the project is to capitalise on the recent offshore discoveries of natural gas in the Eastern Mediterranean.

As a direct result the pipeline will constitute a supply source for Europe which diversifies the supply source, the supply route and the counterparts to Europe with a capacity of around 8-9bcma. Furthermore, the project aims to avoid other transit countries which are part of the current Southern Gas Corridor options and further minimise the security of supply risk.

The diversification of supply source and route will enhance significantly the security of supply of Europe, specifically affecting the Southern Gas Corridor Group, the NSI South Eastern and Central Europe Group and the NSI Western Europe Group.

The project will promote the integration of the market and gas to gas competition.

The additional quantities from East Mediterranean and the alternative route will be the perfect complement to the existing options of the Southern Gas Corridor.

Furthermore the project will alleviate the isolation of at least one MS (i.e. Cyprus) as well as possibly contribute to the alleviation of isolations within a MS (as an example the pipeline may allow the opportunity to alleviate the isolation of Crete from the rest of the Greek national gas grid).

# COMMENTS ABOUT THE PROJECT FINANCING

Public financing	Private financing	Multilateral financing




# TRA-N-128 Compressor Station Kipi Non-FID


**Pipeline including CS** 

SPONSORS

# GENERAL INFORMATION



Promoter	DESFA S.A.
Operator	DESFA S.A.
TEN-E Project ?	Project of Common Interest
Interested by PCI ?	Yes
IGAs	None
Web Link	www.desfa.gr



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	Not relevant
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2014
FID	2013
Construction	2014
Commissioning	2018
Last completed Phase :	FEED

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	2
Total Pipeline Length (km)	
Total Compressor Power (MW)	+38,10
Maximum Capacity (GWh/d)	+374,00
Expected Load Factor	90,00%



PROJECTED CAPACITY INCREASES						
Interconnection	Modelled	Direction	Capacity	(GWh/d)	From Zone	To Zone
Kipi	Yes	entry		102,00	Hub Turkey	Hub Greece
	Yes	entry		374,00	Hub Turkey	Hub Greece
DESCRIPTION OF THE PROJECT						
The project aims at increasing the Transported Capacity of NNGS in order to be publich are likely to be developed in the region.	possible the ti	ransmission o	f natural g	as volumes to the	e Greek and European marke	ts with the use of downstream transmission systems of natural gas, INGS,
EXPECTED BENEFITS						
Market integration (GR-IT-BG-RO), Diversification of sources, Diversification of ro	utes, N-1 Nati	onal (GR), N-1	1 Regional	(GR-IT-BG-RO)		
COMMENTS ABOUT THE PROJECT FINANCING						
Public financing	Private fina	ncing				Multilateral financing




# TRA-N-014 Komotini-Thesprotia pipeline Non-FID

**Pipeline including CS** 

SPONSORS

# GENERAL INFORMATION


# FINANCING



Promoter	DES	DESFA S.A.			
Operator	DES	DESFA S.A.			
TEN-E Project ?	Project of Co	Project of Common Interest			
Interested by PCI ?	,	Yes			
IGAs		1			
Web Link	www.desfa.gr				
TEN-E Requests	Date of Request 1/04/05	Year Funding Granted Not yet			

1/04/03

2004



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	Not relevant
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

End of permitting phase2014FID2013Construction2014	SCHEDULE	
	End of permitting phase	2014
Construction 2014	FID	2013
	Construction	2014
Commissioning 2018	Commissioning	2018
Last completed Phase : FEED	Last completed Phase :	FEED

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+613,00
Total Compressor Power (MW)	+58,20
Maximum Capacity (GWh/d)	+302,70
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
High pressure pipeline from Komotini to Thesprotia area near Ionian coast along v	vith compres	sor stations, c	operation and maintenance	e center.	
EXPECTED BENEFITS					
Security of Supply, Market integration (Western Greece), Diversification of source and Eastern Mediterranean gas sources and European consumers. The project air South Eastern Europe.					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




POW-F-028	Megalopoli pipeline	FID


# Interconnection with a gas-fired power plant

# **SPONSORS**

# **GENERAL INFORMATION**



Promoter	DESFA S.A.
Operator	DESFA S.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	www.desfa.gr



THIRD-PARTY ACCESS REGIME				
Considered TPA Regime	Regulated			
Considered Tariff Regime	Regulated			
Applied for Exemption ?	Not relevant			
Exemption granted ?	Not relevant			
% Exemption in entry direction	0%			
% Exemption in exit direction	0%			

SCHEDULE	
End of permitting phase	2012 Q4
FID	2008 Q2
Construction	2012 Q1
Commissioning	2013 Q3
Last completed Phase :	FEED

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	2
Total Pipeline Length (km)	+166,80
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+42,80
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
High pressure transmission pipeline, metering station from Ag. Theodoroi to Meg	galopoli for co	nnection with	Public Power Corporation	's (PPC) 820 MW gas fired pov	wer plant and urban/industrial areas along the routing.
EXPECTED BENEFITS					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing
From NSRF 2007-2013	DESFA's ow	n equity			EIB loan




TRA-N-188 Reverse flow at GR-BG border (Greek part) Non-FID


**Pipeline including CS** 

SPONSORS

# GENERAL INFORMATION



Promoter	DESFA S.A.
Operator	DESFA S.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	wwwdesfa.gr



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	Not relevant
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	2013 Q2
Construction	2013 Q4
Commissioning	2014 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+33,50
Expected Load Factor	80,00%




PROJECTED CAPACITY INCREASES						
Interconnection	Modelled	Direction	Capacity (G	Wh/d)	From Zone	To Zone
Kula (BG) / Sidirokastron (GR)	Yes	exit	33	3,50	Hub Greece	Hub Bulgaria
DESCRIPTION OF THE PROJECT						
The section is a section of teachers and the Citizens and Development Charles				££		
The project consists of interventions at the Sidirokastro Border Metering Station (				or gas. <ront< td=""><td></td><td></td></ront<>		
color=black>Similar (and more extended) interventions have to take place at the	Bulgarian side	of the netwo	ork			
TVDFCTFR DFAVFFIRE						
EXPECTED BENEFITS						
Security of Supply, Market integration (BG-RO), Reverse Flows, Diversification of sources, Diversification of routes, N-1 Regional (BG-RO)						
COMMENTS ABOUT THE PROJECT FINANCING						
	Duissata fina					No. Itilataval firancias
Public financing	Private fina	nung				Multilateral financing




LNG-F-147	Revythoussa (2nd upgrade)	FID
LNG Terminal		

SPONSORS

# GENERAL INFORMATION



Promoter	D	ESFA S.A.		
Operator	D	DESFA S.A.		
TEN-E Project ?	Project of	Project of Common Interest		
Interested by PCI ?		Yes		
IGAs		None		
Web Link	www.desfa.gr			
TEN-E Requests	Date of Request 30/04/10	Year Funding Granted Not yet		



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	Not relevant
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

2013 Q3
2010 Q2
2014 Q1
2016 Q1
Planned

TECHNICAL INFORMATION	
Regasification facility	Revythoussa LNG Terminal
Expected volume (bcm/y)	+2,10
Storage capacity (m3)	+95.000,00
Send-out (mcm/d)	+5,68
Ship size (m3)	120.000,00
Reloading ability ?	Yes



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Revythoussa	Yes	entry	62,48	LNG Terminals Greece	Hub Greece

# **DESCRIPTION OF THE PROJECT**

The projects consists of:

- the upgrading of the send-out capacity from 1000 to 1400 m3/h (from 14,14 to 19,82 Nm3/d)
- the upgrading of the storage capacity from 130.000 m3 to 225.000 m3 with the addition of a 3rd tank
- the increase of maximum ship size from 140.000 to 260.000  $\mathrm{m}3$

# **EXPECTED BENEFITS**

Security of Supply, Market integration (BG- RO), Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (GR), N-1 Regional (BG- RO), The LNG Terminal at Revythoussa plays significant role regarding the Security of Supply of gas in Greece and contributes to the stable operation of NNGS. The project will enhance the above attitudes along with its flexibility for serving more shippers. It will also increase the storage capacity of the terminal.


# COMMENTS ABOUT THE PROJECT FINANCING

Public financing	Private financing	Multilateral financing
Application to be submitted in 1Q 2013		Loan application not yet submitted



UGS-N-076	Underground Gas Storage at South Kavala	Non-FID
Storage Facility		

GENERAL INFORMATION




**SPONSORS** 

# Promoter Energean Oil & Gas S.A. Operator Energean Oil & Gas S.A. TEN-E Project ? Project of Common Interest Interested by PCI ? Yes IGAs None Web Link TEN-E Requests Date of Request Year Funding Granted

1/02/11

Not yet



THIRD-PARTY ACCESS REGIME		SCHEDULE		TECHNICAL INFORMATION	
Considered TPA Regime	Regulated	End of permitting phase		Storage facility	Underground Gas Storage at South Kayala
Considered Tariff Regime	Regulated	FID	2013 Q4	Working volume (mcm)	+360,00
Applied for Exemption ?	Not yet	Construction	2016 Q2	Injectability (mcm/d)	+5,00
Exemption granted ?	Not yet	Commissioning	2018	Deliverability (mcm/d)	+4,00
% Exemption in entry direction	0%	Last completed Phase :	Planned		
% Exemption in exit direction	0%				



PROJECTED CAPACITY INCREASES						
Interconnection	Modelled	Direction	Capacity	(GWh/d)	From Zone	To Zone
UGS - GR - DESFA/Energean Oil&Gas	Yes	entry		55,00	Hub Greece	Storage Greece
	Yes	exit		44,00	Storage Greece	Hub Greece
DESCRIPTION OF THE PROJECT						
The project is aiming to the conversion of the South Kavala offshore natural gas in the conversion of the South Kavala offshore natural gas in the conversion of the South Kavala offshore natural gas in the conversion of the South Kavala offshore natural gas in the conversion of the South Kavala offshore natural gas in the conversion of the South Kavala offshore natural gas in the conversion of the South Kavala offshore natural gas in the conversion of the South Kavala offshore natural gas in the conversion of the South Kavala offshore natural gas in the conversion of the South Kavala offshore natural gas in the conversion of the South Kavala offshore natural gas in the conversion of the South Kavala offshore natural gas in the conversion of the South Kavala offshore natural gas in the conversion of the South Kavala offshore natural gas in the conversion of the Con						
m, contained between a sequence of evaporites. The license for the developmer Development Fund (HRADF) to which the rights over the field have been transferr	•					
EXPECTED BENEFITS						
Security of Supply, Diversification of sources, N-1 National (Greece), N-1 Regional	(Balkans). Ba	ack-up for ren	newables. o	Security of Sup	ply. Extension of transport car	pacity of Russian gas to the West. Integration of Nord Stream off- and on-
Shore in the European gas infrastructure	(	· · · · ·	, .	, , , , , , , , , , , , , , , , , , , ,	,,,	,
COMMENTS ABOUT THE PROJECT FINANCING						
Public financing	Private fina	ncina				Multilateral financing
i done intunents	i iivate iiila	inemig				manuacia manung




LNG-N-062 Alexandroupolis Independent Natural Gas System - LNG Section Non-FID


**LNG Terminal** 

**SPONSORS** 

# GENERAL INFORMATION



Promoter	Gastrade S.A.
Operator	Gastrade S.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2013 Q2
FID	2013 Q2
Construction	2013 Q3
Commissioning	2015 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
Regasification facility	Alexandroupolis INGS LNG - FSRU
Expected volume (bcm/y)	+2,60
Storage capacity (m3)	+170.000,00
Send-out (mcm/d)	+16,80
Ship size (m3)	170.000,00
Reloading ability ?	No



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Alexandropolis LNG	Yes	exit	184,80	LNG Terminals Greece	Hub Greece
DESCRIPTION OF THE PROJECT					
The project comprises an offshore floating LNG terminal (FSRU) including mooring, flex risers, PLEM, etc. located permanently in the Sea of Thrace, NE Greece					
EXPECTED BENEFITS					
Security of Supply, Market integration (SEE+Serbia+FYROM), Diversification of sources, Diversification of routes, N-1 National (Greece), N-1 Regional (SEE+Serbia+FYROM), Back-up for renewables, Power-to-gas, Extension of transport capacity of Russian gas to the West, Integration of Nord Stream off- and on-Shore in the European gas infrastructure					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-N-063 Alexandroupolis Independent Natural Gas System - Pipeline Section Non-FID


Pipeline including CS

SPONSORS

# GENERAL INFORMATION



Promoter	Gastrade S.A.
Operator	Gastrade S.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2013 Q2
FID	2013 Q2
Construction	2013 Q3
Commissioning	2015 Q4
Last completed Phase :	Planned
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+29,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+268,00
Expected Load Factor	30,00%



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Alexandropolis LNG	Yes	exit	268,00	LNG Terminals Greece	Hub Greece
DESCRIPTION OF THE PROJECT					
The project is a 29 km gas transmission pipeline connecting the Alexandroupolis II	NGS LNG sect	ion (FSRU) to	the Greek Natural Gas Trai	nsmission System (NNGS). The	pipeline has a 25 km subsea and 4 km onshore sections
EXPECTED BENEFITS					
Security of Supply, Market integration (SEE+Serbia+FYROM), Diversification of sources, Diversification of routes, N-1 National (Greece), N-1 Regional (SEE+Serbia+FYROM), Back-up for renewables, Power-to-gas, Extension of transport capacity of Russian gas to the West, Integration of Nord Stream off- and on-Shore in the European gas infrastructure					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing

# Hungary








UGS-N-209	Pusztaederics - Compressor System Reconstruction	Non-FID


**Storage Facility** 

**SPONSORS** 

# GENERAL INFORMATION



Promoter	E.ON Földgaz
Operator	E.ON Hungary Storage
TEN-E Project ?	Project of Common Interest
Interested by PCI ?	Yes
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2013 Q1
FID	2012 Q4
Construction	2013 Q2
Commissioning	2013
Last completed Phase :	FEED

TECHNICAL INFORMATION	
Storage facility	Pusztaederics
Working volume (mcm)	+340,00
Injectability (mcm/d)	+2,50
Deliverability (mcm/d)	+2,90



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Pusztaederics	Yes	exit	31,90	Storage Hungary	Hub Hungary
	Yes	entry	27,50	Hub Hungary	Storage Hungary
DESCRIPTION OF THE PROJECT					
DESCRIPTION OF THE PROJECT					
To significantly increase the operational reliability and flexibility of storage service	as in the year	crucial part of	f the North/South Carridan	in the Region towards Slevenia	Creatia and Carbia
		cruciai part o	i the North/South Corndor	in the Region towards Slovenia	, Croatia and Serbia.
Also to generate ~20% increased daily injection peak (0,5 Mm3/d) and off season	operation.				
EXPECTED BENEFITS					
ENFECTED BENEFITS					
Market integration, Diversification of routes					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




UGS-N-234 Zsana UGS - Decrease of the minimum injection capacity Non-FID


**Storage Facility** 

SPONSORS

# GENERAL INFORMATION



Promoter	E.ON Földgaz
Operator	E.ON Hungary Storage
TEN-E Project ?	Project of Common Interest
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2016 Q1
FID	2015 Q4
Construction	2016 Q3
Commissioning	2016 Q4
Last completed Phase :	Market test

TECHNICAL INFORMATION	
Storage facility	Zsana
Working volume (mcm)	+2.140,00
Injectability (mcm/d)	+17,20
Deliverability (mcm/d)	+28,00



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
UGS - HU - FGSZ/E.ON Hungary	Yes	exit	308,00	Storage Hungary	Hub Hungary
	Yes	entry	189,20	Storage Hungary	Hub Hungary


DESCRIPTION OF THE PROJECT				
Flexible operation down to 0,24 Mm3/d and beyond the existing 17,0 Mm3/d.				
EXPECTED BENEFITS				
Market integration, Diversification of routes				
COMMENTS ABOUT THE PROJECT FINANCING				
Public financing	Private financing	Multilateral financing		




TRA-N-019	Csepel connecting pipeline	Non-FID

### **SPONSORS**

### **GENERAL INFORMATION**



Promoter	FGSZ Natural Gas Transmission
Operator	FGSZ Natural Gas Transmission
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	www.fgsz.hu



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2013 Q4
FID	2013 Q2
Construction	2013 Q4
Commissioning	2014 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+20,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
nterconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
New pipeline to Csepel					
EXPECTED BENEFITS					
Market integration (Budapest region new power plant supply), the Hungarian projects taken as a whole main aim, is to enhance the flexibility of the Hungarian transmission system by connecting to neighbouring systems, ensuring reserves flow availability, and guaranteeing flow deliverability which will enhance the transmission systems security of supply position along with helping with further market integration.					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-N-061	Ercsi-Szazhalombatta	Non-FID
1 KM-14-00T	Li CSI-SZAZIIAIOIIIDALLA	HOII-I ID

### **SPONSORS**

### **GENERAL INFORMATION**



Promoter	FGSZ Natural Gas Transmission
Operator	FGSZ Natural Gas Transmission
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2014 Q1
FID	2013 Q2
Construction	2014 Q1
Commissioning	2016 Q3
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+11,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
New pipeline between Ercsi and Szazhalombatta nodes, DN800 PN63, 11 km					
EXPECTED BENEFITS					
ENTECTED DENETITS					
Security of Supply, Market integration (Security of Supply of Budapest region, New power plant supply at Budapest region, Increase capacity Sk>HU and HU>SK), Reverse Flows, Diversification of sources. The Hungarian projects taken as a whole main aim, is to enhance the flexibility of the Hungarian transmission system by connecting to neighbouring systems, ensuring reserves flow availability, and guaranteeing flow deliverability which will enhance the transmission systems security of supply position along with helping with further market integration.					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing
		Ü			




TRA-N-065	Hajduszoboszlo CS	Non-FID

### **SPONSORS**

### GENERAL INFORMATION



Promoter	FGSZ Natural Gas Transmission
Operator	FGSZ Natural Gas Transmission
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	www.fgsz.hu



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2016 Q3
FID	2016 Q2
Construction	2016 Q3
Commissioning	2018 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	
Total Compressor Power (MW)	+5,70
Maximum Capacity (GWh/d)	
Expected Load Factor	



PROJECTED CAPACITY INCREASES						
nterconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone	
DESCRIPTION OF THE PROJECT						
Equipment replacement						
EXPECTED BENEFITS						
The Hungarian projects taken as a whole main aim, is to enhance the flexibility of the Hungarian transmission system by connecting to neighbouring systems, ensuring reserves flow availability, and guaranteeing flow deliverability which will enhance the transmission systems security of supply position along with helping with further market integration. In particular, this project helps the reverse flow from Varösföld to Beregdaroc.						
COMMENTS ABOUT THE PROJECT FINANCING						
Public financing	Private fina	ancing			Multilateral financing	




### TRA-N-124 Local Odorisation - FGSZ Non-FID


**Pipeline including CS** 

SPONSORS

### GENERAL INFORMATION



Promoter	FGSZ Natural Gas Transmission
Operator	FGSZ Natural Gas Transmission
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	www.fgsz.hu



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2014 Q1
FID	2013 Q2
Construction	2014 Q1
Commissioning	2015 Q3
Last completed Phase :	Permitting

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	
Total Pipeline Length (km)	
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
The Hungarian projects taken as a whole main aim, is to enhance the flexibility o will enhance the transmission systems security of supply position along with helpi	f the Hungar ng with furth	ian transmissi er market inte	ion system by connecting t egration.	o neighbouring systems, ensu	uring reserves flow availability, and guaranteeing flow deliverability which
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-N-286 Romanian-Hungarian reverse flow Hungarian section Non-FID


**Pipeline including CS** 

SPONSORS

### GENERAL INFORMATION



Promoter	FGSZ Natural Gas Transmission
Operator	FGSZ Natural Gas Transmission
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2014 Q1
FID	2013 Q2
Construction	2014 Q1
Commissioning	2015 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	3
Total Pipeline Length (km)	
Total Compressor Power (MW)	+13,50
Maximum Capacity (GWh/d)	+127,40
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Csanadpalota	No	entry	50,90	Hub Romania	Hub Hungary
	Yes	entry	12,60	Hub Romania	Hub Hungary
Csanadpalota	No	entry	127,40	Hub Romania	Hub Hungary


DESCRIPTION OF THE PROJECT			
New compressor station at Csanádpalota.			
EXPECTED BENEFITS			
Security of Supply, Market integration (RO and HU markets), Reverse Flows, Diversification of sources, Diversification of routes, N-1 National			
COMMENTS ABOUT THE PROJECT FINANCING			
Public financing	Private financing	Multilateral financing	




TRA-N-123	Városföld CS	Non-FID
IIVA II IZS	Talosiola Co	INOIL LED

### **SPONSORS**

### GENERAL INFORMATION



Promoter	FGSZ Natural Gas Transmission
Operator	FGSZ Natural Gas Transmission
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	www.fgsz.hu



THIRD-PARTY ACCESS REGIME		
Considered TPA Regime	Regulated	
Considered Tariff Regime	Regulated	
Applied for Exemption ?	No	
Exemption granted ?	No	
% Exemption in entry direction	0%	
% Exemption in exit direction	0%	

SCHEDULE	
End of permitting phase	2014 Q1
FID	2013 Q3
Construction	2014 Q1
Commissioning	2016 Q3
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	
Total Compressor Power (MW)	+5,70
Maximum Capacity (GWh/d)	
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
Compressor station extension, 5,7 MW					
EXPECTED BENEFITS					
o The Hungarian projects taken as a whole main aim, is to enhance the flexibility will enhance the transmission systems security of supply position along with helpi	of the Hunga ng with furth	rian transmis er market int	sion system by connecting egration.	to neighbouring systems, ens	uring reserves flow availability, and guaranteeing flow deliverability which
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




### TRA-N-018 Városföld-Ercsi-Győr Non-FID


**Pipeline including CS** 

SPONSORS

### GENERAL INFORMATION



Promoter	FGSZ Natural Gas Transmission
Operator	FGSZ Natural Gas Transmission
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	www.fgsz.hu



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2016 Q3
FID	2013 Q2
Construction	2014 Q1
Commissioning	2015 Q3
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+220,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
Pipeline between Városföld-Ercsi and Győr nodes, DN1000, PN100, 220 km. Mosonmagyarovar interconnection point to realize reverse flow capacity up to				nnection point to reach its fu	ll capacity of 153 GWh/d from Austria to Hungary.It will also enable the
EXPECTED BENEFITS					
Security of Supply, Market integration (Increase AT/HU border capacity, Secur Diversification of sources, o The Hungarian projects taken as a whole main aim flow deliverability which will enhance the transmission systems security of sup	, is to enhance	the flexibility of	of the Hungarian transmiss	ion system by connecting to n	
COMMENTS ABOUT THE PROJECT FINANCING					
	Dubunta Gua				Baulathannal Commission
Public financing	Private fina	incing			Multilateral financing




TRA-F-195	AGRI Pipeline - Hungarian section	FID
Pineline including CS		

SPONSORS

### GENERAL INFORMATION



Promoter	Magyar Gaz Tranzit Zrt.
Operator	MGT Hungarian Gas Transit Ltd.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	1
Web Link	



THIRD-PARTY ACCESS REGIME		SCHEDULE		TECHNICAL INFORMATION	
Considered TPA Regime	0	End of permitting phase		# of Pipelines, nodes, CS	1
Considered Tariff Regime	0	FID		Total Pipeline Length (km)	
Applied for Exemption ?	No	Construction		Total Compressor Power (MW)	
Exemption granted ?	no	Commissioning	2022*	Maximum Capacity (GWh/d)	
% Exemption in entry direction	0%	Last completed Phase :		Expected Load Factor	
% Exemption in exit direction	0%				



ROJECTED CAPACITY INCREASES					
terconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
st-West Pipeline RO-HU (AGRI)	No	entry	0,00	Hub Romania	Hub Hungary


DESCRIPTION OF THE PROJECT		
The project is in feassibility phase		
EXPECTED BENEFITS		
COMMENTS ABOUT THE PROJECT FINANCING		
Public financing	Private financing	Multilateral financing




TRA-F-016	Slovakia - Hungary interconnection	FID
nt a di cari a di care e e e		

SPONSORS

### GENERAL INFORMATION



Promoter	eustream, a.s.
Operator	eustream, a.s.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	1
Web Link	www.eustream.sk/en_transmission-system/en_sk-hu- interconnector



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2012 Q1
FID	2010 Q1
Construction	2014 Q2
Commissioning	2014 Q4
Last completed Phase :	Supply contract

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+115,00
Total Compressor Power (MW)	+7,00
Maximum Capacity (GWh/d)	+127,40
Expected Load Factor	80,00%



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Balassagyarmat	Yes	entry	50,90	Hub Hungary	Hub Slovakia
	Yes	exit	127,40	Hub Slovakia	Hub Hungary


DESCRIPTION OF THE PROJECT				
Creation of a missing interconnection between SK and HU and thus increase the SoS in CEE region, and enhance market integration and functionality.				
EXPECTED BENEFITS				
Security of Supply, Market integration (CEE region), Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (Slovakia, Hungary), N-1 Regional (CEE region), Back-up for renewables, Power-to-gas				
COMMENTS ABOUT THE PROJECT FINANCING				
Public financing	Private financing	Multilateral financing		
Interconnector Slovakia – Hungary: EEPR: € 3.3 mil.	eustream, a.s.			




TRA-F-196	South Stream Hungary	FID

### SPONSORS

### GENERAL INFORMATION



Promoter	Magyar Gaz Tranzit Zrt.
Operator	MGT Hungarian Gas Transit Ltd.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	1
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	0
Considered Tariff Regime	0
Applied for Exemption ?	0
Exemption granted ?	0
% Exemption in entry direction	50%
% Exemption in exit direction	45%

SCHEDULE	
End of permitting phase	2015
FID	
Construction	2014
Commissioning	2015 Q1
Last completed Phase :	

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+220,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
South Stream (Bata, Nagykanizsa) (HU)	Yes	entry	224,00	Interconnector South Stream	Hub Hungary

DESCRIPTION OF THE PROJECT		
Hungarian section 220 km. DN1400/1200, Pn 90 bar.		
EXPECTED BENEFITS		
COMMENTS ABOUT THE PROJECT FINANCING		
Public financing	Private financing	Multilateral financing

### Ireland









TRA-N-059	Physical Reverse Flow at Moffat Interconnection Point	Non-FID

**SPONSORS** 

### GENERAL INFORMATION



Promoter	Gaslink
Operator	Gaslink
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2017
Last completed Phase :	Market test

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+37,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+38,50
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Moffat	Yes	exit	38,50	Hub Ireland	Hub United Kingdom
DESCRIPTION OF THE PROJECT					
The interconnection point at Moffat is currently uni-directional with gas flow fron	n UK to Irelan	d. This projec	t would be to make the M	offat interconnection point bi-c	lirectional.
EXPECTED BENEFITS					
Security of Supply, Market integration (Ireland & UK; Ireland & Northern ireland available in Ireland and Northern Ireland from 2017 onwards and there may be participation by Irish shippers in the UK market facilitates closer linkage to the European Control of the European Control of Supplementary (Ireland & UK; Ireland & Northern ireland available in Ireland & UK; Ireland & Northern ireland available in Ireland & UK; Ireland & Northern ireland available in Ireland & UK; Ireland & Northern ireland available in Ireland & UK; Ireland & Northern ireland available in Ireland & UK; Ireland & Northern ireland available in Ireland & Ir	e an over su	pply for expo	ortation to the UK. In orde	er to enable the physical expo	
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-N-071	Physical Reverse Flow on South North Pipeline	Non-FID
Pipeline including CS		

GENERAL INFORMATION

Gaslink (100%)

**SPONSORS** 

# Promoter Gaslink Operator Gaslink TEN-E Project ? Not part of TEN-E Interested by PCI ? Yes IGAs None Web Link



THIRD-PARTY ACCESS REGIME		SCHEDULE		TECHNICAL INFORMATION	
Considered TPA Regime	Regulated	End of permitting phase		# of Pipelines, nodes, CS	1
Considered Tariff Regime	Regulated	FID		Total Pipeline Length (km)	
Applied for Exemption ?	No	Construction		Total Compressor Power (MW)	
Exemption granted ?	Not relevant	Commissioning	2017	Maximum Capacity (GWh/d)	+27,60
% Exemption in entry direction	0%	Last completed Phase :	Market test	Expected Load Factor	
% Exemption in exit direction	0%				




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Gormanston	Yes	entry	27,60	<b>Hub United Kingdom</b>	Hub Ireland
DESCRIPTION OF THE PROJECT					
Currently gas flow between Ireland & Dorthern Ireland via the South North I	Pipeline is uni-	-directional (a	at the Gormanston Interco	nnection Point)	
EXPECTED BENEFITS					
Security of Supply, Market integration (Northern Ireland), Reverse Flows, Diver integrated market on the island of ireland, having significant importance in the participants.3 Contributes to the viability of LNG and storage projects.					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing		N	Aultilateral financing




TRA-N-060	Twinning of South West Scotland Onshore System	Non-FID

**SPONSORS** 

### GENERAL INFORMATION



Promoter	Gaslink
Operator	Gaslink
TEN-E Project ?	Project of Common Interest
Interested by PCI ?	Not defined yet
IGAs	2
Web Link	



THIRD-PARTY ACCESS REGIME		SCHEDULE
Considered TPA Regime	Regulated	End of permitting ph
Considered Tariff Regime	Regulated	FID
Applied for Exemption ?	No	Construction
Exemption granted ?	Not relevant	Commissioning
% Exemption in entry direction	0%	Last completed Phase
% Exemption in exit direction	0%	

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2015 Q1
Last completed Phase :	Market test


TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+50,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+375,00
Expected Load Factor	86,00%



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Moffat	No	entry	0,00	<b>Hub United Kingdom</b>	Hub Ireland
DESCRIPTION OF THE PROJECT					
Twinning a 50km section of pipeline between Cluden and Brighouse Bay in South	West Scotlan	d.			
EXPECTED BENEFITS					
Security of Supply, Market integration (Increases interoperability between Ireland (Ireland, Northern Ireland & UK), Biogas, 1.Reinforcing the 50km single section of long term.2 Ireland is on the Western peripheral of Europe and is quite isolated remove a capacity 'bottleneck' on the Interconnection System; this will increase t	f the SWSOS from mainlar	transmission nd Europe. Ire	system guarantees the supeland would greatly benefi	oply capacity and the security t t from any infrastructure that v	o meet Ireland's future demand requirements in the short, medium and would further connect Ireland to the gas system in the UK. It would also
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing



UGS-N-197	Southwest Kinsale Storage Expansion Project		Non-FID
Storage Facility			
SPONSORS	GENERAL INFORMATION	FINANCING	



Promoter	Kinsale Energy Ltd
Operator	Kinsale Energy Ltd
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	www.kinsale-energy.ie



THIRD-PARTY ACCESS REGIME		SCHEDULE		TECHNICAL INFORMATION	
Considered TPA Regime	Negotiated (e.g. Exemption)	End of permitting phase	2014 Q4	Storage facility	Southwest Kinsale Gas Storage Expansion
Considered Tariff Regime	Negotiated (e.g. Exemption)	FID	2013 Q4	Working volume (mcm)	+174,00
Applied for Exemption ?	Not yet	Construction	2015 Q2	Injectability (mcm/d)	+2,80
Exemption granted ?	Not yet	Commissioning	2015 Q3	Deliverability (mcm/d)	+3,70
% Exemption in entry direction	85%	Last completed Phase :	Planned		
% Exemption in exit direction	100%				



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Kinsale Southwest	Yes	entry	30,80	Hub Ireland	Storage Ireland
	Yes	exit	40,70	Hub Ireland	Storage Ireland
DESCRIPTION OF THE PROJECT					
The project involves the expansion of the existing Southwest Kinsale storage facil	ity from 226m	ncm to 400mc	m through the drilling of a	new well (s) and process equi	pment modifications to provide additional injection / withdrawal capacity
EXPECTED BENEFITS					
Security of Supply, Market integration, Diversification of sources, N-1 National (Ir	eland), Back-ι	up for renewal	oles		
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing

PROJECTED CAPACITY INCREASES




### LNG-N-030 Shannon LNG Terminal Non-FID


### **LNG Terminal**

### **SPONSORS**

### GENERAL INFORMATION



Promoter	Shannon LNG
Operator	Shannon LNG
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	www.shannonIngplanning.ie



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	Yes
Exemption granted ?	Yes
% Exemption in entry direction	100%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2013
FID	2013
Construction	2017
Commissioning	2017
Last completed Phase :	Market test

TECHNICAL INFORMATION	
Regasification facility	Shannon LNG Limited
Expected volume (bcm/y)	+3,00
Storage capacity (m3)	+200.000,00
Send-out (mcm/d)	+10,70
Ship size (m3)	265.000,00
Reloading ability ?	No



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Shannon LNG	Yes	exit	117,70	LNG Terminals Ireland	Hub Ireland

### **DESCRIPTION OF THE PROJECT**

Shannon LNG has obtained all of the major permits and consents for the LNG project including planning permission for the terminal and export pipeline, pipeline rights of way and foreshore leases and licenses.

The Shannon LNG terminal is designed and permitted to export to the national gas grid up to 26.8 million normal cubic metres per day of natural gas. It is currently envisaged the project will have initial deliverability of 10.7 normal million cubic metres per day.

### **EXPECTED BENEFITS**

Security of Supply, Market integration, Diversification of sources, Diversification of routes, N-1 National (Ireland), Back-up for renewables, The Shannon LNG project will increase Ireland security of gas supply. Ireland imports over 90% of its gas via two pipelines from Scotland. Ireland is unable to meet its N-1 Infrastructure requirements under Regulation (EU) No 994/2010 (CER Consultation Paper "Draft National Preventive Action Plan – Gas 2012-2014 Ireland" (CER/12/088)). The initial phase of the Shannon LNG project will be capable of supplying approximatly 40% of forecast Irish peak demand for 2019/2020 (Calculated using 1 in 50 Winter Peak Day Demand & Base Supply Scenario forecast, Gaslink 2011 Joint Gas Capacity Statement). The proposed LNG terminal will increase market integration and system flexibility by providing a new gas supply route to Ireland. The project supports emmission reductions and will enhance Irelands long-term security of supply resiliance by providing an entirely new supply source for Ireland with LNG imported from geographies that may include Africa, Middle East, North America, Russia etc

## COMMENTS ABOUT THE PROJECT FINANCING Public financing Private financing Multilateral financing










LNG-N-085

api nòva energia S.r.l. – LNG off-shore regasification terminal of Falconara Marittima (Ancona, Italy)

Non-FID


### **LNG Terminal**

### **SPONSORS**



### GENERAL INFORMATION

Promoter	API Nova	API Nova Energia S.r.I.		
Operator	API Nova	API Nova Energia S.r.l.		
TEN-E Project ?	Project of Co	ommon Interest		
Interested by PCI ?		Yes		
IGAs	N	None		
Web Link	apinovaenergia.gruppoapi.co	om/Gas-Power/Terminale-GNL/		
TEN-E Requests	Date of Request 24/04/09	Year Funding Granted 2010		
	28/02/11	Not yet		



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	Yes
Exemption granted ?	Not yet
% Exemption in entry direction	100%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2012 Q1
FID	2013 Q3
Construction	2014 Q2
Commissioning	2016 Q1
Last completed Phase :	Permitting

TECHNICAL INFORMATION	
Regasification facility	apı nova energia S.r.i. – LNG OTT-SNOTE
Expected volume (bcm/y)	+4,00
Storage capacity (m3)	+150.000,00
Send-out (mcm/d)	+25,90
Ship size (m3)	150.000,00
Reloading ability ?	No



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Falconara Marittima	Yes	exit	284,90	LNG Terminals Italia	Hub Italia
DESCRIPTION OF THE PROJECT					
The project envisages the utilization of an off-shore mooring structure, Single Point Mooring type, located 16 km off the coast and currently used for the crude oil discharge for the Falconara Marittima refinery, to be adapted in order to allow also the mooring of Floating Storage Regasification Unit (FSRU) vessels and the discharge of regasified natural gas in the national gas network through a new off-shore and on-shore 20 km long connection pipeline, and one or more FSRU vessels for the onboard regasification of LNG and the discharge through the SPM of regasified natural gas. Regasification operations shall be performed directly onboard the FSRU vessels, that shall load LNG either from liquefaction plants abroad or via transhipment from LNG carriers away from the SPM. No on-shore fixed LNG storage facilities shall be installed: the regasified gas shall be transported to the coast through a new submarine pipeline and shall then be redirected to a regulation and metering station for the connection with the existing national transport network, located close to the landing point.					
EXPECTED BENEFITS					
Security of Supply, Market integration, Reverse Flows, Diversification of sources, Diversification of routes, N-1 National, N-1 Regional					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




LNG-N-011	Brindisi LNG	Non-FID


### **LNG Terminal**

### **SPONSORS**

### GENERAL INFORMATION



Promoter	BG Group
Operator	BG Group
TEN-E Project ?	Priority Project
Interested by PCI ?	Yes
IGAs	None
Web Link	www.brindisiIng.it



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	Yes
Exemption granted ?	Yes
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2013 Q4
FID	2014
Construction	
Commissioning	2017 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
TECHNICAL INFORMATION	
Regasification facility	
Expected volume (bcm/y)	+8,00
Storage capacity (m3)	+320.000,00
Send-out (mcm/d)	+25,00
Ship size (m3)	
Reloading ability ?	No



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Brindisi	Yes	exit	275,00	LNG Terminals Italia	Hub Italia

DESCRIPTION OF THE PROJECT				
EXPECTED BENEFITS				
Security of Supply, Market integration, Diversification of sources: gas for the Project is intended to be sourced from BG's LNG supply portfolio. The Project should therefore increase the number of supply sources to the Italian market and reduce the EU's dependence on a few large suppliers (Russia and Algeria). This will enhance the security of supply not only to Italy but also to the Southern European region. The development of the Brindisi LNG project will provide an alternative mechanism to pipelines at a national and European level for the transportation of gas into the EU. The investment in the Terminal will also support wider infrastructure enhancement in the SNAM Rete Gas national transportation network.  Market Integration (Increase of competition): The project will allow the entry of new operators into the Italian wholesale gas market and will provide the power generators, industrial users and the retail gas market with important alternative sources to the incumbent gas wholesaler. The project will therefore promote competition in both the wholesale and retail markets, whilst constituting an important investment in Italian gas infrastructure.				
COMMENTS ABOUT THE PROJECT FINANCING				
Public financing	Private financing	Multilateral financing		



# TRA-N-012 GALSI Pipeline Non-FID

### **Pipeline including CS**


### SPONSORS

# Hera Trading Srl (10%) Edison SpA (21%) Ejel Produzione Spa (15%) Sfirs Spa (12%)

### GENERAL INFORMATION

Promoter	Edison
Operator	Galsi S.p.A.
TEN-E Project ?	Project of European Interest
Interested by PCI ?	Yes
IGAs	1
Web Link	www.galsi.it





THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	Not relevant
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2012 Q4
FID	2012 Q4
Construction	2016 Q4
Commissioning	2016 Q3
Last completed Phase :	FEED

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	3
Total Pipeline Length (km)	+861,00
Total Compressor Power (MW)	+151,00
Maximum Capacity (GWh/d)	+258,20
Expected Load Factor	90,00%



### PROJECTED CAPACITY INCREASES

Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Olbia (Galsi)	Yes	entry	244,00		Interconnector GALSI
Algerian Coast (Galsi)	Yes	entry	244,00	Supplier Algeria	Interconnector GALSI
Porto Botte (Galsi)	Yes	exit	244,00	Interconnector GALSI	
Olbia (Galsi)	Yes	exit	30,50	Hub Italia	
Piombino (Galsi)	Yes	exit	244,00	Interconnector GALSI	Hub Italia

### **DESCRIPTION OF THE PROJECT**

Gas pipeline project aiming to create a new link between Algeria and Italy via Sardinia

### **EXPECTED BENEFITS**

Security of Supply, Reverse Flows, Diversification of sources, Diversification of routes (the Galsi project will improve security of supply in Italy and Europe, providing for a new and more efficient route for Algerian gas to reach the centre of Italian gas consumption (located in northern Italy) and further on the Northern European markets; in the longer term, with the development of new projects interconnecting different gas sources in Africa (e.g. new Algerian shale gas or TSGP project for Nigerian gas), the Galsi pipeline could provide a highly strategic diversification of gas supply routes to European markets and their supply flexibility; the project will contribute to the creation of an Italian gas hub for gas supply to Europe which, through the increase of gas liquidity, will enable the export of major gas volumes from Italy to other European markets through the development of reverse flow capacities)

Market integration (the Galsi project represents an unique opportunity to bring natural gas to the island of Sardinia currently not connected to the Italian gas network; similar benefits could potentially be further extended to Corsica, through the Cyrénéé project, improving thereby cohesion within Europe and the already excellent relations between Italy and France; in addition, new entrants will be able to develop and/or consolidate their market positions in the Italian gas market through an independent infrastructure)

N-1 National (on the basis of the "Transportation Capacity Multi-Annual" as published by Snam Rete Gas, in the year of commissioning of Galsi project, the largest gas supply infrastructure to Italy – in terms of transportation capacity – will be the Trans Austrian Gas pipeline (TAG) with a firm capacity of 107 mSm3/day at the entry point of Tarvisio; in the event of disruption on the TAG pipeline, additional capacities could be made available by maximizing the gas flow in the Galsi pipeline to an extent that will depend upon the then prevailing operating conditions)

Back-up for renewables (a significant quota of electricity generation in Italy (approx. 50% today) is represented by CCGTs whose utilization is increasingly shifting towards a back-up of RES, in the light of their dramatic increase witnessed in these last years)

Reduction of GHG emissions (the Galsi project complies with sustainable development guidelines, i.e. the promotion of the substitution of high pollutant fossil fuels with a low pollutant such as natural gas, the improvement of efficiency in the electricity production by switching from other fossil fuels to natural gas, and the penetration of the use of natural gas in industrial/residential and tertiary sector)

Power-to-gas, Biogas

### COMMENTS ABOUT THE PROJECT FINANCING


Public financing	Private financing	Multilateral financing




UGS-N-235	Nuovi Sviluppi Edison Stoccaggio	Non-FID

### **SPONSORS**

### GENERAL INFORMATION



Promoter	Edison Stoccagio S.p.A.
Operator	Edison Stoccagio S.p.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2016 Q1
Last completed Phase :	Planned

TECHNICAL INFORMATION	
Storage facility	
Working volume (mcm)	+1.000,00
Injectability (mcm/d)	+10,00
Deliverability (mcm/d)	+10,00



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
UGS - IT - Snam Rete Gas/Edison	Yes	exit	110,00	Storage Italia	Hub Italia
	Yes	entry	110,00	Hub Italia	Storage Italia


DESCRIPTION OF THE PROJECT				
EXPECTED BENEFITS				
Security of Supply, Market integration, o SoS and Market Integration (Increase of competition): The Italian Storage facilities is a market characterized by absence of a different operators, low level of development new storage capacity by the major operator (with the 97% market share). Our projects will enhance the level of competition and security of supply at national level.				
COMMENTS ABOUT THE PROJECT FINANCING				
Public financing	Private financing	Multilateral financing		




UGS-N-237	Palazzo Moroni	Non-FID

### **SPONSORS**

### GENERAL INFORMATION



Promoter	Edison Stoccagio S.p.A.
Operator	Edison Stoccagio S.p.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2014 Q2
Last completed Phase :	FEED

TECHNICAL INFORMATION	
Storage facility	
Working volume (mcm)	+66,00
Injectability (mcm/d)	+1,00
Deliverability (mcm/d)	+1,00



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
UGS - IT - Snam Rete Gas/Edison	Yes	exit	11,00	Storage Italia	Hub Italia
	Yes	entry	11,00	Hub Italia	Storage Italia

DESCRIPTION OF THE PROJECT				
EXPECTED BENEFITS				
Security of Supply, Market integration (Increase of competition): The Italian Storage facilities is a market characterized by absence of a different operators, low level of development new storage capacity by the major operator (with the 97% market share). Our projects will enhance the level of competition and security of supply at national level.				
COMMENTS ABOUT THE PROJECT FINANCING				
Public financing	Private financing	Multilateral financing		




UGS-F-236	San Potito e Cotignola	FID

### **SPONSORS**

# Edison Stoccaggio S.p.A. (90%)

### GENERAL INFORMATION

Promoter	Edison Stoccagio S.p.A.
Operator	Edison Stoccagio S.p.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2029 Q2
FID	2006 Q3
Construction	
Commissioning	2013 Q2
Last completed Phase :	FID

TECHNICAL INFORMATION	
Storage facility	
Working volume (mcm)	+868,00
Injectability (mcm/d)	+6,80
Deliverability (mcm/d)	+6,80



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
UGS - IT - Snam Rete Gas/Edison	Yes	exit	74,80	Storage Italia	Hub Italia
	Yes	entry	74,80	Hub Italia	Storage Italia

DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Market integration, o SoS and Market Integration (Increase of competition): The Italian Storage facilities is a market characterized by absence of a different operators, low level of development new storage capacity by the major operator (with the 97% market share). Our projects will enhance the level of competition and security of supply at national level.					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private financing	Multilateral financing			




LNG-N-217	Zaule - LNG Terminal in Trieste (Italy)	Non-FID


### **LNG Terminal**

### **SPONSORS**

### **GENERAL INFORMATION**



Promoter	Gas Natural Rigassificazione Italia
Operator	gasNatural Rigassificazione S.p.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	www.rigassificatoretrieste.gasnatural.com/it/128508535707 4/inizio.html



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	Not yet
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2013 Q2
FID	2014
Construction	2015 Q1
Commissioning	2018
Last completed Phase :	FEED

TECHNICAL INFORMATION	
Regasification facility	Zaule LNG Terminal (Trieste - Italy)
Expected volume (bcm/y)	+8,00
Storage capacity (m3)	+280.000,00
Send-out (mcm/d)	+24,00
Ship size (m3)	145.000,00
Reloading ability ?	No



PROJECTED CAPACITY INCREASES						
Interconnection	Modelled	Direction	Capacity	(GWh/d)	From Zone	To Zone
Zaule LNG (Trieste)	Yes	exit		264,00	LNG Terminals Italia	Hub Italia
DESCRIPTION OF THE PROJECT						
Onshore regasification terminal with 8 bcm/y capacity. Storage capacity: 2 x 140.000 m3; Send-out capacity: 1.075.000 m3(s)/hour. Single jetty and maximum vessel size of 145.000 m3.						
EXPECTED BENEFITS						
Security of Supply, Market integration (Italy and North and Central Europe), Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (Italy), N-1 Regional (Region South - North), Back-up for renewables, Power-to-gas, Decontamination of part of Trieste Industrial Harbour. Boost in economic activity in the city, province and region.						
COMMENTS ABOUT THE PROJECT FINANCING						
Public financing	Private fina	ncing				Multilateral financing




LNG-N-216	Panigaglia LNG	Non-FID
LI10-I1-210	ranigagna Livo	HOII-I ID


### **LNG Terminal**

### **SPONSORS**

### GENERAL INFORMATION



Promoter	GNL Italia
Operator	GNL Italia
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	www.gnlitalia.it/en/activities/Innovation-and- research/modernisation-project.html



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2022*
Last completed Phase :	Planned

TECHNICAL INFORMATION	
Regasification facility	Panigaglia LNG
Expected volume (bcm/y)	+8,00
Storage capacity (m3)	+240.000,00
Send-out (mcm/d)	+13,00
Ship size (m3)	140.000,00
Reloading ability ?	No



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Panigaglia	Yes	exit	153,00	LNG Terminals Italia	Hub Italia
DESCRIPTION OF THE PROJECT					
Expansion Project under consideration					
EXPECTED BENEFITS					
EAFECTED BENEFITS					
Security of Supply, Diversification of sources, N-1 National, Back-up for renewable	20				
Extension of transport capacity of Russian gas to the West, Integration of Nord St	ream off- and	on-Shore in	the European gas infrastru	cture	
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing

PROJECTED CAPACITY INCREASES




# UGS-N-242 Cornegliano UGS Non-FID


### **Storage Facility**

### SPONSORS

### GENERAL INFORMATION



Promoter	ITAL Gas Storage S.r.l.
Operator	ITAL Gas Storage S.r.l.
TEN-E Project ?	Project of European Interest
Interested by PCI ?	Yes
IGAs	None
Web Link	www.italgasstorage.it



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2011 Q1
FID	2012 Q4
Construction	2012 Q4
Commissioning	2015 Q1
Last completed Phase :	Permitting

TECHNICAL INFORMATION	
Storage facility	Cornegliano UGS
Working volume (mcm)	+1.300,00
Injectability (mcm/d)	+27,00
Deliverability (mcm/d)	+27,00




PROJECTED CAPACITY INCREASES						
Interconnection	Modelled	Direction	Capacity	(GWh/d)	From Zone	To Zone
Cornegliano	Yes	entry		297,00	Storage Italia	Storage Italia
	Yes	exit		297,00	Storage Italia	Hub Italia
DESCRIPTION OF THE PROJECT						
Ital Gas Storage will construct a new gas storage facility located in Lombardy (Ita the facility will be 27 million cubic meters per day (+10% of actual capacity). To commence from Q4 2014/Q1 2015.						
EXPECTED BENEFITS						
Security of Supply, Market integration (Italy, South Europe, Central Europe), Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (Italy), N-1 Regional (West), Back-up for renewables, Cornegliano UGS will contribute to the development of reverse gas flow from South Europe to Central Europe and North Europe by providing shippers with an important source of flexibility and gas modulation at relatively low cost (the national tariff in Italy is the lowest among Europe).						
COMMENTS ABOUT THE PROJECT FINANCING						
Public financing	Private fina	ncing				Multilateral financing



# LNG-N-198 Porto Empedocle LNG Non-FID

### **LNG Terminal**


### SPONSORS



### GENERAL INFORMATION

Promoter	Nuove Energie S.r.l.
Operator	Nuove Energie S.r.l.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	www.enel.it/it-IT/eventi_news/news/terminale-di- rigassificazione-di-porto-empedocle/p/090027d9819310b8





THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	Yes
Exemption granted ?	Yes
% Exemption in entry direction	100%
% Exemption in exit direction	100%

SCHEDULE	
End of permitting phase	2011 Q3
FID	2013
Construction	
Commissioning	2017 Q2
Last completed Phase :	Permitting

TECHNICAL INFORMATION	
Regasification facility	Porto Empedocle LNG
Expected volume (bcm/y)	+8,00
Storage capacity (m3)	+320.000,00
Send-out (mcm/d)	+23,10
Ship size (m3)	155.000,00
Reloading ability ?	No




PROJECTED CAPACITY INCREASES						
Interconnection	Modelled	Direction	Capacity (	(GWh/d)	From Zone	To Zone
Porto Empedocle LNG	Yes	exit		254,10	LNG Terminals Italia	LNG Terminals Italia
DESCRIPTION OF THE PROJECT						
The planned Porto Empedocie Livo Terminal will be located in Italy, in the Sicily K	egion, cadasti	rai area oi Po	по Етреао	cie, for which th	e promoter received a thirty-	/ear concession. It will consist or:
– two underground storage tanks of 160.000 of m <sup>3</sup> of capacity each,						
– vaporiser pumps and other treatment facilities required to process LNG and						
– a breakwater with mooring jetty and unloading arms.						
The ING Terminal will be able to inject the case at the standard crid process (around 70 bar) and will be connected to the transmission system operated by SpamBateGas by means of a pineline section specifically built by SpamBateGas						
EXPECTED BENEFITS						
Security of Supply, Market integration, Diversification of sources, Diversification of	of routes, The	LNG termina	l will provide	e some storage o	capacity within its tanks, allow	ring to provide flexibility to the system in an area where gas storage is not
currently present.						
COMMENTS ABOUT THE PROJECT FINANCING						
Public financing	Private fina	ncing				Multilateral financing






### **LNG Terminal**

# SPONSORS



### GENERAL INFORMATION

Promoter	OLT Offshore LNG Toscana S.p.A
Operator	OLT Offshore LNG Toscana S.p.A
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	www.oltoffshore.it/



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	Yes
Exemption granted ?	Yes
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2013 Q2
FID	2008 Q1
Construction	2012 Q4
Commissioning	2013 Q2
Last completed Phase :	FID

TECHNICAL INFORMATION	
Regasification facility	FSRU Toscana
Expected volume (bcm/y)	+3,75
Storage capacity (m3)	+137.500,00
Send-out (mcm/d)	+11,00
Ship size (m3)	138.000,00
Reloading ability ?	Yes




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
FSRU Toscana	Yes	exit	121,00	LNG Terminals Italia	Hub Italia
DESCRIPTION OF THE PROJECT					
The OLT Offshore LNG Toscana project provides for the conversion of an LNG				ication unit (FSRU) permanent	ly anchored about 22 km offshore Tuscany coast. The FSRU is directly
connected with the national gas grid throught a 29 km subsea pipeline and 7 km i	n land pipelin	ie already buil	It by Snam Rete Gas.		
EXPECTED BENEFITS					
Security of Supply, Market integration, Reverse Flows, Diversification of sources,	Diversification	n of routes			
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-N-007	Adriatica and Tirrenica pipelines	Non-FID

**SPONSORS** 

### GENERAL INFORMATION



Promoter	Snam Rete Gas S.p.A.
Operator	Snam Rete Gas S.p.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	www.snamretegas.it/export/sites/snamretegas/repository/file/ENG/Thermal_Year_20112012/Information_for_User/Capacity_plans/Capacity_and_development_Plan_2011_2012.pdf



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2022*
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	3
Total Pipeline Length (km)	+1.130,00
Total Compressor Power (MW)	+168,00
Maximum Capacity (GWh/d)	+264,00
Expected Load Factor	65,00%




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
	No	entry	264,00		Hub Italia
DESCRIPTION OF THE PROJECT					
The project consists in new on-shore and off-shore pipelines and in new compres	sor stations a	ong the cente	er-south of Italy to permit th	he increase of transport capa	city at new or existing Entry Points in south Italy
The project consists in term of shore and on shore pipelines and in term complete		oge ee	or south or really to permit to	ne moreuse or transport cupa.	any action of entang line y contains an action tell
EXPECTED BENEFITS					
Security of Supply, Diversification of sources, Diversification of routes, N-1 Nation	al (Italy), Bacl	c-up for renev	vables, Power-to-gas, Mark	et Integration (Increase of co	mpetition), Flexibility of the system
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-F-214	Cross Border Bi-directional Flows - Phase 2	FID

### **SPONSORS**

### GENERAL INFORMATION



Promoter	Snam Rete Gas S.p.A.
Operator	Snam Rete Gas S.p.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	www.snamretegas.it/export/sites/snamretegas/repository/fi le/ENG/Thermal_Year_20112012/Information_for_User/Cap acity_plans/Capacity_and_development_Plan_2011_2012.pd f



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2016 Q4
Last completed Phase :	FID

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+80,00
Total Compressor Power (MW)	+95,00
Maximum Capacity (GWh/d)	+375,00
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Griespass (CH) / Passo Gries (IT)	Yes	exit	375,00	Hub Italia	Hub Switzerland
DESCRIPTION OF THE PROJECT					
The project consists in new on-shore pipelines and new compressor stations in th	e north of Ita	ly and it perm	its to increase the physical	reverse flow capacity available v	with the phase 1
EXPECTED BENEFITS					
Security of Supply, Reverse Flows, Diversification of routes, Back-up for renewable	es, Power-to-	gas, Market Ir	ntegration (Increase of com	petition), N-1 Regional, Flexibilit	ry of the system, reducing of GHG emissions
COMMENTS ABOUT THE PROJECT FINANCING					
	Drivata fire	noina			Autilatoral financing
Public financing	Private fina	ncing		N	Aultilateral financing




TRA-F-213	Cross Border Bi-directional Flows - Phase 1	FID

### **SPONSORS**

### **GENERAL INFORMATION**



Promoter	Snam Rete Gas S.p.A.
Operator	Snam Rete Gas S.p.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	www.snamretegas.it/export/sites/snamretegas/repository/fi le/ENG/Thermal_Year_20112012/information_for_User/Cap acity_plans/Capacity_and_development_Plan_2011_2012.pd f



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2015 Q4
Last completed Phase :	Permitting

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+370,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+54,00
Expected Load Factor	



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Griespass (CH) / Passo Gries (IT)	Yes	exit	54,00	Hub Italia	Hub Switzerland
onespass (enj.) i asse ones (ii)		Cate	5-1,00		
DESCRIPTION OF THE PROJECT					
The project consists in new on-shore pipelines in the north of Italy and it permits	to make availi	able a new se	rvice of physical reverse flo	ow capacity	
EXPECTED BENEFITS					
Security of Supply, Reverse Flows, Diversification of routes, Back-up for renewables, Power-to-gas, Market Integration (Increase of competition), N-1 Regional, Flexibility of the system, reducing of GHG emissions					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing


PROJECTED CAPACITY INCREASES




TRA-N-008	Development in North East Italy	Non-FID

### **SPONSORS**

### **GENERAL INFORMATION**



Promoter	Snam Rete Gas S.p.A.
Operator	Snam Rete Gas S.p.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	www.snamretegas.it/export/sites/snamretegas/repository/fi le/ENG/Thermal_Year_20112012/Information_for_User/Cap acity_plans/Capacity_and_development_Plan_2011_2012.pd f



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2022*
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+120,00
Total Compressor Power (MW)	+100,00
Maximum Capacity (GWh/d)	+350,00
Expected Load Factor	65,00%




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
	No	entry	350,00		Hub Italia
DESCRIPTION OF THE PROJECT					
The project consists in new on-shore pipelines and in a new compressor station in	n the north ea	st of Italy to p	permit the increase of trans	port capacity at new or existing	g Entry Points in that area
EXPECTED BENEFITS					
EXPECTED BENEFITS					
Security of Supply, Diversification of sources, Diversification of routes, N-1 Nation	nal (Italy), Bac	k-up for renev	wables, Power-to-gas, Mark	et Integration (Increase of com	petition), Flexibility of the system
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-N-215	Panigaglia Panigaglia	Non-FID
	· amgagna	

### **SPONSORS**

### GENERAL INFORMATION



Promoter	Snam Rete Gas S.p.A.
Operator	Snam Rete Gas S.p.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	www.snamretegas.it/export/sites/snamretegas/repository/fi le/ENG/Thermal_Year_20112012/Information_for_User/Cap acity_plans/Capacity_and_development_Plan_2011_2012.pd f



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2022*
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+150,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+135,00
Expected Load Factor	65,00%




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Panigaglia	Yes	entry	135,00	LNG Terminals Italia	Hub Italia
DESCRIPTION OF THE PROJECT					
The project consists in new on-shore pipelines to permit the increase of transport	capacity at ti	ne Entry Point	t interconnected with the e	xisting Panigaglia LNG Termin	al
EXPECTED BENEFITS					
Security of Supply, Market integration, Diversification of sources, N-1 National (ITALY), Back-up for renewables, Market Integration (Increase of competition), Flexibility of the system, reducing of GHG emissions					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-N-009	Second Southern initiative	Non-FID

### **SPONSORS**

### GENERAL INFORMATION



Promoter	Snam Rete Gas S.p.A.
Operator	Snam Rete Gas S.p.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	www.snamretegas.it/export/sites/snamretegas/repository/fi le/ENG/Thermal_Year_20112012/information_for_User/Cap acity_plans/Capacity_and_development_Plan_2011_2012.pd f



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2022*
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+660,00
Total Compressor Power (MW)	+90,00
Maximum Capacity (GWh/d)	+275,00
Expected Load Factor	65,00%



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
	No	entry	275,00		Hub Italia
DESCRIPTION OF THE PROJECT					
The project consists in new on-shore and off-shore pipelines and in development	of compresso	r stations alo	ng the center-south of Italy	to permit the increase of tran	nsport capacity at new or existing Entry Points in south Italy
EXPECTED BENEFITS					
Security of Supply, Market integration, Diversification of sources, N-1 National (ITALY), Back-up for renewables, Power-to-gas, SoS, Market Integration (Increase of competition), Flexibility of the system					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




LNG-N-088 LNG Medgas Terminal S.r.l. Non-FID


### **LNG Terminal**

### **SPONSORS**

### **GENERAL INFORMATION**



Promoter	Sor	genia S.p.A.
Operator	LNG Med	lgas Terminal S.r.l.
TEN-E Project ?	Prio	ority Project
Interested by PCI ?		Yes
IGAs		None
Web Link	www.sorgenia.com/	
TEN-E Requests	Date of Request 2/12/08	Year Funding Granted 2010



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	0
Considered Tariff Regime	0
Applied for Exemption ?	Not yet
Exemption granted ?	0
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2012 Q1
FID	2013 Q4
Construction	2016 Q4
Commissioning	2017 Q1
Last completed Phase :	Planned

TECHNICAL INFORMATION	
Regasification facility	LNG Medgas Terminal S.r.l.
Expected volume (bcm/y)	+12,00
Storage capacity (m3)	+640.000,00
Send-out (mcm/d)	+32,90
Ship size (m3)	270.000,00
Reloading ability ?	No




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Medgas Terminal LNG	Yes	exit	361,90	LNG Terminals Italia	Hub Italia
DESCRIPTION OF THE PROJECT					
The LNG Terminal of Gioia Tauro will contribute to the satisfaction of the Europe geopolitical risk, in particular for Italy which is highly dependent on Russian and A The position of Gioia Tauro is extremely strategic both for cargoes coming from play a crucial role in allowing the supply of natural gas from alternative sources, where the supply of	Algerian impo the Suez Char	ts. This aspec	ct is in line with the specific Atlantic basin. In the even	criteria of the security of supportuality of disruptions in gas su	ly.  pplies from North African countries, the Gioia Tauro LNG Terminal would
EXPECTED BENEFITS					
Security of Supply, Market integration (Development of Italy as a gas hub and possibility to become an exporting country.), Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (Italy), N-1 Regional, N-1 criteria completion (regional level): a region is not yet formally defined; the LNG Medgas Terminal will however bring advantages at bith national level and at regional level, considering the nature of a LNG project					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




UGS-F-259	Bordolano	FID

### **SPONSORS**

### GENERAL INFORMATION



Promoter	STOGIT
Operator	STOGIT
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	www.stogit.it/en/activities/Innovation-and- research/Progetto_Bordolano.html



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2013 Q1
FID	2006 Q2
Construction	2015 Q4
Commissioning	2015 Q4
Last completed Phase :	FID

TECHNICAL INFORMATION	
Storage facility	Bordolano
Working volume (mcm)	+1.138,00
Injectability (mcm/d)	+14,00
Deliverability (mcm/d)	+19,00



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
UGS - IT - Snam Rete Gas/STOGIT	Yes	entry	154,00	Hub Italia	Storage Italia
	Yes	exit	209,00	Storage Italia	Hub Italia


DESCRIPTION OF THE PROJECT				
Depleted gas fields on-shore (new field)				
EXPECTED BENEFITS				
Security of Supply, Reverse Flows, Diversification of sources, Diversification of routes, N-1 National, N-1 Regional, Back-up for renewables, Power-to-gas, Market Integration (increase of competition and market liquidity), Increased flexibility of the system				
COMMENTS ABOUT THE PROJECT FINANCING				
Public financing	Private financing	Multilateral financing		




UGS-F-260 System Enhancements - Stogit - on-shore gas fields	FID
--	-----

SPONSORS

### GENERAL INFORMATION



Promoter	STOGIT
Operator	STOGIT
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2015 Q1
FID	2006 Q2
Construction	2022 Q4
Commissioning	2022 Q4
Last completed Phase :	FID

TECHNICAL INFORMATION	
Storage facility	Stogit Ennancements and New
Working volume (mcm)	+1.863,00
Injectability (mcm/d)	
Deliverability (mcm/d)	+18,50



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
UGS - IT - Snam Rete Gas/STOGIT	Yes	exit	203,50	Storage Italia	Hub Italia
DESCRIPTION OF THE PROJECT					
rne project envisages the development of the following depleted on-shore gas in	eias:				
- Settala					
- Fiume Treste					
- Minerbio					
- Pinalta					
EXPECTED BENEFITS					
Security of Supply, Market integration, Reverse Flows, Diversification of source	es, Diversifica	tion of route	s, N-1 National, N-1 Regio	onal, Back-up for renewables	, Power-to-gas, Market Integration (increase of competition and market
liquidity),Increased flexibility of the system					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing

PROJECTED CAPACITY INCREASES



UGS-N-002	Alsace Sud	Non-FID


## **Storage Facility**

## **SPONSORS**


## GENERAL INFORMATION

## FINANCING

2005



Promoter		Storengy
Operator		Storengy
TEN-E Project ?	Project o	of Common Interest
Interested by PCI ?	No	ot defined yet
IGAs		None
Web Link		
TEN-E Requests	Date of Request	Year Funding Granted



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2022 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
Storage facility	Alsace Sud
Working volume (mcm)	+200,00
Injectability (mcm/d)	+3,00
Deliverability (mcm/d)	+9,60



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Alsace Sud	Yes	exit	105,60	Storage France(PEG South)	Hub France(PEG South)
	Yes	entry	33,00	Hub France(PEG North)	Storage France(PEG North)

DESCRIPTION OF THE PROJECT		
Creation of a new salt cavity storage site of up to 200 mcm of working gas volume		
EXPECTED BENEFITS		
Security of Supply, Market Integration (Increase of competition) The project will contribute to the increase of storage capacity in France, which will enhance security of supply and provide more flexibility to the market thus facilitating competition.		
COMMENTS ABOUT THE PROJECT FINANCING		
Public financing	Private financing	Multilateral financing










## TRA-N-131 Enhancement of Latvia-Lithuania interconnection Non-FID


## **Pipeline including CS**

## SPONSORS

## GENERAL INFORMATION



Promoter	Latvijas Gaze
Operator	Latvijas Gaze
TEN-E Project ?	Priority Project
Interested by PCI ?	Yes
IGAs	None
Web Link	www.lg.lv/



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	2021 Q4
Commissioning	2021 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	2
Total Pipeline Length (km)	+90,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Kiemenai	Yes	entry	62,20	Hub Lithuania	Hub Latvia
	Yes	exit	62,20	Hub Latvia	Hub Lithuania

DESCRIPTION OF THE PROJECT				
In order to further enhace LV-LT interconnection section of gas pipeline in Latvia shall be built and gas metering station in Lithuania upgraded				
EXPECTED BENEFITS				
Security of Supply, Market integration, Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (Lithuania), Project will significantly increase interoperability of Latvian and Lithuanian gas systems, improve security of supply for Lithuania and will be part of important route connecting common European gas grid with gas systems of the East-Baltic countries.				
COMMENTS ABOUT THE PROJECT FINANCING				
Public financing	Private financing	Multilateral financing		
Union financial assistance	Latvijas Gaze, Lietuvos Dujos			




## UGS-N-130 Modernisation of Incukalns Underground Gas Storage Non-FID


**Storage Facility** 

SPONSORS

## GENERAL INFORMATION



Promoter	Latvij	as Gaze
Operator	Latvij	as Gaze
TEN-E Project ?	Priorit	y Project
Interested by PCI ?	Y	es es
IGAs	N	one
Web Link	www.lg.lv/	
TEN-E Requests	Date of Request 28/04/10	Year Funding Granted Not yet



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	2013 Q4
Construction	2025 Q4
Commissioning	2025 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
Storage facility	Incukalns Underground Gas Storage
Working volume (mcm)	+2.300,00
Injectability (mcm/d)	+17,00
Deliverability (mcm/d)	+30,00



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
UGS - LV - Latvijas Gaze	Yes	entry	198,00	Storage Latvia	Hub Latvia
	Yes	exit	385,00	Hub Latvia	Storage Latvia
UGS - LV - Latvijas Gaze	Yes	exit	187,00	Hub Latvia	Storage Latvia
	Yes	entry	330,00	Storage Latvia	Hub Latvia

## DESCRIPTION OF THE PROJECT Modernization of existing and construction of new facilities with the aim to increase daily output from 30 to 35 million m3 and to comply with the EN 1918:1

### **EXPECTED BENEFITS**

Security of Supply, Market integration, Diversification of sources, Diversification of routes, N-1 Regional (BEMIP), Back-up for renewables, The Implementation of the Projects will enhance cross-border interconnection capacity, along with strengthening economic cooperation in the region, building links between Poland and Lithuania, and strengthening the economic cohesion with the common EU grid.

## COMMENTS ABOUT THE PROJECT FINANCING Public financing Private financing Multilateral financing Union financial assistance Latvijas Gaze Other parties keeping gas in the storage

## Lithuania








LNG-F-058	Klaipeda LNG terminal	FID


## **LNG Terminal**

## SPONSORS

## **GENERAL INFORMATION**



Promoter	Klaiped	los Nafta		
Operator	AB Klaipe	AB Klaipėdos Nafta		
TEN-E Project ?	Project of Co	Project of Common Interest		
Interested by PCI ?	Not def	fined yet		
IGAs	No	one		
Web Link	www.oil.lt/index.php?id=lng&	.L=1		
TEN-E Requests	Date of Request 1/07/09	Year Funding Granted 2010		



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2013 Q2
FID	2012 Q1
Construction	2014 Q4
Commissioning	2014 Q4
Last completed Phase :	FEED

TECHNICAL INFORMATION	
Regasification facility	
Expected volume (bcm/y)	+2,00
Storage capacity (m3)	+170.000,00
Send-out (mcm/d)	+5,00
Ship size (m3)	170.000,00
Reloading ability ?	Yes



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Klaipeda (LNG)	Yes	exit	55,00	LNG Terminals Lithuania	Hub Lithuania
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
EXPECTED BENEFITS					
Security of Supply, Market integration, Diversification of sources, Diversification of	of routes, N-1	National (Lith	uania), Reduce Lithu	ania's dependence on the single ex	ternal natural gas supplier;
Ensure diversification of natural gas supply sources; Create real gas market and ensuring natural gas supply in Lithuania.					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-N-238	Enhancement of Capacity of Pipeline Klaipeda-Kiemenai	Non-FID


## **Pipeline including CS**

## **SPONSORS**

## GENERAL INFORMATION



Promoter	Lietuvos Dujos
Operator	Lietuvos Dujos
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	www.dujos.lt



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2017 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+110,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+62,00
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Klaipeda (LNG)	Yes	entry	62,00	LNG Terminals Lithuania	Hub Lithuania
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Diversification of sources, Diversification of routes, N-1 National (Lithuania), N-1 Regional (Baltic States).  This project would provide capacity to transport the gas from LNG terminal in Klaipeda to other Baltic states for the needs of national consumption as well as to the Incukalns underground gas storage (Latvia) as well as would provide ar opportunity for the market players of certain Baltic states to diversify gas supply routes and sources and possibly enhance competition in the gas market.					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing
Support from EU structural funds is expected.					




TRA-F-239	Gas pipeline Jurbarkas-Klaipeda	FID
Pipeline including CS		

SPONSORS GENERAL INFORMATION





Promoter	Lietuvos Dujos
Operator	Lietuvos Dujos
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	www.dujos.lt



THIRD-PARTY ACCESS REGIME		
Considered TPA Regime	Regulated	
Considered Tariff Regime	Regulated	
Applied for Exemption ?	No	
Exemption granted ?	No	
% Exemption in entry direction	0%	
% Exemption in exit direction	0%	

SCHEDULE	
End of permitting phase	
FID	2011 Q4
Construction	2013 Q4
Commissioning	2013 Q4
Last completed Phase :	FID

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+137,60
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, The Klaipeda-Jubarkas gas pipeline will create a circular natura	al gas transmi	ssion system i	in Lithuania contributing th	us to the security of supply.	
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing
Support from EU structural funds.	Lietuvos Du	ios			
Support from Lo structural funus.	Lietuvos Du	jus			




UGS-N-034	Syderiai	Non-FID

## **Storage Facility**

## **SPONSORS**

## GENERAL INFORMATION


## **FINANCING**



Promoter	Lietuvos e	energija AB
Operator	Lietuvos e	energija AB
TEN-E Project ?	Project of Cor	mmon Interest
Interested by PCI ?	Y	'es
IGAs	No	one
Web Link	le.lt	
TEN-E Requests	Date of Request 28/02/11	Year Funding Granted 2012

27/06/08

2010



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2015 Q4
FID	2014 Q3
Construction	2018 Q4
Commissioning	2019 Q4
Last completed Phase :	

TECHNICAL INFORMATION	
Storage facility	Syderiai underground gas storage
Working volume (mcm)	+500,00
Injectability (mcm/d)	+5,00
Deliverability (mcm/d)	+10,00



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Syderiai	Yes	entry	55,00	Hub Lithuania	Storage Lithuania
	Yes	exit	110,00	Storage Lithuania	Hub Lithuania
DESCRIPTION OF THE PROJECT					
Expected total capacity – 1 billion m3, storage will create conditions for gas reser	ve storage in l	Lithuania, inc	rease the security of su	oply and contribute to the creati	on of national gas market
EXPECTED BENEFITS					
Security of Supply, Market integration, Diversification of sources, The project sho	ould create co	onditions for	natural gas reserve sto	age in Lithuania, increase the se	ecurity of natural gas supply in the region and contribute to the creation of
national gas market					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing

PROJECTED CAPACITY INCREASES




ENTSOG AISBL
Avenue de Cortenbergh 100
B-1000 Brussels
T +32 (0)2 894 51 00
info@entsog.eu
www.entsog.eu







## Luxembourg








TRA-N-013	OS GRTgaz/Creos	Non-FID


## **Pipeline including CS**

## **SPONSORS**

## GENERAL INFORMATION



Promoter	Creos Luxembourg S.A.
Operator	Creos Luxembourg S.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2014 Q2
FID	2013 Q3
Construction	2014 Q2
Commissioning	2017 Q3
Last completed Phase :	Construction


TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+2,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+40,00
Expected Load Factor	



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
New IP France/Luxemburg	Yes	entry	40,00	Hub France(PEG North)	Hub Luxemburg
DESCRIPTION OF THE PROJECT					
add entry capacity from France to Lux					
EXPECTED BENEFITS					
Security of Supply, Market integration, Diversification of sources, Diversificatio European gas infrastructure	n of routes, I	N-1 National,	N-1 Regional, Extension of	f transport capacity of Russia	n gas to the West, Integration of Nord Stream off- and on-Shore in the
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing

PROJECTED CAPACITY INCREASES

## The Netherlands









## **Pipeline including CS**

## **SPONSORS**

## GENERAL INFORMATION



Promoter	Gasunie Transport Services B.V.
Operator	Gasunie Transport Services B.V.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2020
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	




Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
	No	exit	0,00		
DECORPORATION OF THE PROJECT					
DESCRIPTION OF THE PROJECT					
Additional blending facilities to allow additional Quality Conversion					
EXPECTED BENEFITS					
Security of Supply, Market integration, Diversification of sources					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing

PROJECTED CAPACITY INCREASES




TRA-N-192	Entry capacity expansion GATE terminal	Non-FID
Pipeline including CS		

GENERAL INFORMATION



**SPONSORS** 

# Promoter Gasunie Transport Services B.V. Operator Gasunie Transport Services B.V. TEN-E Project ? Not part of TEN-E Interested by PCI ? Not defined yet IGAs None Web Link



THIRD-PARTY ACCESS REGIME		SCHEDULE		TECHNICAL INFORMATION	
Considered TPA Regime	Regulated	End of permitting phase		# of Pipelines, nodes, CS	1
Considered Tariff Regime	Regulated	FID		Total Pipeline Length (km)	+25,00
Applied for Exemption ?	No	Construction		Total Compressor Power (MW)	
Exemption granted ?	Not relevant	Commissioning	2016	Maximum Capacity (GWh/d)	+200,00
% Exemption in entry direction	0%	Last completed Phase :	Planned	<b>Expected Load Factor</b>	
% Exemption in exit direction	0%				



To Zone

Multilateral financing

DESCRIPTION OF THE PROJECT  Expansion of entry capacity into GTS network  EXPECTED BENEFITS  Security of Supply, Diversification of sources, Diversification of routes						
Expansion of entry capacity into GTS network  EXPECTED BENEFITS  Security of Supply, Diversification of sources, Diversification of routes	Gate Terminal (I)	Yes	entry	200,00	LNG Terminals Netherlands	Hub Netherlands
Expansion of entry capacity into GTS network  EXPECTED BENEFITS  Security of Supply, Diversification of sources, Diversification of routes						
Expansion of entry capacity into GTS network  EXPECTED BENEFITS  Security of Supply, Diversification of sources, Diversification of routes						
Expansion of entry capacity into GTS network  EXPECTED BENEFITS  Security of Supply, Diversification of sources, Diversification of routes						
Expansion of entry capacity into GTS network  EXPECTED BENEFITS  Security of Supply, Diversification of sources, Diversification of routes						
Expansion of entry capacity into GTS network  EXPECTED BENEFITS  Security of Supply, Diversification of sources, Diversification of routes						
Expansion of entry capacity into GTS network  EXPECTED BENEFITS  Security of Supply, Diversification of sources, Diversification of routes	DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS  Security of Supply, Diversification of sources, Diversification of routes	DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS  Security of Supply, Diversification of sources, Diversification of routes						
EXPECTED BENEFITS  Security of Supply, Diversification of sources, Diversification of routes						
Security of Supply, Diversification of sources, Diversification of routes	Expansion of entry capacity into GTS network					
Security of Supply, Diversification of sources, Diversification of routes						
Security of Supply, Diversification of sources, Diversification of routes						
Security of Supply, Diversification of sources, Diversification of routes						
	EXPECTED BENEFITS					
	Security of Sunnly Diversification of sources Diversification of routes					
COMMENTS ABOUT THE PROJECT FINANCING	security of supply, biversification of sources, biversification of fouces					
COMMENTS ABOUT THE PROJECT FINANCING						
COMMENTS ABOUT THE PROJECT FINANCING						
	COMMENTS ABOUT THE PROJECT FINANCING					

From Zone

Modelled Direction Capacity (GWh/d)

Private financing

PROJECTED CAPACITY INCREASES

Interconnection

**Public financing** 



TRA-N-193	Gas Compressor Optimisation Program	Non-FID
Pipeline including CS		

Pipeline including C

SPONSORS



GENERAL INFORMATION

Operator Gasunie Transport Services B.V.


TEN-E Project ? Not part of TEN-E

Interested by PCI ? Yes

IGAs None

Gasunie Transport Services B.V.

Web Link



**FINANCING** 

THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
	-0.
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

Gas Transport Services (100%)

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2022*
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	
Total Compressor Power (MW)	+540,00
Maximum Capacity (GWh/d)	+3.560,00
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Hilvarenbeek/'s Gravenvoeren	No	exit	0,00	<b>Hub Netherlands</b>	Hub Belgium
Winterswijk/Zevenaar/Bocholtz	No	exit	0,00	<b>Hub Netherlands</b>	Hub Germany

DESCRIPTION OF THE PROJECT				
Project is carried out in order to to comply with Industrial Emissions Directive				
EXPECTED BENEFITS				
Security of Supply, Market integration (), Diversification of sources, Sustainability by reduction of emissions				
COMMENTS ABOUT THE PROJECT FINANCING				
Public financing	Private financing	Multilateral financing		




TRA-F-268	System Enhancements FID update - Gas Transport Services	FID
-----------	---	-----


**Pipeline including CS** 

**SPONSORS** 

## GENERAL INFORMATION



Promoter	Gasunie Transport Services B.V.
Operator	Gasunie Transport Services B.V.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	www.integratedopenseason.com



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2014 Q3
Last completed Phase :	FID

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+100,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Virtual IP (GTS) NL-DE	Yes	entry	97,00	<b>Hub Germany</b>	Hub Netherlands
Virtual Ips (GTS) NL - UK	No	exit	0,00	<b>Hub Netherlands</b>	Hub United Kingdom
Virtual Ips (GTS) NL-DE (NCG)	Yes	entry	24,00	Hub Germany(NCG)	Hub Netherlands
Virtual Ips (GTS) NL-DE (Gaspool)	Yes	entry	73,00	Hub Germany(Gaspool)	Hub Netherlands
Virtual IP (GTS) NL-BE	No	entry	0,00	<b>Hub Belgium</b>	Hub Netherlands
	Yes	exit	203,00	<b>Hub Netherlands</b>	Hub Belgium
UGS - NL - GTS/DE	Yes	entry	111,00	Storage Germany	Hub Netherlands
Various system capacity enhancements (further expansion of gas roundabout, Integrated Open Season, connection to Bergermeer Storage)					
EXPECTED BENEFITS					
Security of Supply, Market integration (increase of competition), Diversification of sources, Diversification of routes, Import, Quality Conversion Further expansion of the gas roundabout increases SoS since it enables additional import of gas and also connects storages to the gas networks. Furthermore, interconnection capacity between TSOs is increased which increases market integration.					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	<b>Private fina</b>	ncing			Multilateral financing



## LNG-N-050 Gate terminal phase 3 Non-FID


## **LNG Terminal**

## **SPONSORS**

# OMV (5%) DONG Energy (5%) NV Nederlandse Gasunie (45%) Royal Vopak NV (45%)

## GENERAL INFORMATION

Promoter	Gate Terminal B.V.	
Operator	Gate Terminal B.V.	
TEN-E Project ?	Not part of TEN-E	
Interested by PCI ?	Not defined yet	
IGAs	None	
Web Link	www.gateterminal.com	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	Yes
Exemption granted ?	Yes
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2007 Q4
FID	2013 Q3
Construction	2016 Q3
Commissioning	2016 Q3
Last completed Phase :	Permitting

TECHNICAL INFORMATION	
Regasification facility	Gate terminal Rotterdam
Expected volume (bcm/y)	+4,00
Storage capacity (m3)	+180.000,00
Send-out (mcm/d)	+11,00
Ship size (m3)	266.000,00
Reloading ability ?	No



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Gate Terminal (I)	Yes	exit	121,00	LNG Terminals Netherlands	Hub Netherlands
DESCRIPTION OF THE PROJECT					
Increase the capacity by 4 BCM p.a. from the current 12 BCM p.a. to 16 BCM p.a.					
EXPECTED BENEFITS					
Security of Supply, Diversification of sources, Diversification of routes, Back-up for renewables, Market Integration (Increase of competition)  Gate terminal obtained an exempted ex Art 22 Gas Directive 2003/55/EC. In order to obtain an exemption it needed to be demonstrated that Gate terminal enhanced both security of supply and the competition on the gas market.					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing
Unknown	Unknown				




## UGS-F-052 Gas Storage Bergermeer (GSB) FID


## **Storage Facility**

## SPONSORS

## GENERAL INFORMATION



Promoter	TAQA Gas Storage B.V.		
Operator	TAQA Gas Storage B.V.		
TEN-E Project ?	Not part of TEN-E		
Interested by PCI ?	Not defined yet		
IGAs	None		
Web Link	www.gasstoragebergermeer.com/		



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%


SCHEDULE	
End of permitting phase	2012 Q2
FID	2009 Q4
Construction	
Commissioning	2014 Q1
Last completed Phase :	Permitting

TECHNICAL INFORMATION	
Storage facility	Gas Storage Bergermeer
Working volume (mcm)	+4.100,00
Injectability (mcm/d)	+42,00
Deliverability (mcm/d)	+57,00



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Bergermeer	Yes	exit	627,00	Storage Netherlands	Hub Netherlands
	Yes	entry	462,00	Hub Netherlands	Storage Netherlands
DESCRIPTION OF THE PROJECT					
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
EXPECTED DENEFITS					
Security of Supply, Market integration (Trading, infrastructure and transport in no				•	• , ,
Bergermeer Gas Storage will significantly enhance the security of energy supply to Dutch and European consumers, providing a reserve of the equivalent to the annual gas consumption of approximately 1.6 million Dutch households. The planned working volume amounts to 4.1 bcm. It will also be a major contributor to liquidity in the North-West European gas markets.					
The project is a valuable contribution towards the ambition the Dutch State to realise the 'gas roundabout of North-West Europe' in The Netherlands.  Once commercially operational, the majority of the capacity of the facility will be made available for third party access. This will contribute to increased competition on the market.					
Once commercially operational, the majority of the capacity of the facility will be	illaue avallab	іе іог піна ра	irty access. This will contri	bute to increased competition	on the market.
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing










LNG-N-211 Connection of Malta to the European Gas Network - LNG Regasification Infrastructure Non-FID

## **LNG Terminal**

## **SPONSORS**


## GENERAL INFORMATION

## FINANCING



Promoter	Ener	nalta Corporation
Operator	Enen	nalta Corporation
TEN-E Project ?	No	ot part of TEN-E
Interested by PCI ?		Yes
IGAs		None
Web Link		
TEN E Danwarts	Data of Barres	Veen Franking Counted

TEN-E Requests Date of Request Year Funding Granted 28/02/12 Not yet



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2015 Q3
FID	2013 Q3
Construction	2015 Q4
Commissioning	2018 Q4
Last completed Phase :	Planned

Malta FSRU OffshoreTerminal
+2,00
+200.000,00
+5,50
135.000,00
Yes



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Malta FSRII Offshore Terminal	Vos	evit	60 50	Hub Malta	Huh Italia

## **DESCRIPTION OF THE PROJECT**

Malta is a small island Member State with no gas interconnections to the European network, thus the project will: connect Malta to the European Natural Gas Network via a 150 kilometre 25" diameter pipeline to Sicily; and install a Floating LNG Storage and Re-gasification Unit (FSRU) to be supplied with LNG shipments and which would be connected to the Delimara Power Station (via a 12 kilometre pipeline) and to the gas interconnection. The objectives of the proposal are: to connect Malta to the European Gas network and strengthen Malta's energy security of supply; to deliver Natural Gas (NG) to Malta for electricity generation and to local consumers for commercial, industrial and domestic use; to export natural gas by pipeline to Sicily from the FSRU offshore terminal which will incorporate a 200,000 m3 LNG storage facitity. This questionnaire addresses the offshore LNG regasification infrastructure part of the project.

## **EXPECTED BENEFITS**

Security of Supply, Market integration (Malta and Italy), Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (Malta and Italy), N-1 Regional (Sicily), Back-up for renewables, The project will be ending the isolation that Malta has from the European Gas networks. It will provide diversification of fuels by reducing the current complete dependence on imported liquid fossil fuels. It will provide access to a potentially lower cost fuel for electricity generation and for commercial and domestic use, thereby improving competitiveness and affordability of energy in Malta. It will also deliver energy efficiency gains in generation of electricity and other uses. Natural gas, being a cleaner fuel than the current fossil fuels in use, will contribute to a reduction of energy-related emissions and will be beneficial to reach Climate Change targets. The pipeline connection to Sicily will also serve to increase security of supply by serving as a backup supply option in the case of prolonged interruption of the LNG supply, as natural gas can be sourced from the Italian gas network.

# COMMENTS ABOUT THE PROJECT FINANCING Public financing Private financing Multilateral financing




TRA-N-031	Connection of Malta to the European Gas Network - Pipelines	Non-FID

**Pipeline including CS** 

SPONSORS

## GENERAL INFORMATION


## **FINANCING**



Promoter	Enem	alta Corporation
Operator	Enem	alta Corporation
TEN-E Project ?	No	t part of TEN-E
Interested by PCI ?		Yes
IGAs		None
Web Link		
TEN-E Requests	Date of Request	Year Funding Granted

28/02/12

Not yet



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2015 Q3
FID	2013 Q3
Construction	2015 Q4
Commissioning	2018 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	2
Total Pipeline Length (km)	+162,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+48,20
Expected Load Factor	



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
FSRU (Malta) to Sicily Interconnection	Yes	exit	48,20	LNG Terminals Malta	Hub Italia
FSRU (Malta) to Delimara (Malta) Connection	Yes	exit	12,00	LNG Terminals Malta	Hub Malta

## **DESCRIPTION OF THE PROJECT**

Malta is a small island Member State with no gas interconnections to the European network, thus the project will: connect Malta to the European Natural Gas Network via a 150 kilometre 25"diameter pipeline to Sicily; and install a Floating LNG Storage and Re-gasification Unit (FSRU) to be supplied with LNG shipments and which would be connected to the Delimara Power Station (via a 12 kilometre pipeline) and to the gas interconnection. The objectives of the proposal are: to connect Malta to the European Gas network and strengthen Malta's energy security of supply; to deliver Natural Gas (NG) to Malta for electricity generation and to local consumers for commercial, industrial and domestic use; to export natural gas by pipeline to Sicily from the FSRU offshore terminal which will incorporate a 200,000 m3 LNG storage facitilty. This questionnaire addresses only the pipelines infrastructure part of this project whilst a separate questionnaire addresses the offshore LNG regasification infrastructure part of the project.

## **EXPECTED BENEFITS**

Security of Supply, Market integration (Malta and Italy), Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (Malta and Italy), N-1 Regional (Sicily), Back-up for renewables. The project will be ending the isolation that Malta has from the European Gas networks. It will provide diversification of fuels by reducing the current complete dependence on imported liquid fossil fuels. It will provide access to a potentially lower cost fuel for electricity generation and for commercial and domestic use, thereby improving competitiveness and affordability of energy in Malta. It will also deliver energy efficiency gains in generation of electricity and other uses. Natural gas, being a cleaner fuel than the current fossil fuels in use, will contribute to a reduction of energy-related emissions and will be beneficial to reach Climate Change targets. The pipeline connection to Sicily will also serve to increase security of supply by serving as a backup supply option in the case of prolonged interruption of the LNG supply, as natural gas can be sourced from the Italian gas network.

Public financing	Private financing	Multilateral financing










## TRA-N-212 Gas Interconnection Poland-Lithuania (GIPL) Non-FID


## **Pipeline including CS**

## SPONSORS

## GENERAL INFORMATION



Promoter	GAZ-S	YSTEM S.A.		
Operator	GAZ-S	GAZ-SYSTEM S.A.		
TEN-E Project ?	Project of C	Project of Common Interest		
Interested by PCI ?		Yes		
IGAs		None		
Web Link	en.gaz-system.pl/nasze-inw systemem/polska-litwa/	estycje/integracja-z-europejski-		
TEN-E Requests	Date of Request	Year Funding Granted 2012		



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	2013 Q4
Construction	
Commissioning	2017
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+562,00
Total Compressor Power (MW)	+2,10
Maximum Capacity (GWh/d)	+68,00
Expected Load Factor	44,00%



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Interconnector PL-LT	Yes	exit	68,00	Hub Poland	Hub Lithuania
	Yes	entry	29,00	Hub Lithuania	Hub Poland
Interconnector PL-LT	No	exit	63,70	Hub Poland	Hub Lithuania

## **DESCRIPTION OF THE PROJECT**

GIPL aims to connect the gas transmission systems in Poland and Lithuania and, consiquently, enable the integration of the isolated gas markets in the Baltic States (and Finland) with Polish and EU gas markets contributing to the creation of the regional gas market, enhancing competition and the security of gas supply. The project will also provide an access to the global LNG market for the Baltic States (via the LNG terminal in Świnoujście). The construction of GIPL, except the above benefits for security and diversification of gas supplies in the Baltic region, will allow to connect the Baltic States with the CEE countries, thus providing strategic link between BEMIP and North-South priority corridors in this part of Europe.

## **EXPECTED BENEFITS**

Security of Supply, Market integration (market areas in the Baltic States and Central-Eastern Europe), Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (Lithuania and possibly Latvia, Estonia), N-1 Regional (the Baltic Sea region), Back-up for renewables, The very aim of GIPL is the integration of the isolated gas markets of the Baltic States into the EU gas grid, by introducing the alternative gas supply route to the Baltic States. This interconnection will diversify the gas supply sources, increase the security of supply and will serve for the enhancement of competition in the gas market of the Baltic States.

For the Baltic States, GIPL will provide the access both to EU gas spot market and to the global LNG market via LNG terminal in Świnoujście. From long-term perspective, it may also be used for importing shale-gas from Poland, if production of it comes into large scale level. For the Polish market players, GIPL will provide the opportunity of using Latvian Incukalns UGS. Also through GIPL, gas could be supplied to currently non-gasified areas in Poland and Lithuania.

Public financing	Private financing	Multilateral financing
TEN-E (obtained for studies), support from other EU funds is expected		




LNG-F-246	LNG terminal in Świnoujście	FID
LNG-F-246	LNG terminal in Świnoujście	FID


## **LNG Terminal**

## SPONSORS

## GENERAL INFORMATION



Promoter	GAZ-SYSTEM S.A.
Operator	Polskie LNG S.A.
TEN-E Project ?	Priority Project
Interested by PCI ?	No
IGAs	None
Web Link	en.gaz-system.pl/terminal-lng/



THIRD-PARTY ACCESS REGIME		SCHEDULE
Considered TPA Regime	Regulated	End of permit
Considered Tariff Regime	Regulated	FID
Applied for Exemption ?	No	Construction
Exemption granted ?	Not relevant	Commissionin
% Exemption in entry direction	0%	Last complete
% Exemption in exit direction	0%	

SCHEDULE	
End of permitting phase	
FID	2010
Construction	
Commissioning	2014
Last completed Phase :	FID

TECHNICAL INFORMATION	
Regasification facility	LNG terminal in Świnoujście
Expected volume (bcm/y)	+5,00
Storage capacity (m3)	+320.000,00
Send-out (mcm/d)	+13,68
Ship size (m3)	216.000,00
Reloading ability ?	No



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Swinoujscie	Yes	exit	150,48	LNG Terminals Poland	Hub Poland

## **DESCRIPTION OF THE PROJECT**

The LNG terminal in Śwnoujście will be the first LNG terminal in the Baltic Sea region. It will come on stream in 2014 with annual re-gasification capacity of 5 bcm/y. In the following years, depending on the increase of demand for gas, it will be possible to increase the capacity up to 7,5 bcm/y, without the need to increase the area on which the terminal will be constructed. The terminal in Świnoujście will consist of two storage tanks, each with the capacity of 160 tcm. The LNG terminal in Świnoujście will offer its regasification capacities not only to gas consumers in Poland, but also in the Baltic Sea region (supplies to be directed via Gas Interconnection Poland-Lithuania and/or LNG ships) and in Central-Eastern Europe (supplies within the North-South Gas Interconnections).

## **EXPECTED BENEFITS**

Security of Supply, Diversification of sources, Diversification of routes, N-1 National (Poland and possibly Lithuania, Latvia, Estonia, Denmark, Slovakia and Hungary), N-1 Regional (Baltic Sea region, Central-Eastern Europe), Back-up for renewables, The LNG terminal in Swinoujscie will have an impact on: increasing security of supply in the Baltic Sea and CEE regions by diversifying supply routes, sources (the first new physical source of supply for both regions) and counterparts (access to global LNG market); creating well-interconnected gas infrastructure in the Baltic Sea and CEE regions; eliminating the energy islands, as the terminal in Swinoujscie may play the role of regional LNG terminal for the Baltic States and Finland (transport of gas via Gas Interconnection Poland-Lithuania or transport by LNG vessels); enhancing competition on regional markets; promoting natural gas as a reliable, competitive and environmentally-friendly source of energy e.g. in the transport sector (maritime transport); creating a physical hub in Swinoujscie and/or a virtual hub in Poland; establishing adequate technical conditions necessary to cover the forecasted growth of the gas demand in Poland based on the development of the power generation sector and possible leverage for market coupling potential in the Baltic Sea region and in Central-Eastern Europe.

The LNG terminal in Świnoujście contributes to North-South gas interconnections in Central Eastern and South Eastern Europe, as the supplies from Świnoujście may be directed through upgraded transmission system in Poland (the North-South Corridor in Poland), PL-CZ and PL-SK interconnections towards the South, to other CEE countries.

Public financing	Private financing	Multilateral financing
EEPR, ERDF (Operational Programme Infrastructure and Environment), TEN-E	Equity, commercial banks	EIB, EBRD




TRA-N-273	PL - CZ interconnection	Non-FID


## **Pipeline including CS**

## SPONSORS

## **GENERAL INFORMATION**



Promoter	GAZ-SYS	STEM S.A.
Operator	GAZ-SYS	STEM S.A.
TEN-E Project ?	Project of Co	mmon Interest
Interested by PCI ?	Y	'es
IGAs	No	one
Web Link		
TEN-E Requests	Date of Request	Year Funding Granted Not yet



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	2014
Construction	
Commissioning	2017
Last completed Phase :	Planned

TECHNICAL INFORMATION		
# of Pipelines, nodes, CS	1	
Total Pipeline Length (km)	+107,00	
Total Compressor Power (MW)		
Maximum Capacity (GWh/d)	+195,90	
Expected Load Factor	80,00%	



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Interconnector CZ-PL	Yes	exit	150,60	Hub Poland	Hub Czech Republic
	Yes	entry	195,90	Hub Czech Republic	Hub Poland

## **DESCRIPTION OF THE PROJECT**

The project aims to increase the cross-border capacity between Poland and the Czech Republic by establishing a large transportation corridor that will allow for flexible transport of gas in Central-Eastern Europe within the North-South corridor.

## **EXPECTED BENEFITS**

Security of Supply, Market integration (market areas in Central-Eastern Europe), Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (Poland, possibly Slovakia and Hungary), N-1 Regional (Central-Eastern Europe), Back-up for renewables, Implementation of PL-CZ interconnection will have an impact on:

increasing the security of gas supply and providing the overall flexibility for the CEE region and diversifying the supply routes for the CEE region;

improving European gas grid interconnection;

increasing the security and reliability of the cross-border gas transmission between the Czech Republic and Poland (fulfilment of N-1 rule in Poland);

creating a robust, well-functioning internal market in the Czech Republic and Poland and promoting the competition;

contributing to the creation of an integrated and competitive gas market in the CEE region;

establishing adequate technical conditions necessary to cover the forecasted growth of the gas demand in Poland based on the development of the power generation sector and possible leverage for market coupling potential in Central-Eastern Europe.

Public financing	Private financing	Multilateral financing
Support from EU funds is expected		




TRA-N-271 PL - DK interconnection (Baltic Pipe) Non-FID	
---	--


## **Pipeline including CS**

## **SPONSORS**

## GENERAL INFORMATION



Promoter	GAZ-SY	STEM S.A.
Operator	GAZ-SY	STEM S.A.
TEN-E Project ?	Project of Co	mmon Interest
Interested by PCI ?		Yes
IGAs	N	one
Web Link	en.gaz-system.pl/nasze-inwe systemem/baltyckibaltic-pipe	stycje/integracja-z-europejski- :/
TEN-E Requests	Date of Request 30/06/08	Year Funding Granted 2009
	24/04/09	2010



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	2015
Construction	
Commissioning	2020
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	2
Total Pipeline Length (km)	+324,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+90,40
Expected Load Factor	



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Interconnector PL-DK	Yes	exit	90,40	Hub Poland	Hub Denmark
	Yes	entry	90,40	Hub Denmark	Hub Poland

## **DESCRIPTION OF THE PROJECT**

Baltic Pipe aims to connect the gas transmission systems in Poland and Denmark and thus cover the higher import needs of Danish and Swedish markets originating from declining production in the Danish part of the North Sea. The project will also cover the forecasted growth of the gas demand in Poland based on the development of the power generation sector and possible leverage for market coupling potential in the Baltic States and Central-Eastern Europe.

## **EXPECTED BENEFITS**

Security of Supply, Market integration (market areas in the Baltic Sea region and Central-Eastern Europe), Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (Poland, Denmark), N-1 Regional (the Baltic Sea region), Back-up for renewables, Baltic Pipe will have a significant impact on:

increasing security of supply in the Baltic Sea region by diversifying supply routes, sources and counterparts;

creating well-interconnected gas infrastructure in the Baltic Sea region;

enhancing competition on the regional markets;

promoting natural gas as a reliable, competitive and environmentally-friendly source of energy e.g. in the power generation sector.

The Baltic Pipe project also contributes to North-South gas interconnections in Central Eastern and South Eastern Europe, as the project which will allow to transport gas from North Sea deposits to the CEE countries, namely to the Czech Republic and Slovakia (via the North-South corridor in Poland, PL-CZ and PL-SK interconnections).

Public financing	Private financing	Multilateral financing
TEN-E (obtained), support from other EU funds is expected		




TRA-N-275	PL - SK interconnection	Non-FID


## **Pipeline including CS**

## SPONSORS

## **GENERAL INFORMATION**



Promoter	GAZ-	GAZ-SYSTEM S.A.			
Operator	GAZ-	GAZ-SYSTEM S.A.			
TEN-E Project ?	Project of	Project of Common Interest			
Interested by PCI ?		Yes			
IGAs		None			
Web Link	en.gaz-system.pl/nasze-in systemem/polska-slowacj	westycje/integracja-z-europejski- a/			
TEN-E Requests	Date of Request 28/02/11	Year Funding Granted Not yet			



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	2014
Construction	
Commissioning	2016
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+180,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+171,70
Expected Load Factor	84,00%



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Interconnector PL - SK	Yes	entry	171,70	Hub Slovakia	Hub Poland
	Yes	exit	129,50	Hub Poland	Hub Slovakia

## **DESCRIPTION OF THE PROJECT**

The main goal of the project is to create an important part of the North-South gas interconnections in Central-Eastern Europe by implementing a missing interconnection between the transmission systems in Poland and Slovakia and, thus, increase the security of gas supplies in Central-Eastern Europe through the diversification of supply sources and routes, as well as integration of Sub-Carpathian Market Area and enhancing market functionality.

## **EXPECTED BENEFITS**

Security of Supply, Market integration (market areas in Central-Eastern Europe), Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (Poland, Slovakia and possibly Hungary), N-1 Regional (Central-Eastern Europe), Back-up for renewables, Implementation of PL-SK interconnection will have an impact on:

creating the cross-border capacity between Poland and Slovakia by establishing a large transportation corridor that will allow for flexible transport of gas in Central Europe within the North-South axis;

increasing the security of gas supply and diversification of supply routes for the CEE region;

improve European gas grid interconnection;

increasing the security and reliability of the cross-border gas transmission between Slovakia and Poland (contribution to N-1 standard in Poland and Slovakia);

creating a robust, well-functioning internal market in Slovakia and Poland and promote the competition;

establishing adequate technical conditions necessary to cover the forecasted growth of the gas demand in Poland based on the development of the power generation sector and possible leverage for market coupling potential in Central-Eastern Europe.

Public financing	Private financing	Multilateral financing
TENE (obtained), support from EU funds is expected		




TRA-N-247	The North-South corridor in Western Poland	Non-FID
ipeline including CS		


Pipeline including C

SPONSORS

## **GENERAL INFORMATION**



Promoter	GAZ-SYSTEM S.A.		
Operator	GAZ-SYSTEM S.A.		
TEN-E Project ?	Not part of TEN-E		
Interested by PCI ?	Yes		
IGAs	None		
Web Link	en.gaz-system.pl/nasze-inwestycje/krajowy-system- przesylowy/		



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	2015
Construction	
Commissioning	2021
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	11
Total Pipeline Length (km)	+913,00
Total Compressor Power (MW)	+2,30
Maximum Capacity (GWh/d)	
Expected Load Factor	



## PROJECTED CAPACITY INCREASES Interconnection Modelled Direction Capacity (GWh/d) From Zone To Zone

## **DESCRIPTION OF THE PROJECT**

The investment tasks within the project constitute essential elements of the planned North-South gas interconnections in Central-Eastern Europe. This corridor consists of two routings on the Polish territory – the basic one that is located in Western and Southern Poland and the complementary routing covering the area of potential unconventional gas deposits in Eastern Poland. Implementation of the project will enhance functionality of transmission system in Western and Southern Poland. It will also enforce the internal system in order to facilitate better operational functioning of the upgraded PL-CZ interconnection, as well as to initiate gas flow on the planned PL-SK interconnection.

## **EXPECTED BENEFITS**

Security of Supply, Market integration (market areas in Central-Eastern Europe), Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (Poland), N-1 Regional (Central-Eastern Europe), Back-up for renewables, Implementation of the investment tasks within this project will have an impact on:

enhancing functionality of transmission system in Central and Southern Poland in order to facilitate better operational functioning of the upgraded PL-CZ interconnection, as well as to initiate gas flow on the planned PL-SK interconnection. increasing the security of supply sources, routes and counterparts, as well as to providing the overall flexibility for the CEE region.

improving European gas grid interconnections.

creating a robust, well-functioning internal market in the CEE region, by ensuring high reliability of the cross-border transmission between Poland, the Czech Republic and Slovakia.

## COMMENTS ABOUT THE PROJECT FINANCING Public financing Private financing Multilateral financing support from EU funds is expected




## TRA-N-245 The North-South Gas Corridor in Eastern Poland Non-FID


**Pipeline including CS** 

**SPONSORS** 

## **GENERAL INFORMATION**



Promoter	GAZ-SYSTEM S.A.
Operator	GAZ-SYSTEM S.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	2017
Construction	
Commissioning	2020
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	8
Total Pipeline Length (km)	+378,00
Total Compressor Power (MW)	+18,30
Maximum Capacity (GWh/d)	
Expected Load Factor	



## PROJECTED CAPACITY INCREASES Interconnection Modelled Direction Capacity (GWh/d) From Zone To Zone

## **DESCRIPTION OF THE PROJECT**

The investment tasks within the project constitute essential elements of the planned North-South gas interconnections in Central Eastern and South Eastern Europe. The corridor consists of two routings on the Polish territory – the basic one that is located in western and southern Poland and the complementary routing covering the area of potential unconventional gas deposits in Eastern Poland and being connected to two interconnectors, i.e. Poland – Lithuania (GIPL) and Poland – Slovakia. Implementation of the project will allow for significant volumes of gas to be transported by means of PL-SK interconnection. It will also enhance the access to the USG Strachocina that have large expansion potential and may serve as essential security of supply infrastructure in the CEE region.

## **EXPECTED BENEFITS**

Security of Supply, Market integration (market areas in Central-Eastern Europe and the Baltic States), Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (Poland and possibly Lithuania, Latvia, Estonia.), N-1 Regional (Central-Eastern Europe, Baltic Sea region), Back-up for renewables, Implementation of the investment tasks within this project will allow for significant volumes of gas to be transported by means of PL-SK interconnection. They will also enhance the access to the USG Strachocina that have large expansion potential and may serve as essential security of supply infrastructure in the CEE region.

The projects in eastern Poland are located in the area which offers the possibility to extract unconventional gas. If reserves are confirmed, the transmission infrastructure in Eastern Poland might well be used to transport unconventional gas to the Baltic states (via Gas Interconnection Poland-Lithuania) and CEE countries (via PL-SK and PL-CZ interconnections).

Construction of the pipelines within this project, together with completion of the PL-SK interconnection and GIPL, will definitely have a positive impact on the competition in the CEE and Baltic regions, as the project will provide a possibility to open the market for more gas suppliers. This would in turn mean ending the state of major dependency on one single gas supplier for the countries in the respective regions thanks to the potential access to gas deliveries from new sources.

## COMMENTS ABOUT THE PROJECT FINANCING Public financing Private financing Multilateral financing




TRA-F-248	Upgrade of gas infrastructure in northern and central Poland	FID
-----------	--	-----


**Pipeline including CS** 

SPONSORS

## GENERAL INFORMATION



Promoter	GAZ-SYSTEM S.A.	
Operator	GAZ-SYSTEM S.A.	
TEN-E Project ?	Not part of TEN-E	
Interested by PCI ?	No	
IGAs	None	
Web Link	en.gaz-system.pl/nasze-inwestycje/krajowy-system- przesylowy/	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	2007
Construction	
Commissioning	2014
Last completed Phase :	FID


TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	5
Total Pipeline Length (km)	+887,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	




PROJECTED CAPACITY INCREASES						
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone	
DESCRIPTION OF THE PROJECT						
The project consists of the internal pipelines that are currently being constructed in northern and central Poland with the aim to enhance functionality of the transmission system in Poland and, thus, provide adequate techincal conditions to distribute natural gas supplied to the LNG terminal in Świnoujście. The project is strictly linked to the development of gas infrastructure within the North-South gas interconnections in Central Eastern and South Eastern Europe. Implementation of the internal pipelines will contribute to increasing the security of supply sources, routes and counterparts, as well as to providing the overall flexibility for the gas market in Poland and the whole CEE region.						
EXPECTED BENEFITS						
Security of Supply, Market integration (market areas in the Central-Eastern Europe and possibly in the Baltic States), Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (Poland and possibly Slovakia, Hungary, Lithuania, Latvia and Estonia), N-1 Regional (Central-Eastern Europe, Baltic Sea region), Back-up for renewables,						
COMMENTS ABOUT THE PROJECT FINANCING						
Public financing	Private fina	ncing			Multilateral financing	
EEPR, ERDF (Operational Programme Infrastructure and Environment)	Equity, com	mercial bank	S			



TRA-N-274	Upgrade of PL-DE interconnection in Lasów		Non-FID
Pipeline including CS			
SPONSORS	GENERAL INFORMATION	FINANCING	



## GAZ-SYSTEM S.A. Promoter Operator GAZ-SYSTEM S.A. TEN-E Project ? **Project of Common Interest** Interested by PCI ? Yes IGAs None en.gaz-system.pl/nasze-inwestycje/ Web Link TEN-E Requests Date of Request Year Funding Granted 2012



THIRD-PARTY ACCESS REGIME				
Considered TPA Regime	Regulated			
Considered Tariff Regime	Regulated			
Applied for Exemption ?	No			
Exemption granted ?	Not relevant			
% Exemption in entry direction	0%			
% Exemption in exit direction	0%			

SCHEDULE	
End of permitting phase	
FID	2012
Construction	
Commissioning	2015
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	4
Total Pipeline Length (km)	+106,00
Total Compressor Power (MW)	+8,10
Maximum Capacity (GWh/d)	
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Lasów	Yes	entry	42.00	Hub Germany(Gaspool)	Hub Poland

## **DESCRIPTION OF THE PROJECT**

The main objective of the project is to modernize and expand the transmission system near PL-DE interconnection in Lasów with a view to upgrading the capacity of the interconnection point in Lasow from 1,5 up to 3 bcm/y. The upgraded PL-DE interconnection in Lasów will improve security of gas supplies, increase reliability of cross-border transmission infrastructure between Poland and Germany and will contribute to well-interconnected gas network in the CEE region. The upgrade of PL-DE interconnection in Lasow up to 3 bcm/y requires modernization of the transmission systems both in Poland and in Germany.

## **EXPECTED BENEFITS**

Security of Supply, Market integration (integration of market areas in Central-Eastern Europe and Western Europe (GASPOOL in Germany)), Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (Poland), N-1 Regional (Central-Eastern Europe), Back-up for renewables, The upgraded PL-DE interconnection in Lasów will have an impact on:

 $improving\ security\ of\ gas\ supplies\ and\ increasing\ reliability\ of\ cross-border\ transmission\ infrastructure\ between\ Poland\ and\ Germany;$ 

creating well-interconnected gas network in the CEE region;

enhancing the access of gas market players in the CEE region to a developed, competitive and diversified Western European gas market (Germany);

establishing adequate technical conditions necessary to cover the forecasted growth of the gas demand in Poland based on the development of the power generation sector and possible leverage for market coupling potential in Central-Eastern Europe.

Public financing	Private financing	Multilateral financing
Support from EU funds is expected		




TRA-N-276 Upgrade of the entry points in Lwówek and Włocławek on the Yamal-Europe pipeline Non-FID


**Pipeline including CS** 

**SPONSORS** 

## GENERAL INFORMATION



Promoter	GAZ-SYSTEM S.A.
Operator	GAZ-SYSTEM S.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME					
Considered TPA Regime	Regulated				
Considered Tariff Regime	Regulated				
Applied for Exemption ?	No				
Exemption granted ?	Not relevant				
% Exemption in entry direction	0%				
% Exemption in exit direction	0%				

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2015
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	2
Total Pipeline Length (km)	
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+219,60
Expected Load Factor	



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Lwowek	Yes	entry	36,60	Hub Poland	Hub Poland
Wloclawek	Yes	entry	183,00	Hub Poland	Hub Poland

## **DESCRIPTION OF THE PROJECT**

The main objective of the project is to upgrade the capacity of the entry points in Lwówek and Wloclawek on the Yamal-Europe pipeline. The project will enable to benefit from the economies of scale, as relatively low investment costs will significantly increase the possibility of gas deliveries via physical reverse flow (currently virtual reverse flow is available only) on the Yamal-Europe pipeline to entry into the transmission system in Poland and later on in the Baltic States (via Gas Interconnection Poland-Lithuania) and other CEE countries (via the North-South Gas Interconnections). This will in turn enhance the access of gas markets players in these countries to well-developed market area in Germany.

### **EXPECTED BENEFITS**

Security of Supply, Market integration (integration of market areas in the Baltic Sea region and Central-Eastern Europe with Western Europe (GASPOOL and NetConnect in Germany)), Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (Poland and possibly Lithuania, Latvia, Estonia, Slovakia, Hungary), N-1 Regional (the Baltic Sea region, Central-Eastern Europe), Back-up for renewables, The upgrade of the capacity of the entry points in Lwowek and Wloclawek on the Yamal-Europe pipeline will have an impact on:

enhancing competition in Poland and other countires in the Baltic and CEE regions by significantly facilitating the access to the Western European gas markets (in particular GASPOOL and NetConnect in Germany);

increasing security of supply in the Baltic Sea and CEE regions by diversifying supply routes and counterparts (the access to the Western European gas markets);

creating well-interconnected gas infrastructure between Western Europe (Germany), the Baltic Sea and CEE regions;

contributing to elimination of the energy islands, as the project may constitute a source of gas supplies for the Baltic States and Finland (via Gas Interconnection Poland-Lithuania);

establishing adequate technical conditions necessary to cover the forecasted growth of the gas demand in Poland based on the development of the power generation sector and possible leverage for market coupling potential in the Baltic Sea region and in Central-Eastern Europe.


Public financing	Private financing	Multilateral financing
Support from EU funds is expected		




## LNG-N-272 Upgrade of the LNG terminal in Świnoujście Non-FID LNG Terminal

SPONSORS

GENERAL INFORMATION



Promoter	GAZ-SYSTEM S.A.	
Operator	Polskie LNG S.A.	
TEN-E Project ?	Not part of TEN-E	
Interested by PCI ?	Yes	
IGAs	None	
Web Link	en.gaz-system.pl/terminal-lng/	



THIRD-PARTY ACCESS REGIME		SCHE
Considered TPA Regime	Regulated	End o
Considered Tariff Regime	Regulated	FID
Applied for Exemption ?	No	Const
Exemption granted ?	Not relevant	Comr
% Exemption in entry direction	0%	Last o
% Exemption in exit direction	0%	

SCHEDULE	
End of permitting phase	
FID	2014
Construction	
Commissioning	2020
Last completed Phase :	Planned

TECHNICAL INFORMATION	
Regasification facility	LNG terminal in Świnoujście
Expected volume (bcm/y)	+2,50
Storage capacity (m3)	+160.000,00
Send-out (mcm/d)	+6,84
Ship size (m3)	216.000,00
Reloading ability ?	Yes



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Swinoujscie	Yes	exit	75,24	LNG Terminals Poland	Hub Poland

## **DESCRIPTION OF THE PROJECT**

The main objective of the project is to upgrade the capacity of the LNG terminal in Swinoujście from 5 up to 7,5 bcm/y. The project will enable to benefit from the economies of scale, as relatively low investment costs (no need to construct the facility from scratch, the majority of costs will be related to the construction of the 3rd storage tank) may bring further benefits to gas consumers in the Baltic Sea area and the CEE region (increase of SoS, competition and liquidity, decrease of gas prices).

## **EXPECTED BENEFITS**

Security of Supply, Diversification of sources, Diversification of routes, N-1 National (Poland and possibly Lithuania, Latvia, Estonia, Denmark, Slovakia and Hungary), N-1 Regional (Baltic Sea region, Central-Eastern Europe), Back-up for renewables, The extension of the LNG terminal in Swinoujscie will have an impact on:

increasing security of supply in the Baltic Sea and CEE regions by diversifying supply routes, sources (the first new physical source of supply for both regions) and counterparts (access to global LNG market); creating well-interconnected gas infrastructure in the Baltic Sea and CEE regions:

eliminating the energy islands, as the terminal in Swinoujscie may play the role of regional LNG terminal for the Baltic States and Finland (transport of gas via Gas Interconnection Poland-Lithuania or transport by LNG vessels); enhancing competition on regional markets;

promoting natural gas as a reliable, competitive and environmentally-friendly source of energy e.g. in the transport sector (maritime transport);

creating a physical hub in Swinoujscie and/or a virtual hub in Poland;

establishing adequate technical conditions necessary to cover the forecasted growth of the gas demand in Poland based on the development of the power generation sector and possible leverage for market coupling potential in the Baltic Sea region and in Central-Eastern Europe.

The LNG terminal in Świnoujście contributes to North-South gas interconnections in Central Eastern and South Eastern Europe, as the supplies from Świnoujście may be directed through upgraded transmission system in Poland (the North-South Corridor in Poland), PL-CZ and PL-SK interconnections towards the South, to other CEE countries.


Public financing	Private financing	Multilateral financing
Support from EU funds is expected		




UGS-F-199	KPMG Kosakowo	FID

## **SPONSORS**

## GENERAL INFORMATION



Promoter	PGniG
Operator	Operator Systemu Magazynowania Sp. Z o.o.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME		
Considered TPA Regime	Regulated	
Considered Tariff Regime	Regulated	
Applied for Exemption ?	No	
Exemption granted ?	No	
% Exemption in entry direction	0%	
% Exemption in exit direction	0%	

SCHEDULE	
End of permitting phase	2021
FID	2007 Q1
Construction	2021
Commissioning	2021
Last completed Phase :	FID

TECHNICAL INFORMATION	
Storage facility	KPMG Kosakowo
Working volume (mcm)	+250,00
Injectability (mcm/d)	+2,40
Deliverability (mcm/d)	+9,60



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
UGS - PL - Gaz-System/Magazynowania	No	exit	105,60	Storage Poland	Hub Poland
	Yes	entry	26,40	Storage Poland	Hub Poland
UGS - PL - Gaz-System/Magazynowania	Yes	exit	105,60	Storage Poland	Hub Poland
	No	entry	26,40	Hub Poland	Storage Poland


DESCRIPTION OF THE PROJECT				
Construction of new underground gas storage (KPMG) to secure uninterrupted gas supplies in northern Poland.				
EXPECTED BENEFITS				
COMMENTS ABOUT THE PROJECT FINANCING				
Public financing	Private financing	Multilateral financing		




UGS-F-200	KPMG Mogilnio	FID

**SPONSORS** 

## GENERAL INFORMATION



Promoter	PGniG
Operator	Operator Systemu Magazynowania Sp. Z o.o.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2020
FID	2007 Q4
Construction	2020
Commissioning	2020
Last completed Phase :	FID

TECHNICAL INFORMATION	
Storage facility	KPMG Mogilno
Working volume (mcm)	+800,00
Injectability (mcm/d)	+9,60
Deliverability (mcm/d)	+20,64



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
UGS - PL - Gaz-System/Magazynowania	Yes	entry	105,60	Hub Poland	Storage Poland
	No	entry	105,60	Hub Poland	Storage Poland
UGS - PL - Gaz-System/Magazynowania	No	exit	227,04	Storage Poland	Hub Poland
	Yes	exit	227,04	Storage Poland	Hub Poland


DESCRIPTION OF THE PROJECT					
Under gas storage (KPMG) extension in order to increase working gas capacity					
EXPECTED BENEFITS					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private financing	Multilateral financing			




UGS-F-201	PMG Brzeznica	FID
003-1-201	FPIG DIZEZINCA	110

## **SPONSORS**

## GENERAL INFORMATION



Promoter	PGniG
Operator	Operator Systemu Magazynowania Sp. Z o.o.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2016 Q2
FID	2010 Q1
Construction	2015 Q4
Commissioning	2016 Q2
Last completed Phase :	FID

TECHNICAL INFORMATION	
Storage facility	PMG Brzeznica
Working volume (mcm)	+100,00
Injectability (mcm/d)	+1,44
Deliverability (mcm/d)	+1,44



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
UGS - PL - Gaz-System/Magazynowania	No	entry	15,84	Hub Poland	Storage Poland
	No	exit	15,84	Storage Poland	Hub Poland
UGS - PL - Gaz-System/Magazynowania	Yes	entry	15,84	Hub Poland	Storage Poland
	Yes	exit	15,84	Storage Poland	Hub Poland


DESCRIPTION OF THE PROJECT					
Underground gas storage (PMG) extension in order to increase working gas capacity injection and withdrawal rates. Instalation of compressor station to allow for a more flexible operation.					
EXPECTED BENEFITS					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private financing	Multilateral financing			




UGS-F-202	PMG Husów	FID
003 1 202	THO HUSOW	110

## **SPONSORS**

## GENERAL INFORMATION



Promoter	PGniG
Operator	Operator Systemu Magazynowania Sp. Z o.o.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2015 Q2
FID	2010 Q4
Construction	2014 Q3
Commissioning	2015 Q2
Last completed Phase :	FID

TECHNICAL INFORMATION	
Storage facility	PMG Husów
Working volume (mcm)	+500,00
Injectability (mcm/d)	+3,68
Deliverability (mcm/d)	+5,76



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
UGS - PL - Gaz-System/Magazynowania	No	exit	63,36	Storage Poland	Hub Poland
	Yes	entry	40,48	Hub Poland	Storage Poland
UGS - PL - Gaz-System/Magazynowania	Yes	exit	63,36	Storage Poland	Hub Poland
	No	entry	40,48	Hub Poland	Storage Poland


DESCRIPTION OF THE PROJECT				
Underground gas storage (PMG) extension in order to increase working gas capacity injection and withdrawal rates. Instalation of additional compressor station to allow for a more flexible opeartion.				
EXPECTED BENEFITS				
COMMENTS ABOUT THE PROJECT FINANCING				
Public financing	Private financing	Multilateral financing		




UGS-F-220	PMG Wierzchowice	FID

## **SPONSORS**

## GENERAL INFORMATION



Promoter	PGniG
Operator	Operator Systemu Magazynowania Sp. Z o.o.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2014 Q2
FID	2007 Q1
Construction	2013 Q4
Commissioning	2014 Q2
Last completed Phase :	FID

TECHNICAL INFORMATION	
Storage facility	PMG Wierzchowice
Working volume (mcm)	+1.200,00
Injectability (mcm/d)	+6,00
Deliverability (mcm/d)	+9,60



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
UGS - PL - Gaz-System/Magazynowania	Yes	exit	105,60	Storage Poland	Hub Poland
	No	exit	105,60	Storage Poland	Hub Poland
UGS - PL - Gaz-System/Magazynowania	No	entry	66,00	Hub Poland	Storage Poland
	Yes	entry	66,00	Hub Poland	Storage Poland

DESCRIPTION OF THE PROJECT				
Underground gas storage (PMG) extension in order to increase working gas capacity, injection and withdrawal rates				
EXPECTED BENEFITS				
COMMENTS ABOUT THE PROJECT FINANCING				
Public financing	Private financing	Multilateral financing		




UGS-N-219	PMG Wierzchowice extension	Non-FID


**Storage Facility** 

**SPONSORS** 

### GENERAL INFORMATION



Promoter	PGniG
Operator	Operator Systemu Magazynowania Sp. Z o.o.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	2014
Construction	
Commissioning	2022*
Last completed Phase :	Planned

TECHNICAL INFORMATION	
Storage facility	PMG Wierzchowice
Working volume (mcm)	+2.000,00
Injectability (mcm/d)	+18,00
Deliverability (mcm/d)	+25,00



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
UGS - PL - Gaz-System/Magazynowania	No	entry	198,00	Hub Poland	Storage Poland
	No	exit	275,00	Storage Poland	Hub Poland
UGS - PL - Gaz-System/Magazynowania	Yes	exit	275,00	Storage Poland	Hub Poland
	Yes	entry	198,00	Hub Poland	Storage Poland

DESCRIPTION OF THE PROJECT				
Underground gas storage (PMG) extension in order to increase working gas capacity.				
EXPECTED BENEFITS				
COMMENTS ABOUT THE PROJECT FINANCING				
Public financing	Private financing	Multilateral financing		

# Portugal








UGS-F-081	Carriço UGS development	FID


### **Storage Facility**

### SPONSORS

### GENERAL INFORMATION



Promoter	REN - Gasodutos, S.A.
Operator	REN Armazenagem
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	www.ren.pt



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	2014 Q2
Commissioning	2014 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
Storage facility	Armazenamento Subterraneo do Carrico
Working volume (mcm)	+178,00
Injectability (mcm/d)	+1,00
Deliverability (mcm/d)	+3,60



### PROJECTED CAPACITY INCREASES

Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
UGS - PT - REN Gasodutos/REN Amazenagem	Yes	exit	42,90	Storage Portugal	Hub Portugal
	Yes	entry	11,90	Hub Portugal	Storage Portugal

### **DESCRIPTION OF THE PROJECT**

Carriço UGS is based on caverns leached in a salt dome. Surface plant includes the facilities for injection and withdrawal of natural gas from the caverns in operation.

The expansion of the Carriço UGS infrastructure is a multi step / multi stage long term project mainly due to the fact that the average construction time of a salt cavern is about three years and there is a limitation to the number of caverns that can be developed simultaneously (currently two). Presently there is one new cavern under construction (leaching phase) and another one which will start filling in with gas (cushion gas and operating gas) in the 1st quarter of 2013. As for the remainder salt caverns, they may be regarded as planned since they have been integrated in the companies' business plans, together with the later capacity increase of the gas station.

### **EXPECTED BENEFITS**

Security of Supply, Market integration, N-1 National (Portugal), REN applied for PIC label for one salt cavern - RENC-8 (total estimated investment of 38,8 M€). Transgás also applied for PIC label of two salt caverns (TGC-7s and TGC-9s). The increase of storage capacity will contribute to SoS in an effective manner. It will also provide the resources for optimized management of market players' gas portfolios. Operationally, the increased storage capacity will contribute to a more efficient use of the transmission system. The capacity up-grade of the gas station will contribute to the N-1 criteria completion at a national level.

### COMMENTS ABOUT THE PROJECT FINANCING

Public financing	Private financing	Multilateral financing
	100% financing by REN Armazenagem and Transgás Armazenagem of their respective investments (two independent concessionaires)	



## TRA-N-284 PT-ES Interconnector Cantanhede Compressor Station Non-FID


### Pipeline including CS

### **SPONSORS**

# Portuguese sect on. REN Gasodutos (190K) Spanish section, Enegas S.A. (100%)

### GENERAL INFORMATION

Promoter	REN - Gasodutos, S.A.
Operator	REN - Gasodutos, S.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	www.ren.pt



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2017 Q4
FID	2016 Q4
Construction	2018 Q1
Commissioning	2019 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	
Total Compressor Power (MW)	+12,00
Maximum Capacity (GWh/d)	
Expected Load Factor	



### PROJECTED CAPACITY INCREASES Interconnection Modelled Direction Capacity (GWh/d) From Zone To Zone Mangualde (PT) / Zamora (ES) (3rd Spain / Portugal IP) 42,00 **Hub Spain Hub Portugal** Yes entry Yes exit 47,00 **Hub Portugal Hub Spain**

### **DESCRIPTION OF THE PROJECT**

The 3RD IP PORTUGAL-SPAIN is located in the priority corridor North-South in Western Europe, and involves Portugal and Spain by crossing the border between both Member States.

This project will connect both gas systems between Celorico da Beira (Portugal) and Zamora (Spain). It consists of a new set of pipelines and compression reinforcement in both countries.

### **EXPECTED BENEFITS**

Security of Supply, Market integration (Portugal and Spain hubs), Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (Portugal), Back-up for renewables, The new PT-ES interconnection will contribute to compliance with N-1 criterion for SoS (infrastructure standard) in Portugal and meet additional interconnection capacity requirements above existing IP's, increasing the short and long term resilience of the system. It will also create access axis between the UGS facilities of Carriço (PT) and Yela (ES).

### COMMENTS ABOUT THE PROJECT FINANCING

Public financing	Private financing	Multilateral financing
EEPR: € 10.7 mil	REN financing of the remaining part of the investment	



# TRA-N-285 PT-ES Interconnector Pipeline Cantanhede-Mangualde Non-FID


### Pipeline including CS

### SPONSORS

# Portuguese section, REN Gasodutos (100%) \$panish section, Enagás S.A. (100%)

### GENERAL INFORMATION

Promoter	REN - Gasodutos, S.A.
Operator	REN - Gasodutos, S.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	www.ren.pt



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2019 Q4
FID	2018 Q4
Construction	2020 Q1
Commissioning	2021 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+67,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+142,00
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Mangualde (PT) / Zamora (ES) (3rd Spain / Portugal IP)	Yes	exit	45,00	Hub Portugal	Hub Spain
	Yes	entry	25.00	Hub Spain	Hub Portugal

### **DESCRIPTION OF THE PROJECT**

The 3RD IP PORTUGAL-SPAIN is located in the priority corridor North-South in Western Europe, and involves Portugal and Spain by crossing the border between both Member States.

This project will connect both gas systems between Celorico da Beira (Portugal) and Zamora (Spain). It consists of a new set of pipelines and compression reinforcement in both countries.

### **EXPECTED BENEFITS**

Security of Supply, Market integration (Portugal and Spain hubs), Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (Portugal), Back-up for renewables, The new PT-ES interconnection will contribute to compliance with N-1 criterion for SoS (infrastructure standard) in Portugal and meet additional interconnection capacity requirements above existing IP's, increasing the short and long term resilience of the system. It will also create access axis between the UGS facilities of Carriço (PT) and Yela (ES).

### COMMENTS ABOUT THE PROJECT FINANCING

Public financing	Private financing	Multilateral financing
EEPR: € 10.7 mil	REN financing of the remaining part of the investment	



## TRA-N-283 PT-ES Interconnector Pipeline Spanish Border-Celorico Non-FID


### Pipeline including CS

### **SPONSORS**

# Spanish section Enagás S.A. (100%) Portuguese section, REN Gasodutos (100%)

### GENERAL INFORMATION

Promoter	REN - Gasodutos, S.A.
Operator	REN - Gasodutos, S.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	www.ren.pt



THIRD-PARTY ACCESS REGIME		
Considered TPA Regime	Regulated	
Considered Tariff Regime	Regulated	
Applied for Exemption ?	No	
Exemption granted ?	No	
% Exemption in entry direction	0%	
% Exemption in exit direction	0%	

SCHEDULE	
End of permitting phase	2014 Q4
FID	2013 Q4
Construction	2015 Q1
Commissioning	2017 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+158,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Mangualde (PT) / Zamora (ES) (3rd Spain / Portugal IP)	Yes	entry	75,00	Hub Spain	Hub Portugal
	Yes	exit	50,00	Hub Portugal	Hub Spain

### **DESCRIPTION OF THE PROJECT**

The 3RD IP PORTUGAL-SPAIN is located in the priority corridor North-South in Western Europe, and involves Portugal and Spain by crossing the border between both Member States.

This project will connect both gas systems between Celorico da Beira (Portugal) and Zamora (Spain). It consists of a new set of pipelines and compression reinforcement in both countries.

### **EXPECTED BENEFITS**

Security of Supply, Market integration (Portugal and Spain hubs), Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (Portugal), Back-up for renewables, The new PT-ES interconnection will contribute to compliance with N-1 criterion for SoS (infrastructure standard) in Portugal and meet additional interconnection capacity requirements above existing IP's, increasing the short and long term resilience of the system. It will also create access axis between the UGS facilities of Carriço (PT) and Yela (ES).

### COMMENTS ABOUT THE PROJECT FINANCING

Public financing	Private financing	Multilateral financing
EEPR: € 10.7 mil	REN financing of the remaining part of the investment	

# Romania









TRA-N-132 AGRI Pipeline - Romanian section (East-West	Pipeline) Non-FID
---	-------------------

**SPONSORS** 

### GENERAL INFORMATION



Promoter	Transgaz
Operator	Transgaz
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2015
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+850,00
Total Compressor Power (MW)	+42,00
Maximum Capacity (GWh/d)	+231,00
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
East-West Pipeline RO-HU (AGRI)	Yes	exit	168,00	Hub Romania	Hub Hungary
DESCRIPTION OF THE PROJECT					
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Market integration (RO, HU and HU neighbours ), Diversification	on of sources,	Diversificatio	n of routes, N-1 National (F	For RO, N-1 inrcreases from 1,	65 to 1,73), Power-to-gas, Biogas
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-F-139	Integration of the transit and transmission system - reverse flow Isaccea	FID

### **SPONSORS**

### GENERAL INFORMATION



Promoter	Transgaz
Operator	Transgaz
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	2010
Construction	
Commissioning	2013
Last completed Phase :	Permitting

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+147,00
Expected Load Factor	



Interconnection Mode				
merconnection	elled Directi	ion Capacity (GWh/d)	From Zone	To Zone
Isaccea (RO) - Orlovka (UA)	entry	0,00	Hub Bulgaria	Hub Romania
Yes	entry	147,00	Transit Ukraine	Hub Bulgaria


DESCRIPTION OF THE PROJECT			
The project implies the construction of a connection pipeline between the DN 1000 Pipeline (Transit 1 Bulgaria) and the NTS, with the possibility to meter the natural gas volumes transmitted in both directions.			
EXPECTED BENEFITS			
Security of Supply, Market integration (RO, BG, UKR), Reverse Flows, Diversification of sources, Power-to-gas, Biogas			
COMMENTS ABOUT THE PROJECT FINANCING			
Public financing	Private financing	Multilateral financing	




TRA-F-142	Reverse flow at Negru Voda	FID
Pipeline including CS		

SPONSORS

## GENERAL INFORMATION



Promoter	Transgaz
Operator	Transgaz
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	2010
Construction	
Commissioning	2013
Last completed Phase :	Permitting

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+168,00
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Negru Voda I	Yes	entry	168,00	Hub Bulgaria	Hub Romania
	No	entry	0,00	Transit Ukraine	Hub Bulgaria
Negru Voda I	No	exit	0,00	Hub Bulgaria	Transit Ukraine
	No	exit	0,00	Hub Romania	Hub Bulgaria


DESCRIPTION OF THE PROJECT				
Upgrades of technical installation currently existing at the GMS Negru Voda in order to ensure reverse flow capacity with the possibility to measure such capacity.				
EXPECTED BENEFITS				
Security of Supply, Market integration (RO; BG; UKR), Reverse Flows, Diversification of sources, Power-to-gas, Biogas				
COMMENTS ABOUT THE PROJECT FINANCING				
Public financing	Private financing	Multilateral financing		




TRA-N-126	Reverse flow on the interconnector Romania - Hungary	Non-FID
-----------	--	---------

**SPONSORS** 

### GENERAL INFORMATION



Promoter	Transgaz
Operator	Transgaz
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2013 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+12,60
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Csanadpalota	Yes	exit	12,60	<b>Hub Romania</b>	Hub Hungary
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Market integration (RO and HU markets), Reverse Flows, Diverse	rsification of s	ources, Powe	er-to-gas, Biogas		
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-F-029	RO-BG Interconnection	FID
-----------	-----------------------	-----

### SPONSORS

### GENERAL INFORMATION



Promoter	Transgaz
Operator	Transgaz
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	www.transgaz.ro



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2011 Q4
FID	2010 Q4
Construction	2013 Q2
Commissioning	2013 Q2
Last completed Phase :	Supply contract

TECHNICAL INFORMATION				
# of Pipelines, nodes, CS	1			
Total Pipeline Length (km)	+25,00			
Total Compressor Power (MW)				
Maximum Capacity (GWh/d)	+14,38			
Expected Load Factor	1,00			



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Interconnector Bulgaria-Romania (IBR)	Yes	entry	14,38	Hub Bulgaria	Hub Romania
	Yes	exit	14,38	Hub Romania	Hub Bulgaria

DESCRIPTION OF THE PROJECT		
EXPECTED BENEFITS		
	f energy, routes and supplies; increasing the degree of interconnectivity between nal gas flows; contribution to the establishment of the South-Eastern European reg	
COMMENTS ABOUT THE PROJECT FINANCING		
	Drivete financina	Naulailataval financina
Public financing	Private financing	Multilateral financing

# Slovakia









TRA-N-190	Poland - Slovakia interconnection	Non-FID
Discoling to deading CC		

**SPONSORS** 

### GENERAL INFORMATION



Promoter	eus	eustream, a.s.		
Operator	eus	tream, a.s.		
TEN-E Project ?	Project of	Project of Common Interest		
Interested by PCI ?		Yes		
IGAs		None		
Web Link	www.eustream.sk/en_traninterconnector	nsmission-system/en_pl-sk-		
TEN-E Requests	Date of Request 28/02/11	Year Funding Granted Not yet		
	20/02/11	. tot yet		



THIRD-PARTY ACCESS REGIME				
Considered TPA Regime	Regulated			
Considered Tariff Regime	Regulated			
Applied for Exemption ?	No			
Exemption granted ?	No			
% Exemption in entry direction	0%			
% Exemption in exit direction	0%			

SCHEDULE	
End of permitting phase	
FID	2014
Construction	2016
Commissioning	2016 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	2
Total Pipeline Length (km)	+180,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+176,90
Expected Load Factor	84,00%



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Interconnector PL - SK	Yes	exit	176,90	Hub Slovakia	Hub Poland
	Yes	entry	132,10	Hub Poland	Hub Slovakia
DESCRIPTION OF THE PROJECT					
To build interconnection between SK&PL transmission sys. and thus increase	the SoS in CE	E reg. &	contribute to establishing	a well-functioning internal ga	s market
EXPECTED BENEFITS					
Security of Supply, Market integration (CEE region), Reverse Flows, Diversification	of sources, D	iversification	of routes, N-1 National (Po	oland, Slovakia, Hungary), N-1	Regional (CEE region), Back-up for renewables, Power-to-gas
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing
		-			


PROJECTED CAPACITY INCREASES




TRA-F-016	Slovakia - Hungary interconnection	FID
nt a di cari a di care e e e		

SPONSORS

### GENERAL INFORMATION



Promoter	eustream, a.s.
Operator	eustream, a.s.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	1
Web Link	www.eustream.sk/en_transmission-system/en_sk-hu- interconnector



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2012 Q1
FID	2010 Q1
Construction	2014 Q2
Commissioning	2014 Q4
Last completed Phase :	Supply contract

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+115,00
Total Compressor Power (MW)	+7,00
Maximum Capacity (GWh/d)	+127,40
Expected Load Factor	80,00%



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Balassagyarmat	Yes	entry	50,90	Hub Hungary	Hub Slovakia
	Yes	exit	127,40	Hub Slovakia	Hub Hungary


DESCRIPTION OF THE PROJECT				
Creation of a missing interconnection between SK and HU and thus increase the SoS in CEE region, and enhance market integration and functionality.				
EXPECTED BENEFITS				
Security of Supply, Market integration (CEE region), Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (Slovakia, Hungary), N-1 Regional (CEE region), Back-up for renewables, Power-to-gas				
COMMENTS ABOUT THE PROJECT FINANCING				
Public financing	Private financing	Multilateral financing		
Interconnector Slovakia – Hungary: EEPR: € 3.3 mil.	eustream, a.s.			




TRA-F-017	System Enhancements - Eustream	FID

### SPONSORS

### GENERAL INFORMATION



Promoter	eustream, a.s.
Operator	eustream, a.s.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	www.eustream.sk.



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	2010
Construction	2016
Commissioning	2017
Last completed Phase :	FID

TECHNICAL INFORMATION		
# of Pipelines, nodes, CS	1	
Total Pipeline Length (km)		
Total Compressor Power (MW)		
Maximum Capacity (GWh/d)		
Expected Load Factor		



PROJECTED CAPACITY INCREASES						
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone	
DESCRIPTION OF THE PROJECT						
Modernization and Upgrade of the Network and Replacement of Technologies du	ue to Environn	nental Norms				
EXPECTED BENEFITS						
Security of Supply, Market integration, Back-up for renewables, Power-to-gas, M	odernization a	ind upgrade o	of the network and replace	ment of technologies due to e	environmental norms.	
COMMENTS ABOUT THE PROJECT FINANCING						
Public financing	Private fina	ncing			Multilateral financing	
	eustream, a	.S.				









TRA-N-093


### CS Ajdovščina (2nd phase - 4th and 5th unit on M3/1 pipeline of total power up to 20 MW)

Non-FID


### **Pipeline including CS**

SPONSORS

### GENERAL INFORMATION



Promoter	Plinovodi d.o.o.
Operator	Plinovodi d.o.o.
TEN-E Project ?	Project of Common Interest
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	www.plinovodi.si/wp-content/uploads/2011/09/RN-2013- 2022-Posvetovalni-dokument.pdf



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2022*
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	
Total Compressor Power (MW)	+20,00
Maximum Capacity (GWh/d)	
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
Cross-border transmission.					
EXPECTED BENEFITS					
Removing bottlenecks of transmission system and increase of its capacities up to the existing capacities of neighbouring transmission system operators (first phase). Ensuring additional capacities for further market development and transits, including reverse flows (second phase).					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-N-092	CS Ajdovščina (3rd unit up to 5 MW)	Non-FID

### SPONSORS

### GENERAL INFORMATION



Promoter	Plinovodi d.o.o.
Operator	Plinovodi d.o.o.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	www.plinovodi.si/wp-content/uploads/2011/09/RN-2013- 2022-Posvetovalni-dokument.pdf



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2016
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	
Total Compressor Power (MW)	+5,00
Maximum Capacity (GWh/d)	
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
Adjustment to operating parameters of the transmission system of the Italian TSO. Reverse flow.					
EXPECTED BENEFITS					
Removing bottlenecks of transmission system and increase of its capacities up to the existing capacities of neighbouring transmission system operators (first phase). Ensuring additional capacities for further market development and transits, including reverse flows (second phase).					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private finar	ncing			Multilateral financing




TRA-N-094 CS Kidričevo (2nd phase - up to 3 units with total power up to 30 MW) Non-FID


**Pipeline including CS** 

SPONSORS

### GENERAL INFORMATION



Promoter	Plinovodi d.o.o.
Operator	Plinovodi d.o.o.
TEN-E Project ?	Project of Common Interest
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	www.plinovodi.si/wp-content/uploads/2011/09/RN-2013- 2022-Posvetovalni-dokument.pdf



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2016
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	
Total Compressor Power (MW)	+30,00
Maximum Capacity (GWh/d)	
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
Takeover of natural gas from cross-border transmission pipeline to M2/1 pipeline.					
EXPECTED BENEFITS					
Removing bottlenecks of transmission system and increase of its capacities up to the existing capacities of neighbouring transmission system operators (first phase). Ensuring additional capacities for further market development and transits, including reverse flows (second phase).					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private finan	ncing			Multilateral financing




TRA-F-096 CS Kidričevo (3rd unit 3,5 MW) FID	
--	--

**SPONSORS** 

#### GENERAL INFORMATION



Promoter	Plinovodi d.o.o.
Operator	Plinovodi d.o.o.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	www.plinovodi.si/wp-content/uploads/2011/09/RN-2013- 2022-Posvetovalni-dokument.pdf



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	2011
Construction	
Commissioning	2014
Last completed Phase :	FEED

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	
Total Compressor Power (MW)	+3,50
Maximum Capacity (GWh/d)	
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
Increasing the capacity of the transmission system.					
EXPECTED BENEFITS					
Removing bottlenecks of transmission system and increase of its capacities up to the existing capacities of neighbouring transmission system operators (first phase). Ensuring additional capacities for further market development and transits, including reverse flows (second phase).					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private finar	ncing			Multilateral financing




TRA-N-095	CS Rogatec (up to 2 MW)	Non-FID

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	Plinovodi d.o.o.
Operator	Plinovodi d.o.o.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	www.plinovodi.si/wp-content/uploads/2011/09/RN-2013-2022-Posvetovalni-dokument.pdf



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2022*
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	
Total Compressor Power (MW)	+2,00
Maximum Capacity (GWh/d)	
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
Connection to the transmission system of the Croatian TSO. Reverse flow.					
EXPECTED BENEFITS					
Removing bottlenecks of transmission system and increase of its capacities up to the existing capacities of neighbouring transmission system operators (first phase). Ensuring additional capacities for further market development and transits, including reverse flows (second phase).					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private finar	ncing			Multilateral financing



TRA-N-102


# CS Vodice II (on M2/1 pipeline up to 3 units with total power up to 30 MW)

Non-FID


# **Pipeline including CS**

SPONSORS

## GENERAL INFORMATION



Promoter	Plinovodi d.o.o.
Operator	Plinovodi d.o.o.
TEN-E Project ?	Project of Common Interest
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	www.plinovodi.si/wp-content/uploads/2011/09/RN-2013-2022-Posvetovalni-dokument.pdf



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2022*
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	
Total Compressor Power (MW)	+30,00
Maximum Capacity (GWh/d)	
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
Compressor station on the M2/1 pipeline for cross-border transmission.					
EXPECTED BENEFITS					
EAFECIED BENEFITS					
Removing bottlenecks of transmission system and increase of its capacities up to	the existing o	anacities of n	oighbouring transmission s	ustom operators (first phase)	
Ensuring additional capacities for further market development and transits, include				ystem operators (mist phase).	
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-N-103	Godovič - Žiri - Škofja Loka	Non-FID

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	Plinovodi d.o.o.			
Operator	Plinovodi d.o.o.			
TEN-E Project ?	Not part of TEN-E			
Interested by PCI ?	No			
IGAs	None			
Web Link	www.plinovodi.si/wp-content/uploads/2011/09/RN-2013- 2022-Posvetovalni-dokument.pdf			



THIRD-PARTY ACCESS REGIME				
Considered TPA Regime	Regulated			
Considered Tariff Regime	Regulated			
Applied for Exemption ?	No			
Exemption granted ?	No			
% Exemption in entry direction	0%			
% Exemption in exit direction	0%			

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2022*
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+44,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE REQUEST					
DESCRIPTION OF THE PROJECT					
Connecting new municipalities. Transmission system loop.					
Connecting new municipalities. Transmission system loop.					
EXPECTED BENEFITS					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-N-109	M1/3 SLO-A border crossing	Non-FID

### **SPONSORS**

#### GENERAL INFORMATION



Promoter	Plinovodi d.o.o.		
Operator	Plinovodi d.o.o.		
TEN-E Project ?	Project of Common Interest		
Interested by PCI ?	Not defined yet		
IGAs	None		
Web Link	www.plinovodi.si/wp-content/uploads/2011/09/RN-2013- 2022-Posvetovalni-dokument.pdf		



THIRD-PARTY ACCESS REGIME				
Considered TPA Regime	Regulated			
Considered Tariff Regime	Regulated			
Applied for Exemption ?	No			
Exemption granted ?	No			
% Exemption in entry direction	0%			
% Exemption in exit direction	0%			

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2022*
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+0,20
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+181,35
Expected Load Factor	70,00%




PROJECTED CAPACITY INCREASES						
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone	
	No	entry	181,35	Hub Austria	Hub Slovenia	
DESCRIPTION OF THE PROJECT						
Adjustment to operating parameters of the transmission system of the Austrian T	SO, with para	llel connectio	on to the existing pipeline.			
EXPECTED BENEFITS						
Removing bottlenecks of transmission system and increase of its capacities up to				ystem operators (first phase)		
Ensuring additional capacities for further market development and transits, include	ding reverse fl	lows (second	phase)			
COMMENTS ABOUT THE PROJECT FINANCING						
Public financing	Private fina	ncing			Multilateral financing	




TRA-N-100	M10 Vodice - Rateče	Non-FID

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	Plinov	Plinovodi d.o.o.			
Operator	Plinov	odi d.o.o.			
TEN-E Project ?	Project of C	Project of Common Interest			
Interested by PCI ?		Yes			
IGAs	ſ	None			
Web Link	www.plinovodi.si/wp-content/uploads/2011/09/RN-2013- 2022-Posvetovalni-dokument.pdf				
TEN-E Requests	Date of Request 28/02/11	Year Funding Granted Not yet			
	1/04/10	2011			



THIRD-PARTY ACCESS REGIME				
Considered TPA Regime	Negotiated (e.g. Exemption)			
Considered Tariff Regime	Negotiated (e.g. Exemption)			
Applied for Exemption ?	Not yet			
Exemption granted ?	Not yet			
% Exemption in entry direction	0%			
% Exemption in exit direction	0%			

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2017
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+79,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+289,00
Expected Load Factor	90,00%



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Tarvisio (IT) /Rateče (SI)	No	exit	754,00	<b>Hub Slovenia</b>	Hub Italia
	Yes	exit	289,00	Hub Slovenia	Hub Italia


DESCRIPTION OF THE PROJECT		
Cross-border transmission.		
EXPECTED BENEFITS		
Security of Supply, Market integration, Reverse Flows, Diversification of sources, Diversification of routes, N-1 National, N-1 Regional		
COMMENTS ABOUT THE PROJECT FINANCING		
Public financing	Private financing	Multilateral financing




TRA-F-104	M2/1 Rogaška Slatina – Trojane	FID

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	Plinovodi d.o.o.
Operator	Plinovodi d.o.o.
TEN-E Project ?	Project of Common Interest
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	www.plinovodi.si/wp-content/uploads/2011/09/RN-2013- 2022-Posvetovalni-dokument.pdf



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	2010
Construction	2013
Commissioning	2014
Last completed Phase :	Supply contract

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+65,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+13,97
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
Increasing the capacity of the transmission system.					
EXPECTED BENEFITS					
Removing bottlenecks of transmission system and increase of its capacities up to t Ensuring additional capacities for further market development and transits, includ	he existing caing reverse fl	apacities of ne ows (second p	eighbouring transmission sy phase)	/stem operators (first phase)	
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-F-097	M2/1 Trojane – Vodice	FID

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	Plinovodi d.o.o.
Operator	Plinovodi d.o.o.
TEN-E Project ?	Project of Common Interest
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	www.plinovodi.si/wp-content/uploads/2011/09/RN-2013- 2022-Posvetovalni-dokument.pdf



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	2010
Construction	2013
Commissioning	2014
Last completed Phase :	Supply contract

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+34,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+13,97
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
Increasing the capacity of the transmission system.					
EXPECTED BENEFITS					
Removing bottlenecks of transmission system and increase of its capacities up to the existing capacities of neighbouring transmission system operators (first phase) Ensuring additional capacities for further market development and transits, including reverse flows (second phase)					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-N-108	M3 pipeline reconstruction from CS Ajdovščina to Šempeter/Gorizia	Non-FID
		1

SPONSORS

#### GENERAL INFORMATION



Promoter	Plinovo	odi d.o.o.		
Operator	Plinovo	Plinovodi d.o.o.		
TEN-E Project ?	Project of Co	Project of Common Interest		
Interested by PCI ?	Not de	Not defined yet		
IGAs	None			
Web Link	www.plinovodi.si/wp-content 2022-Posvetovalni-dokument			
TEN-E Requests	Date of Request 1/04/10	Year Funding Granted 2011		



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2022*
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+31,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+25,40
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Šempeter/Gorizia	Yes	exit	25,40	Hub Slovenia	Hub Italia
	Yes	exit	62,99	Hub Slovenia	Hub Italia


DESCRIPTION OF THE PROJECT					
Adjustment to operating parameters of the transmission system of the Italian TSO.					
EXPECTED BENEFITS					
Removing bottlenecks of transmission system and increase of its capacities up to the existing capacities of neighbouring transmission system operators (first phase) Ensuring additional capacities for further market development and transits, including reverse flows (second phase)					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private financing	Multilateral financing			




TRA-N-099	M3/1a Gorizia/Šempeter - Ajdovščina	Non-FID
Pineline including CS		

# SPONSORS

# GENERAL INFORMATION



Promoter	Pline	Plinovodi d.o.o.		
Operator	Pline	Plinovodi d.o.o.		
TEN-E Project ?	Project of	Project of Common Interest		
Interested by PCI ?		Yes		
IGAs		None		
Web Link		www.plinovodi.si/wp-content/uploads/2011/09/RN-2013- 2022-Posvetovalni-dokument.pdf		
TEN-E Requests	Date of Request 28/02/11	Year Funding Granted Not yet		



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	Not yet
Exemption granted ?	Not yet
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2017
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+29,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+102,00
Expected Load Factor	75,00%



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Gorizia (IT) /Šempeter (SI)	Yes	exit	340,00	Hub Slovenia	Hub Italia
	No	exit	102,00	Hub Slovenia	Hub Italia


DESCRIPTION OF THE PROJECT					
Cross-border transmission.					
EXPECTED BENEFITS					
Security of Supply, Market integration, Reverse Flows, Diversification of sources, Diversification of routes, N-1 National, N-1 Regional					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private financing	Multilateral financing			




TRA-N-262	M3/1b Ajdovščina - Kalce	Non-FID
	and the control of th	

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	Plinov	Plinovodi d.o.o.			
Operator	Plinov	Plinovodi d.o.o.			
TEN-E Project ?	Project of Co	Project of Common Interest			
Interested by PCI ?		Yes			
IGAs	P	None			
Web Link	www.plinovodi.si/wp-conter 2022-Posvetovalni-dokumen	nt/uploads/2011/09/RN-2013- t.pdf			
TEN-E Requests	Date of Request 28/02/11	Year Funding Granted Not yet			



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	Not yet
Exemption granted ?	Not yet
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2017
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+24,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+102,00
Expected Load Factor	75,00%




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
Cross-border transmission.					
EXPECTED BENEFITS					
Security of Supply, Market integration, Reverse Flows, Diversification of sources, I	Diversification	of routes N	-1 National N-1 Regional		
Security of Supply, Market integration, Neverse Flows, Diversification of Sources, L	olver silication	i oi routes, iv	-1 National, N-1 Regional		
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-N-261	M3/1c Kalce - Vodice	Non-FID
	110, 20 110100	11011 1 22

### **SPONSORS**

#### GENERAL INFORMATION



Promoter	Pline	Plinovodi d.o.o.			
Operator	Pline	Plinovodi d.o.o.			
TEN-E Project ?	Project of	Project of Common Interest			
Interested by PCI ?		Yes			
IGAs		None			
Web Link		www.plinovodi.si/wp-content/uploads/2011/09/RN-2013-2022-Posvetovalni-dokument.pdf			
TEN-E Requests	Date of Request 28/02/11	Year Funding Granted Not yet			



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	Not yet
Exemption granted ?	Not yet
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2017
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+47,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+289,00
Expected Load Factor	75,00%




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
Cross-border transmission.					
EXPECTED BENEFITS					
Security of Supply, Market integration, Reverse Flows, Diversification of sources, Diversification of routes, N-1 National, N-1 Regional					
Security of Supply, Market integration, Neverse Flows, Diversification of Sources, L	olver silication	i oi routes, iv	-1 National, N-1 Regional		
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-F-105	M5 + R51 Vodice - TE-TOL	FID

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	Plinovodi d.o.o.
Operator	Plinovodi d.o.o.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	www.plinovodi.si/wp-content/uploads/2011/09/RN-2013- 2022-Posvetovalni-dokument.pdf



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	2006
Construction	
Commissioning	2015
Last completed Phase :	Permitting

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+19,50
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+13,97
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
Connection to the CHP station TE-TOL for the Municipality of Ljubljana.					
EXPECTED BENEFITS					
Removing bottlenecks of transmission system and increase of its capacities up to the existing capacities of neighbouring transmission system operators (first phase) Ensuring additional capacities for further market development and transits, including reverse flows (second phase)					
Ensuring additional capacities for farther market development and a disciss, made	anig reverse r	10 W3 (3000114	priusey		
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncina			Multilateral financing
Public Illiancing	Private iiia	incing			Multilateral illianting




TRA-N-106	M5 Jarše - Novo mesto	Non-FID

#### **SPONSORS**

#### **GENERAL INFORMATION**



Promoter	Plinovodi d.o.o.
Operator	Plinovodi d.o.o.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	www.plinovodi.si/wp-content/uploads/2011/09/RN-2013- 2022-Posvetovalni-dokument.pdf



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2022*
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+66,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
Connecting new municipalities. Transmission system loop.					
EXPECTED BENEFITS					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-N-107	M6 Ajdovščina - Lucija	Non-FID
Pipeline including CS		

SPONSORS

# GENERAL INFORMATION



Promoter	Plinov	odi d.o.o.		
Operator	Plinov	odi d.o.o.		
TEN-E Project ?	Project of Co	Project of Common Interest		
Interested by PCI ?	Not de	Not defined yet		
IGAs	N	lone		
Web Link	www.plinovodi.si/wp-content/uploads/2011/09/RN-2013- 2022-Posvetovalni-dokument.pdf			
TEN-E Requests	Date of Request 28/02/11	Year Funding Granted		
	28/02/11	Not yet		



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2015
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	2
Total Pipeline Length (km)	+73,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+2,31
Expected Load Factor	



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
San Dorligo della Valle (IT) /Osp (SI)	Yes	entry	6,10	Hub Italia	Hub Slovenia
DESCRIPTION OF THE PROJECT					
Connecting the Coastal-Karst region and the DSO in the Municipality of Koper.					
EXPECTED BENEFITS					

PROJECTED CAPACITY INCREASES

COMMENTS ABOUT THE PROJECT FINANCING

Public financing

Multilateral financing


Private financing




TRA-N-101	M8 Kalce - Jelšane	Non-FID

### SPONSORS

#### GENERAL INFORMATION



Promoter	Plinovo	odi d.o.o.		
Operator	Plinovo	odi d.o.o.		
TEN-E Project ?	Project of Co	Project of Common Interest		
Interested by PCI ?	Yes			
IGAs	None			
Web Link	www.plinovodi.si/wp-content/uploads/2011/09/RN-2013- 2022-Posvetovalni-dokument.pdf			
TEN-E Requests	Date of Request 27/02/12	Year Funding Granted Not yet		



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2017
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+51,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+414,00
Expected Load Factor	80,00%



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Zlobin (Croatia) - Rupa (Slovenia)	Yes	entry	414,00	<b>Hub Croatia</b>	Hub Slovenia
DESCRIPTION OF THE PROJECT					
Interconnector with the transmission system of the Croatian TSO.					
EVALUATED DENIFIES					
EXPECTED BENEFITS					
Security of Supply, Market integration, Reverse Flows, Diversification of sources,	Diversification	of routes, N	-1 National, N-1 Regional		
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing
i done maneng	i iivate iiiia	iiciiig			manacca maneng

PROJECTED CAPACITY INCREASES




TRA-N-098 M9a Lendava - Kidričevo (including CS Kidričevo 3rd phase with up to 5 units of total power up to 80 MW)

Non-FID


**Pipeline including CS** 

SPONSORS

# GENERAL INFORMATION



Promoter	Plino	ovodi d.o.o.		
Operator	Plino	Plinovodi d.o.o.		
TEN-E Project ?	Project of	Project of Common Interest		
Interested by PCI ?		Yes		
IGAs		None		
Web Link	· · · · · · · · · · · · · · · · · · ·	www.plinovodi.si/wp-content/uploads/2011/09/RN-2013-2022-Posvetovalni-dokument.pdf		
TEN-E Requests	Date of Request 28/02/11	Year Funding Granted  Not yet		



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	Not yet
Exemption granted ?	Not yet
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2016
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+72,00
Total Compressor Power (MW)	+80,00
Maximum Capacity (GWh/d)	+288,00
Expected Load Factor	90,00%



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Interconnector SI-HU	No	entry	819,00	Hub Hungary	Hub Slovenia
	Yes	entry	288,00	Hub Hungary	Hub Slovenia

DESCRIPTION OF THE PROJECT				
Cross-border transmission.				
EXPECTED BENEFITS				
Security of Supply, Market integration, Reverse Flows, Diversification of sources, Diversification of routes, N-1 National, N-1 Regional				
COMMENTS ABOUT THE PROJECT FINANCING				
Public financing	Private financing	Multilateral financing		




TRA-N-263 M9b Kidričevo - Vodice (including CS Vodice I - 4 units with total power up to 60 MW)

Non-FID


# Pipeline including CS

# SPONSORS

## GENERAL INFORMATION



Promoter	Plinovodi d.o.o.			
Operator	Plinovo	Plinovodi d.o.o.		
TEN-E Project ?	Project of Common Interest			
Interested by PCI ?	Yes			
IGAs	None			
Web Link	www.plinovodi.si/wp-content/uploads/2011/09/RN-2013- 2022-Posvetovalni-dokument.pdf			
TEN-E Requests	Date of Request 27/02/12	Year Funding Granted Not yet		



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	Not yet
Exemption granted ?	Not yet
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2018
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+115,00
Total Compressor Power (MW)	+60,00
Maximum Capacity (GWh/d)	+288,00
Expected Load Factor	90,00%




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
Cross-border transmission.					
EXPECTED BENEFITS					
Security of Supply, Market integration, Reverse Flows, Diversification of sources, I	Diversification	of routes N	-1 National N-1 Regional		
Security of Supply, Market integration, Neverse Flows, Diversification of Sources, L	olver silication	i oi routes, iv	-1 National, N-1 Regional		
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-N-111	M9c Interconnector with Croatia	Non-FID

**SPONSORS** 

#### GENERAL INFORMATION



Promoter	Plinovodi d.o.o.
Operator	Plinovodi d.o.o.
TEN-E Project ?	Project of Common Interest
Interested by PCI ?	Yes
IGAs	None
Web Link	www.plinovodi.si/wp-content/uploads/2011/09/RN-2013- 2022-Posvetovalni-dokument.pdf



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	Not yet
Exemption granted ?	Not yet
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2016
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+30,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+288,00
Expected Load Factor	90,00%



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Zlobin (Croatia) - Rupa (Slovenia)	No	entry	288,00	Hub Croatia	Hub Slovenia
	No	entry	819,00	Hub Croatia	Hub Slovenia


DESCRIPTION OF THE PROJECT				
Cross-border transmission.				
EXPECTED BENEFITS				
Security of Supply, Market integration, Reverse Flows, Diversification of sources, Diversification of routes, N-1 National, N-1 Regional				
COMMENTS ABOUT THE PROJECT FINANCING				
Public financing	Private financing	Multilateral financing		




TRA-F-110	MRS Šempeter - reconstruction	FID

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	Plinovodi d.o.o.
Operator	Plinovodi d.o.o.
TEN-E Project ?	Project of Common Interest
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	www.plinovodi.si/wp-content/uploads/2011/09/RN-2013- 2022-Posvetovalni-dokument.pdf



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	2012
Construction	2014
Commissioning	2014
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	
Total Pipeline Length (km)	
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Gorizia (IT) /Šempeter (SI)	Yes	exit	25,00	Hub Slovenia	Hub Italia


DESCRIPTION OF THE PROJECT					
Adjustment to operating parameters of the transmission system to the Italian TSO. Reverse flow.					
EXPECTED BENEFITS					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private financing	Multilateral financing			




TRA-N-112	R15/1 Lendava - Kidričevo	Non-FID

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	Plinov	Plinovodi d.o.o.			
Operator	Plinov	Plinovodi d.o.o.			
TEN-E Project ?	Project of C	Project of Common Interest			
Interested by PCI ?		Yes			
IGAs		1			
Web Link	www.plinovodi.si/wp-conter 2022-Posvetovalni-dokumer	nt/uploads/2011/09/RN-2013- t.pdf			
TEN-E Requests	Date of Request 1/04/10	Year Funding Granted Not yet			
	27/02/12	Not yet			



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2018
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+70,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+38,00
Expected Load Factor	70,00%



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Interconnector SI-HU	No	entry	38,00	Hub Hungary	Hub Slovenia
DESCRIPTION OF THE PROJECT					
Interconnector with the transmission system of the Hungarian TSO.					
EXPECTED BENEFITS					
Security of Supply, Market integration, Reverse Flows, Diversification of sources,	Diversification	of routes, N	-1 National, N-1 Regional		
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncina			Multilateral financing
rusiic iiiaiiciiig	Frivate illia	nung			indicial infalling

PROJECTED CAPACITY INCREASES




# TRA-N-122 R21AZ Zreče Loop (Slovenske Konjice 2nd phase) Non-FID


Pipeline including CS

SPONSORS

## GENERAL INFORMATION



Promoter	Plinovodi d.o.o.
Operator	Plinovodi d.o.o.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	www.plinovodi.si/wp-content/uploads/2011/09/RN-2013- 2022-Posvetovalni-dokument.pdf



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2022*
Last completed Phase :	Planned
Commissioning	

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+21,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
Transmission system loop. Connecting the DSO in the Municipality of Oplotnica.					
EVALUATED DENIFITY					
EXPECTED BENEFITS					
	#h =!-#!		-:		
Removing bottlenecks of transmission system and increase of its capacities up to Ensuring additional capacities for further market development and transits, inclu-				system operators (first phase)	
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-N-119	R25/1 Trojane - Hrastnik	Non-FID
	KED/ = 110june 111ubunk	

**SPONSORS** 

#### GENERAL INFORMATION



Promoter	Plinovodi d.o.o.
Operator	Plinovodi d.o.o.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	www.plinovodi.si/wp-content/uploads/2011/09/RN-2013- 2022-Posvetovalni-dokument.pdf



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2022*
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+21,50
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+13,72
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
Increasing the capacity of the transmission system for the region. Connection to	the power sta	tion.			
EXPECTED BENEFITS					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-N-121	R297B Šenčur - Cerklje	Non-FID

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	Plinovodi d.o.o.
Operator	Plinovodi d.o.o.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	www.plinovodi.si/wp-content/uploads/2011/09/RN-2013- 2022-Posvetovalni-dokument.pdf



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2022*
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+4,50
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+2,54
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
Connecting the DSO in the Municipality of Cerklje.					
EXPECTED BENEFITS					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-N-113	R38 Kalce - Godovič	Non-FID

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	Plinovodi d.o.o.
Operator	Plinovodi d.o.o.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	www.plinovodi.si/wp-content/uploads/2011/09/RN-2013-2022-Posvetovalni-dokument.pdf



THIRD-PARTY ACCESS REGIME		
Considered TPA Regime	Regulated	
Considered Tariff Regime	Regulated	
Applied for Exemption ?	No	
Exemption granted ?	No	
% Exemption in entry direction	0%	
% Exemption in exit direction	0%	

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2022*
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+11,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+1,52
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
Connecting the DSO in the Municipality of Idrija.					
EXPECTED BENEFITS					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private finar	ncing			Multilateral financing




TRA-N-118	R45 Novo mesto - Bela Krajina	Non-FID

**SPONSORS** 

#### GENERAL INFORMATION



Promoter	Plinovodi d.o.o.
Operator	Plinovodi d.o.o.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	www.plinovodi.si/wp-content/uploads/2011/09/RN-2013- 2022-Posvetovalni-dokument.pdf



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2022*
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+39,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+3,15
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
Connecting three municipalities in Bela Krajina region (Southeast Slovenia).					
EXPECTED BENEFITS					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-N-117	R51a Jarše - Sneberje, MRS Jarše	Non-FID
	The La bander of the bander	

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	Plinovodi d.o.o.
Operator	Plinovodi d.o.o.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	www.plinovodi.si/wp-content/uploads/2011/09/RN-2013- 2022-Posvetovalni-dokument.pdf



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2022*
Last completed Phase :	Planned
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+3,50
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
Transmission system loop.					
EXPECTED BENEFITS					
COMMENTS ABOUT THE PROJECT FINANCING	- 1 . 6				
Public financing	Private fina	ncing			Multilateral financing




TRA-N-116	R51b TE-TOL - Fužine/Vevče	Non-FID

### **SPONSORS**

#### GENERAL INFORMATION



Promoter	Plinovodi d.o.o.
Operator	Plinovodi d.o.o.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	www.plinovodi.si/wp-content/uploads/2011/09/RN-2013-2022-Posvetovalni-dokument.pdf



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2022*
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+4,50
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+1,52
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
System loop and increasing the capacity of the transmission system.					
EXPECTED BENEFITS					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-N-115	R51c Kozarje - Vevče, MRS Kozarje	Non-FID

SPONSORS

#### GENERAL INFORMATION



Promoter	Plinovodi d.o.o.
Operator	Plinovodi d.o.o.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	www.plinovodi.si/wp-content/uploads/2011/09/RN-2013- 2022-Posvetovalni-dokument.pdf



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2022*
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+15,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
Transmission system loop.					
EXPECTED BENEFITS					
COMMENTS ABOUT THE PROJECT FINANCING	- 1 . 6				
Public financing	Private fina	ncing			Multilateral financing




	· ·	
TRA-N-120	R52 Kleče - TOŠ	Non-FID

### **SPONSORS**

#### GENERAL INFORMATION



Promoter	Plinovodi d.o.o.
Operator	Plinovodi d.o.o.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	www.plinovodi.si/wp-content/uploads/2011/09/RN-2013- 2022-Posvetovalni-dokument.pdf



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2022*
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+4,50
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+6,99
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
Connection to the CHP station TOŠ for the Municipality of Ljubljana.					
EXPECTED BENEFITS					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-N-114	R61 Lucija - Sečovlje	Non-FID

#### SPONSORS

#### GENERAL INFORMATION



Promoter	Plinovodi d.o.o.
Operator	Plinovodi d.o.o.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	www.plinovodi.si/wp-content/uploads/2011/09/RN-2013- 2022-Posvetovalni-dokument.pdf



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2021
Last completed Phase :	Planned


TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+10,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	+2,31
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Sečovlje	Yes	entry	2,31	Hub Croatia	Hub Slovenia
	No	entry	5,08	Hub Croatia	Hub Slovenia

DESCRIPTION OF THE PROJECT		
Possible interconnector with the transmission system of the Croatian TSO.		
EXPECTED BENEFITS		
COMMENTS ABOUT THE PROJECT FINANCING		
Public financing	Private financing	Multilateral financing











LNG-F-152	Bilbao Send-Out increase 1000000	FID

### SPONSORS

## **GENERAL INFORMATION**



Promoter	BBG
Operator	BBG
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME		SCHEDUL
Considered TPA Regime	Regulated	End of pe
Considered Tariff Regime	Regulated	FID
Applied for Exemption ?	No	Construct
Exemption granted ?	No	Commiss
% Exemption in entry direction	0%	Last com
% Exemption in exit direction	0%	

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2015 Q4
Last completed Phase :	FID

TECHNICAL INFORMATION	
Regasification facility	Bilbao LNG Terminal
Expected volume (bcm/y)	
Storage capacity (m3)	
Send-out (mcm/d)	+4,80
Ship size (m3)	
Reloading ability ?	No




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Bilbao	Yes	exit	55,80	LNG Terminals Spain	Hub Spain
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Market Integration, Enhancement of Internal Network; Reduction of internal congestion, N-1 compliance, Integration of LNG plants, Integ	gration of UG:	S, Integration	of new Gas fired power pla	ants	
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




LNG-N-154	Bilbao Send-Out increase 1200000	Non-FID

**SPONSORS** 

#### GENERAL INFORMATION



Promoter	BBG
Operator	BBG
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME		so
Considered TPA Regime	Regulated	Er
Considered Tariff Regime	Regulated	FI
Applied for Exemption ?	No	Co
Exemption granted ?	No	Co
% Exemption in entry direction	0%	La
% Exemption in exit direction	0%	

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2018 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
Regasification facility	Bilbao LNG Terminal
Expected volume (bcm/y)	
Storage capacity (m3)	
Send-out (mcm/d)	+4,80
Ship size (m3)	
Reloading ability ?	No



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Bilbao	Yes	exit	55,80	LNG Terminals Spain	Hub Spain

						łΕ				

#### **EXPECTED BENEFITS**

Security of Supply, Market integration (Iberian Peninsula with Europe), Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (Spain), N-1 Regional (North-south in Western Europe), Back-up for renewables, Enhancement of Internal Network; reduction of internal congestion, N-1 compliance, Integration of LNG plants, Integration of UGS, Integration of new Gas fired power plants.

Bilbao send out increase to 1.200.000 Nm3/h is part of the of the paralell core network in the Spanish System to develop the 3rd Interconnection project between Spain and Portugal, which has been submitted as a PCI. From a European perspective, this project contributes to integrate the European systems and, therefore, an internal gas market development, fulfilling the objectives of the European Union policies and guidelines. This project linked and supplemented with the full development of the IBERIAN-FRENCH CORRIDOR, ensure that no Member State is isolated from the European network, as well as, reinforce the security of supply in any system, increasing the solidarity between countries in all of Europe.

The project has significant impact on cross-border because of the notable increase of the capacity at the Portugal-Spanish border and is part of the development of the Iberian Gas Market (MIBGAS) which mainly aims to achieve a single market in the Iberian Peninsula by developing cross border infrastructures to enhance transmission fluidity between Portugal and Spain.

#### COMMENTS ABOUT THE PROJECT FINANCING


Public financing	Private financing	Multilateral financing




LNG-N-153	Bilbao Send-Out increase 1400000	Non-FID

SPONSORS

#### GENERAL INFORMATION



Promoter	BBG
Operator	BBG
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME		SCHE
Considered TPA Regime	Regulated	End o
Considered Tariff Regime	Regulated	FID
Applied for Exemption ?	No	Const
Exemption granted ?	No	Comn
% Exemption in entry direction	0%	Last c
% Exemption in exit direction	0%	

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2019 Q4
Last completed Phase :	Planned




PROJECTED CAPACITY INCREASES						
Interconnection	Modelled	Direction	Capacity (G	GWh/d)	From Zone	To Zone
Bilbao	Yes	exit	5	55,80	LNG Terminals Spain	Hub Spain
DESCRIPTION OF THE PROJECT						
EXPECTED BENEFITS						
Security of Supply, Market integration (Iberian Peninsula with Europe), Reverse Enhancement of Internal Network, reduction of internal congestion, N-1 complian						
COMMENTS ABOUT THE PROJECT FINANCING						
Public financing	Private fina	ncing				Multilateral financing




LNG-F-150	Bilbao's 3rd LNG Storage Tank	FID

## SPONSORS

# GENERAL INFORMATION



Promoter	BBG
Operator	BBG
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME		S
Considered TPA Regime	Regulated	E
Considered Tariff Regime	Regulated	F
Applied for Exemption ?	No	С
Exemption granted ?	No	С
% Exemption in entry direction	0%	L
% Exemption in exit direction	0%	

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2014 Q4
Last completed Phase :	Construction

TECHNICAL INFORMATION	
Regasification facility	Bilbao LNG Terminal
Expected volume (bcm/y)	
Storage capacity (m3)	+150.000,00
Send-out (mcm/d)	
Ship size (m3)	
Reloading ability ?	No



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Market Integration, Enhancement of Internal Network, reducti	on of internal	congestion, N	N-1 compliance, Integration	of LNG plants, Integration of	UGS, Integration of new Gas fired power plants
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




LNG-N-151	Bilbao's 4th LNG Storage Tank	Non-FID


**LNG Terminal** 

**SPONSORS** 

#### GENERAL INFORMATION



Promoter	BBG			
Operator	BBG			
TEN-E Project ?	Not part of TEN-E			
Interested by PCI ?	No			
IGAs	None			
Web Link				



THIRD-PARTY ACCESS REGIME				
Considered TPA Regime	Regulated			
Considered Tariff Regime	Regulated			
Applied for Exemption ?	No			
Exemption granted ?	No			
% Exemption in entry direction	0%			
% Exemption in exit direction	0%			

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2018 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
Regasification facility	Bilbao LNG Terminal
Expected volume (bcm/y)	
Storage capacity (m3)	+150.000,00
Send-out (mcm/d)	
Ship size (m3)	
Reloading ability ?	No




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Market Integration, Enhancement of Internal Network, reducti	on of internal	congestion, N	N-1 compliance, Integration	of LNG plants, Integration of	UGS, Integration of new Gas fired power plants
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-N-278 Castropodame-Zamora Non-FI	D
--------------------------------------	---

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	Enagás S.A.				
Operator	Enagás S.A.				
TEN-E Project ?	Not part of TEN-E				
Interested by PCI ?	Yes				
IGAs	None				
Web Link					



THIRD-PARTY ACCESS REGIME				
Considered TPA Regime	Regulated			
Considered Tariff Regime	Regulated			
Applied for Exemption ?	No			
Exemption granted ?	No			
% Exemption in entry direction	0%			
% Exemption in exit direction	0%			

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2017 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+170,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
EVALUATED DENIETIES					
EXPECTED BENEFITS					
Security of Supply, Market integration (Spain and Portugal), Reverse Flows, Dive	rsification of	sources Dive	profication of routes N. 1.	National (Portugal) N. 1 Pogis	anal (South are region). Back up for renowables. Enhancement of Interna
Network; reduction of internal congestion, N-1 compliance, Integration of LNG pl			· · · · · · · · · · · · · · · · · · ·	, , ,	onal (South gas region), back-up for renewables, Enhancement of interna
Castropodame-Zamora pipeline is part of the of the paralell core network in the project contributes to integrate the European systems and, therefore, an interest of the paralell core network in the project contributes to integrate the European systems and, therefore, an interest of the paralell core network in the project contributes to integrate the European systems and, therefore, an integrate the paralell core network in the project contributes to integrate the European systems and the paralell core network in the project contributes to integrate the European systems and the paralell core network in the project contributes to integrate the European systems and the paralell core network in the project contributes to integrate the European systems and the paralell core network in the project contributes to integrate the European systems and the project contributes to integrate the European systems and the paralel core network in the project contributes to integrate the European systems and the European systems and the European systems and the European systems and the European systems are not contributed to the European systems and the European systems are not contributed to the European systems and the European systems are not contributed to the European systems and the European systems are not contributed to the European systems are not contributed to the European systems and the European systems are not contributed to the European systems are not contributed to the European system systems are not contributed to the European system systems are not contributed to the European system systems are not contributed to the European systems are not contributed to the European system systems are not contributed to the European system systems are not contributed to the European systems are not contribut		•			
development of the IBERIAN-FRENCH CORRIDOR, ensure that no Member State is					
The project has significant impact on cross-border because of the notable increa market in the Iberian Peninsula by developing cross border infrastructures to enh		•	• .		of the Iberian Gas Market (MIBGAS) which mainly aims to achieve a single
market in the iberian Fermisula by developing cross border infrastructures to emi	ance transim	ssion naturely i	between Fortugal and Spai		
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-F-156	CS Border at Biriatou)	FID

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	Enagás S.A.			
Operator	Enagás S.A.			
TEN-E Project ?	Not part of TEN-E			
Interested by PCI ?	No			
IGAs	None			
Web Link				



THIRD-PARTY ACCESS REGIME					
Considered TPA Regime	Regulated				
Considered Tariff Regime	Regulated				
Applied for Exemption ?	No				
Exemption granted ?	No				
% Exemption in entry direction	0%				
% Exemption in exit direction	0%				

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2015 Q4
Last completed Phase :	FID

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	
Total Compressor Power (MW)	+21,00
Maximum Capacity (GWh/d)	
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Market Integration, Enhancement of Internal Network; reduct	ion of interna	l congestion, f	N-1 compliance, Integration	of LNG plants, Integration of	UGS, Integration of new Gas fired power plants
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-N-279	CS La Barbolla	Non-FID

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	Enagás S.A.			
Operator	Enagás S.A.			
TEN-E Project ?	Not part of TEN-E			
Interested by PCI ?	Yes			
IGAs	None			
Web Link				



THIRD-PARTY ACCESS REGIME					
Considered TPA Regime	Regulated				
Considered Tariff Regime	Regulated				
Applied for Exemption ?	No				
Exemption granted ?	No				
% Exemption in entry direction	0%				
% Exemption in exit direction	0%				

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2021 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	
Total Compressor Power (MW)	+20,00
Maximum Capacity (GWh/d)	
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Mangualde (PT) / Zamora (ES) (3rd Spain / Portugal IP)	Yes	entry	35,00	Hub Portugal	Hub Spain
	Yes	exit	35.00	Hub Spain	Hub Portugal

DESCRIPTION OF THE PROJECT		

#### **EXPECTED BENEFITS**

Security of Supply, Market integration (Spain and Portugal), Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (Portugal), N-1 Regional (South gas region), Back-up for renewables, Enhancement of Internal Network; reduction of internal congestion, N-1 compliance, Integration of LNG plants, Integration of under plants.

CS La Barbolla is part of the of the paralell core network in the Spanish System to develop the 3rd Interconnection project between Spain and Portugal, which has been submitted as a PCI. From a European perspective, this project contributes to integrate the European systems and, therefore, an internal gas market development, fulfilling the objectives of the European Union policies and guidelines. This project linked and supplemented with the full development of the IBERIAN-FRENCH CORRIDOR, ensure that no Member State is isolated from the European network, as well as, reinforce the security of supply in any system, increasing the solidarity between countries in all of Europea.

The project has significant impact on cross-border because of the notable increase of the capacity at the Portugal-Spanish border and is part of the development of the Iberian Gas Market (MIBGAS) which mainly aims to achieve a single market in the Iberian Peninsula by developing cross border infrastructures to enhance transmission fluidity between Portugal and Spain.


## COMMENTS ABOUT THE PROJECT FINANCING Public financing Private financing Multilateral financing




TRA-N-159	CS Zamora power increase	Non-FID

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	Enagás S.A.
Operator	Enagás S.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME		
Considered TPA Regime	Regulated	
Considered Tariff Regime	Regulated	
Applied for Exemption ?	No	
Exemption granted ?	No	
% Exemption in entry direction	0%	
% Exemption in exit direction	0%	

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2018 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	
Total Compressor Power (MW)	+23,00
Maximum Capacity (GWh/d)	
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Market integration (Spain and Portugal), Reverse Flows, Dive Network; reduction of internal congestion, N-1 compliance, Integration of LNG pla	ants, Integrat	ion of UGS, In	ntegration of new Gas fired	d power plants.	
CS Zamora power increase is part of the 3rd Interconnection project between Spa an internal gas market development, fulfilling the objectives of the European Unio	on policies an	d guidelines.	This project linked and su	pplemented with the full deve	
is isolated from the European network, as well as, reinforce the security of supply The project has significant impact on cross-border because of the notable increa market in the Iberian Peninsula by developing cross border infrastructures to enh	se of the cap	acity at the P	ortugal-Spanish border an	nd is part of the development	of the Iberian Gas Market (MIBGAS) which mainly aims to achieve a single
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-F-160	CS Zaragoza power increase	FID
Dinalina including CS		

SPONSORS

#### GENERAL INFORMATION



Promoter	Enagás S.A.
Operator	Enagás S.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME		
Considered TPA Regime	Regulated	
Considered Tariff Regime	Regulated	
Applied for Exemption ?	No	
Exemption granted ?	No	
% Exemption in entry direction	0%	
% Exemption in exit direction	0%	

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2016 Q4
Last completed Phase :	FID

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	
Total Compressor Power (MW)	+4,00
Maximum Capacity (GWh/d)	
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
EM ECIES SENETHS					
Security of Supply, Market integration (Iberian Peninsula with Europe), Reverse Enhancement of Internal Network; reduction of internal congestion, N-1 complian CS Zaragoza power increase is necessary for the development of the "Cross-bord project is to allow to bring gas from any region in Europe to be transported to Spicase of the failure of Barcelona LNG plant, removing the internal bottlenecks of tintegrated -Catalonia will never be isolated in case of N-1 of Barcelona- and with countries, making possible the regional cooperation between member states in the CS Zaragoza power increase is also part of the core network developments (Spani Western Europe, which has been submitted as a PCI. Therefore, although CS Zaramain objectives of the Eastern Axis.	nce, Integration of the continuity of the contin	on of LNG platen. Ebro Valle ely, to Catalor estem and coveral access to th Gas Intercorre Network)	nts, Integration of UGS, In ey Project" in the North-S- nia) through the intercon- vering the total system de the sources and routes for ponnections in Western Eu- for the development of Le	tegration of new Gas fired pove outh gas interconnections in Water nection points between France mand in this event. Thanks to rom the European network. It tope to face disruption and allo e Perthus IP subproject, part of	ver plants.  Vestern Europe, which has been submitted as a PCI. The aim of Ebro Valley and Spain in the North-South Gas Interconnections in Western Europe, in the development of the internal Spanish System, the whole system will be increases the security of supply and involves a better integration of the wing to fulfil the N-1 rule.  the Eastern axis-Midcat Project in the North-South gas interconnections in
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-F-164	Guitiriz-Lugo	FID

SPONSORS

#### **GENERAL INFORMATION**



Promoter	Enagás S.A.
Operator	Enagás S.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2013 Q4
Last completed Phase :	Permitting

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+28,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Market Integration, Enhancement of Internal Network; reduct	ion of interna	l congestion, f	N-1 compliance, Integration	of LNG plants, Integration of	UGS, Integration of new Gas fired power plants
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-N-252	Iberian-French corridor: Eastern Axis-Midcat Project	Non-FID
TRA-N-252	Iberian-French corridor: Eastern Axis-Midcat Project	Non-FID

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	TIGF
Operator	TIGF
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	www.tigf.fr



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2020
Last completed Phase :	

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	2
Total Pipeline Length (km)	+148,00
Total Compressor Power (MW)	+10,00
Maximum Capacity (GWh/d)	
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Le Perthus	Yes	entry	230,00	Hub Spain	Hub France(TIGF)
	Yes	exit	80,00	Hub France(TIGF)	Hub Spain
DESCRIPTION OF THE PROJECT					
In the French side, it's composed by a 120 km long pipeline between the frontier Baran (Artère du Gascogne).	r (near Le Per	thus) and the	CS of Barbaira, the instala	tion of an aditional compression	on of 10 MW at Barbaira, and a 28 km long pipeline between Lupiac and
EXPECTED BENEFITS					
Security of Supply, Market integration, Reverse Flows, Diversification of sources, [	Diversification	n of routes, N-	·1 National, N-1 Regional, B	ack-up for renewables	
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-N-161 Iberian-French corridor: Eastern Axis-Midcat Project (Pipeline Figueras-French border)

Non-FID


#### **Pipeline including CS**

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	Enagás S.A.
Operator	Enagás S.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2020 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+25,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Le Perthus	Yes	entry	80,00	Hub France(TIGF)	Hub Spain
	Yes	exit	230.00	Hub Spain	Hub France(TIGF)

DESCRIPTION OF THE PROJECT			

#### **EXPECTED BENEFITS**

Security of Supply, Market integration (Iberian peninsula with Europe), Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (Spain, France), N-1 Regional (North-south in Western Europe), Back-up for renewables, Security of Supply, Market Integration, Enhancement of Internal Network; reduction of internal congestion, N-1 compliance, Integration of LNG plants, Integration of UGS, Integration of new Gas fired power plants.

Figueras-French Border is necessary for the development of the Le Perthus IP subproject, part of the Eastern axis-Midcat Project in the North-South gas interconnections in western Europe, which has been submitted as a PCI. The Iberian-French Corridor is crucial to better interconnect the Mediterranean area and thus supplies from Africa and the Northern supply Corridor making a reality the strategy concept of the North-South Corridor in Western Europe.

From an European perspective, developing the full IBERIAN-FRENCH CORRIDOR contribute to spread the diversified portfolio of the South Region as well as opens a path to transport gas from Algeria to central Europe through France. The IBERIAN-FRENCH CORRIDOR will contribute to redistribute and balance the entry of supply sources to Europe, increasing the European diversification of supply by reducing the dependence on the incumbent gas source, jointly with the risks linked to security of supply.

From a regional perspective, highlighted is the better integration of these two countries into the South Region, developing the new cross border interconnection capacity. Developing cross-border capacity between France and Spain will bring the European gas market closer, making possible the development of large scale energy trade between countries.


## COMMENTS ABOUT THE PROJECT FINANCING Public financing Private financing Multilateral financing




TRA-N-168	Interconnection ES-PT (3rd IP)	Non-FID

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	Enagás S.A.
Operator	Enagás S.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2017 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+86,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Mangualde (PT) / Zamora (ES) (3rd Spain / Portugal IP)	Yes	exit	107,00	Hub Spain	Hub Portugal
	Yes	entry	107.00	Hub Portugal	Hub Spain

DESCRIPTION OF THE PROJECT			

#### **EXPECTED BENEFITS**

Security of Supply, Market integration (Spain and Portugal), Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (Portugal), N-1 Regional (South gas region), Back-up for renewables, Enhancement of Internal Network; reduction of internal congestion, N-1 compliance, Integration of UGS, Integration of new Gas fired power plants.

The 3rd Interconnection between Spain and Portugal has been submitted as a PCI. From a European perspective, this project contributes to integrate the European systems and, therefore, an internal gas market development, fulfilling the objectives of the European Union policies and guidelines. This project linked and supplemented with the full development of the IBERIAN-FRENCH CORRIDOR, ensure that no Member State is isolated from the European network, as well as, reinforce the security of supply in any system, increasing the solidarity between countries in all of Europe.

The project has significant impact on cross-border because of the notable increase of the capacity at the Portugal-Spanish border and is part of the development of the Iberian Gas Market (MIBGAS) which mainly aims to achieve a single market in the Iberian Peninsula by developing cross border infrastructures to enhance transmission fluidity between Portugal and Spain.

#### COMMENTS ABOUT THE PROJECT FINANCING


Public financing	Private financing	Multilateral financing




TRA-N-167	Loop Arrigorriaga-Lemona	Non-FID
malina inaludina CC		

SPONSORS

#### GENERAL INFORMATION



Promoter	Enagás S.A.
Operator	Enagás S.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2018 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+15,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Market Integration, Enhancement of Internal Network; reduct	ion of interna	l congestion, f	N-1 compliance, Integration	of LNG plants, Integration of	UGS, Integration of new Gas fired power plants
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-F-166	Loop Bermeo-Lemona	FID
Pipeline including CS		

GENERAL INFORMATION

SPONSORS

Enagás S.A. (100%)

# Promoter Enagás S.A. Operator Enagás S.A. TEN-E Project ? Not part of TEN-E Interested by PCI ? No IGAs None Web Link



THIRD-PARTY ACCESS REGIME		SCHEDULE		TECHNICAL INFORMATION	
Considered TPA Regime	Regulated	End of permitting phase		# of Pipelines, nodes, CS	1
Considered Tariff Regime	Regulated	FID		Total Pipeline Length (km)	+32,00
Applied for Exemption ?	No	Construction		Total Compressor Power (MW)	
Exemption granted ?	No	Commissioning	2015 Q4	Maximum Capacity (GWh/d)	
% Exemption in entry direction	0%	Last completed Phase :	Permitting	Expected Load Factor	
% Exemption in exit direction	0%				




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Market Integration, Enhancement of Internal Network; reduct	ion of interna	l congestion, f	N-1 compliance, Integration	of LNG plants, Integration of	UGS, Integration of new Gas fired power plants
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-F-169	Loop Castelnou-Villar de Arnedo	FID
Dinalina including CS		

SPONSORS

#### GENERAL INFORMATION



Promoter	Enagás S.A.
Operator	Enagás S.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME				
Considered TPA Regime	Regulated			
Considered Tariff Regime	Regulated			
Applied for Exemption ?	No			
Exemption granted ?	No			
% Exemption in entry direction	0%			
% Exemption in exit direction	0%			

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2016 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+214,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Market integration (Iberian Peninsula with Europe), Revers Security of Supply, Market Integration, Enhancement of Internal Network; reduc Loop Castelnou-Villar de Arnedo pipeline is necessary for the development of the Ebro Valley project is to allow to bring gas from any region in Europe to be transeurope, in case of the failure of Barcelona LNG plant, removing the internal both system will be integrated -Catalonia will never be isolated in case of N-1 of Barco of the countries, making possible the regional cooperation between member state Loop Castelnou-Villar de Arnedo pipeline is also part of the core network deveinterconnections in Western Europe, which has been submitted as a PCI. Then capacity and the achievements of the main objectives of the Eastern Axis.	ction of internal ne "Cross-borde sported to Spai ottlenecks of th elona- and will ates in the Nort elopments (Spa	congestion, er optimization in (concretely ee Spanish sy have physica h-South Gas unish paralell	N-1 compliance, Integron: Ebro Valley Project" y, to Catalonia) through stem and covering the al access to the sources Interconnections in We Core Network) for the	ation of LNG plants, Integration of in the North-South gas intercond the interconnection points between total system demand in this even and routes from the European natern Europe to face disruption and development of Le Perthus IP servens	of UGS, Integration of new Gas fired power plants.  nections in Western Europe, which has been submitted as a PCI. The aim of veen France and Spain in the North-South Gas Interconnections in Western ent. Thanks to the development of the internal Spanish System, the whole etwork. It increases the security of supply and involves a better integration and allowing to fulfil the N-1 rule subproject, part of the Eastern axis-Midcat Project in the North-South gas
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private final	ncing			Multilateral financing




TRA-F-170	Loop Llanera-Otero	FID

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	Enagás S.A.
Operator	Enagás S.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME				
Considered TPA Regime	Regulated			
Considered Tariff Regime	Regulated			
Applied for Exemption ?	No			
Exemption granted ?	No			
% Exemption in entry direction	0%			
% Exemption in exit direction	0%			

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2013 Q4
Last completed Phase :	Permitting

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+1,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Market Integration, Enhancement of Internal Network; reduct	ion of interna	l congestion, f	N-1 compliance, Integration	of LNG plants, Integration of	UGS, Integration of new Gas fired power plants
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-F-171	Loop Treto-Llanera	FID

#### SPONSORS

#### GENERAL INFORMATION



Promoter	Enagás S.A.
Operator	Enagás S.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2013 Q4
Last completed Phase :	FID

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+216,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Market Integration, Enhancement of Internal Network; reduct	ion of interna	l congestion, f	N-1 compliance, Integration	of LNG plants, Integration of	UGS, Integration of new Gas fired power plants
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-N-172	Loop Vergara-Lemona	Non-FID

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	Enagás S.A.
Operator	Enagás S.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME				
Considered TPA Regime	Regulated			
Considered Tariff Regime	Regulated			
Applied for Exemption ?	No			
Exemption granted ?	No			
% Exemption in entry direction	0%			
% Exemption in exit direction	0%			

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2019 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+15,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Market Integration, Enhancement of Internal Network; reduct	ion of interna	l congestion, f	N-1 compliance, Integration	of LNG plants, Integration of	UGS, Integration of new Gas fired power plants
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-F-173	Loop Villapresente-Burgos	FID
Pipeline including CS		

**SPONSORS** 

### GENERAL INFORMATION



Promoter	Enagás S.A.			
Operator	Enagás S.A.			
TEN-E Project ?	Not part of TEN-E			
Interested by PCI ?	No			
IGAs	None			
Web Link				



THIRD-PARTY ACCESS REGIME		SCHEDULE	
Considered TPA Regime	Regulated	End of permitting phase	
Considered Tariff Regime	Regulated	FID	
Applied for Exemption ?	No	Construction	
Exemption granted ?	No	Commissioning	2014 Q4
% Exemption in entry direction	0%	Last completed Phase :	Permitting
% Exemption in exit direction	0%		

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+153,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Market Integration, Enhancement of Internal Network; reducti	on of internal	congestion, N	N-1 compliance, Integration	of LNG plants, Integration of	UGS, Integration of new Gas fired power plants
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-N-280	Lugo-Villafranca del Bierzo	Non-FID
-----------	-----------------------------	---------

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	Enagás S.A.
Operator	Enagás S.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2017 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+90,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Market integration (Spain and Portugal), Reverse Flows, Dive				, , ,	
Integration, Enhancement of Internal Network; reduction of internal congestion, Lugo-Villafranca del Bierzo pipeline is part of the of the paralell core network in tl		_		_	
this project contributes to integrate the European systems and, therefore, an in	_	•		·	• • • • • • • • • • • • • • • • • • • •
development of the IBERIAN-FRENCH CORRIDOR, ensure that no Member State is The project has significant impact on cross-border because of the notable increa					
market in the Iberian Peninsula by developing cross border infrastructures to enh	ance transmi	ssion fluidity b	petween Portugal and Spair	n	
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-F-175	Martorell-Figueras	FID
Dinalina including CS		

SPONSORS

# GENERAL INFORMATION



Promoter	Enagás S.A.			
Operator	Enagás S.A.			
TEN-E Project ?	Not part of TEN-E			
Interested by PCI ?	No			
IGAs	None			
Web Link				



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2013 Q4
Last completed Phase :	Permitting

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+167,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
			capacity (Carry a)		
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Market integration (Iberian peninsula with Europe), Revers renewables, Security of Supply, Market Integration, Enhancement of Internal Netv Although Martorell-Figueras pipeline has not been applied to be a Project of com-	work; reducti	on of internal	congestion, N-1 compliance	e, Integration of LNG plants,	
(Spanish paralell Core Network) for the development of Le Perthus IP subproject, Martorell-Figueras pipeline is not exclusively linked to the interconnection project	part of the E	astern axis-M	lidcat Project in the North-S	South gas interconnections in	
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




LNG-F-178	Musel LNG terminal	FID

### SPONSORS

### GENERAL INFORMATION



Promoter	Enagás S.A.			
Operator	Enagás S.A.			
TEN-E Project ?	Not part of TEN-E			
Interested by PCI ?	No			
IGAs	None			
Web Link				



THIRD-PARTY ACCESS REGIME				
Considered TPA Regime	Regulated			
Considered Tariff Regime	Regulated			
Applied for Exemption ?	No			
Exemption granted ?	No			
% Exemption in entry direction	0%			
% Exemption in exit direction	0%			

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2013 Q4
Last completed Phase :	Construction

TECHNICAL INFORMATION	
Regasification facility	Musel
Expected volume (bcm/y)	
Storage capacity (m3)	+300.000,00
Send-out (mcm/d)	+19,20
Ship size (m3)	250.000,00
Reloading ability ?	No




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Musel	Yes	entry	223,30	LNG Terminals Spain	Hub Spain
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Market Integration, Enhancement of Internal Network; reduction of internal congestion, N-1 compliance, Integration of LNG plants, Integration of UGS, Integration of new Gas fired power plants					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




LNG-N-179	Musel Send-Out increase	Non-FID

### **SPONSORS**

### **GENERAL INFORMATION**



Promoter	Enagás S.A.
Operator	Enagás S.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME				
Considered TPA Regime	Regulated			
Considered Tariff Regime	Regulated			
Applied for Exemption ?	No			
Exemption granted ?	No			
% Exemption in entry direction	0%			
% Exemption in exit direction	0%			

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2020 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
Regasification facility	Musel
Expected volume (bcm/y)	
Storage capacity (m3)	
Send-out (mcm/d)	+4,80
Ship size (m3)	
Reloading ability ?	No




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Musel	Yes	entry	55,80	LNG Terminals Spain	Hub Spain
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Market Integration, Enhancement of Internal Network; reducti	ion of internal	l congestion,	N-1 compliance, Integratio	n of LNG plants, Integration of	UGS, Integration of new Gas fired power plants
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-F-181	Musel Terminal-Llanera	FID
Pipeline including CS		

**SPONSORS** 

GENERAL INFORMATION



Promoter	Enagás S.A.
Operator	Enagás S.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME				
Considered TPA Regime	Regulated			
Considered Tariff Regime	Regulated			
Applied for Exemption ?	No			
Exemption granted ?	No			
% Exemption in entry direction	0%			
% Exemption in exit direction	0%			

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2013 Q4
Last completed Phase :	Permitting

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+16,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Market Integration, Enhancement of Internal Network; reduct	ion of interna	l congestion, f	N-1 compliance, Integration	of LNG plants, Integration of	UGS, Integration of new Gas fired power plants
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




# LNG-N-174 Musel's 3th LNG Storage Tank Non-FID


# **LNG Terminal**

### **SPONSORS**

# GENERAL INFORMATION



Promoter	Enagás S.A.
Operator	Enagás S.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2016 Q4
Last completed Phase :	Planned

Musel	
+150.000,00	
No	
	+150.000,00




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Market Integration, Enhancement of Internal Network; reduction of internal congestion, N-1 compliance, Integration of LNG plants, Integration of UGS, Integration of new Gas fired power plants					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




LNG-N-177	Musel's 4th LNG Storage Tank	Non-FID

### **SPONSORS**

### **GENERAL INFORMATION**



Promoter	Enagás S.A.
Operator	Enagás S.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2019 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
Regasification facility	Musel
Expected volume (bcm/y)	
Storage capacity (m3)	+150.000,00
Send-out (mcm/d)	
Ship size (m3)	
Reloading ability ?	No




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Market Integration, Enhancement of Internal Network; reduction of internal congestion, N-1 compliance, Integration of LNG plants, Integration of UGS, Integration of new Gas fired power plants					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-F-158	New Utilities CS Tivissa	FID

### SPONSORS

### GENERAL INFORMATION



Promoter	Enagás S.A.
Operator	Enagás S.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2016 Q4
Last completed Phase :	FID

TECHNICAL INFORMATION
# of Pipelines, nodes, CS
Total Pipeline Length (km)
Total Compressor Power (MW)
Maximum Capacity (GWh/d)
Expected Load Factor




PROJECTED CAPACITY INCREASES						
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone	
DESCRIPTION OF THE PROJECT						
EXPECTED BENEFITS						
Security of Supply, Market integration (Iberian Peninsula with Europe), Reverse Security of Supply, Market Integration, Enhancement of Internal Network; reduct CS Tlvissa new utilities are necessary for the development of the "Cross-border project is to allow to bring gas from any region in Europe to be transported to Sp case of the failure of Barcelona LNG plant, removing the internal bottlenecks of t integrated -Catalonia will never be isolated in case of N-1 of Barcelona- and wi countries, making possible the regional cooperation between member states in the	ion of internal optimization: pain (concretel he Spanish systill have physical	congestion, Ebro Valley I y, to Catalon tem and cov al access to	N-1 compliance, Integous Project" in the North-State Intercouse the intercovering the total system the sources and route	ration of LNG plants, Integration South gas interconnections in V onnection points between Fran- demand in this event. Thanks to the from the European network.	of UGS, Integration of new Gas fired power plants. Vestern Europe, which has been submitted as a PCI. ce and Spain in the North-South Gas Interconnection the development of the internal Spanish System, to the tincreases the security of supply and involves a beginning the security of supply and involves a beginning to the security of supply and involves a beginning the security of supply and	The aim of Ebro Valley is in Western Europe, in the whole system will be
COMMENTS ABOUT THE PROJECT FINANCING						
Public financing	Private finan	cing			Multilateral financing	
		Ī			-	




TRA-F-180	Nuevo Tivissa-Arbós	FID

### SPONSORS

# GENERAL INFORMATION



Promoter	Enagás S.A.
Operator	Enagás S.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2016 Q4
Last completed Phase :	Permitting

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+114,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Market integration (Iberian Peninsula with Europe), Reverse Security of Supply, Market Integration, Enhancement of Internal Network; reduct Nuevo Tivissa-Arbós pipeline is necessary for the development of the "Cross-bord project is to allow to bring gas from any region in Europe to be transported to Spicase of the failure of Barcelona LNG plant, removing the internal bottlenecks of the integrated -Catalonia will never be isolated in case of N-1 of Barcelona- and we countries, making possible the regional cooperation between member states in the Nuevo Tivissa-Arbós pipeline is also part of the core network developments (Spain Western Europe, which has been submitted as a PCI. Therefore, although Nuethe main objectives of the Eastern Axis.	ion of interna der optimizati pain (concrete the Spanish sy ill have physi he North-Sout nish paralell (	I congestion, on: Ebro Valle ely, to Catalor estem and coveral access to the Gas Interce Core Network	N-1 compliance, Integration by Project" in the North-Sonia) through the interconnessering the total system denotes and routes from the sources and routes from the total system for the development of Least and the develo	n of LNG plants, Integration o uth gas interconnections in W ection points between France nand in this event. Thanks to om the European network. It upe to face disruption and allo e Perthus IP subproject, part o	f UGS, Integration of new Gas fired power plants.  Vestern Europe, which has been submitted as a PCI. The aim of Ebro Valley and Spain in the North-South Gas Interconnections in Western Europe, in the development of the internal Spanish System, the whole system will be increases the security of supply and involves a better integration of the wing to fulfil the N-1 rule.  Of the Eastern axis-Midcat Project in the North-South gas interconnections
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-F-157	Power increase CS Haro	FID

### SPONSORS

### GENERAL INFORMATION



Promoter	Enagás S.A.
Operator	Enagás S.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME			
Considered TPA Regime	Regulated		
Considered Tariff Regime	Regulated		
Applied for Exemption ?	No		
Exemption granted ?	No		
% Exemption in entry direction	0%		
% Exemption in exit direction	0%		

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2016 Q4
Last completed Phase :	FID

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	
Total Compressor Power (MW)	+12,00
Maximum Capacity (GWh/d)	
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Market integration (Iberian Peninsula with Europe), Reverse Security of Supply, Market Integration, Enhancement of Internal Network; reducti CS Haro power increase is necessary for the development of the "Cross-border or project is to allow to bring gas from any region in Europe to be transported to Sp case of the failure of Barcelona LNG plant, removing the internal bottlenecks of the integrated -Catalonia will never be isolated in case of N-1 of Barcelona- and will countries, making possible the regional cooperation between member states in the	on of internal optimization: ain (concretel he Spanish system of the spanish system).	congestion, I Ebro Valley F ly, to Catalon stem and cov al access to	N-1 compliance, Integrati Project" in the North-Sou ia) through the interconr ering the total system de the sources and routes f	on of LNG plants, Integration o th gas interconnections in We nection points between France mand in this event. Thanks to rom the European network. It	f UGS, Integration of new Gas fired power plants. stern Europe, which has been submitted as a PCI. The aim of Ebro Valley and Spain in the North-South Gas Interconnections in Western Europe, in the development of the internal Spanish System, the whole system will be increases the security of supply and involves a better integration of the
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private finar	ncing			Multilateral financing




TRA-N-281	Villafranca del Bierzo-Castropodame	Non-FID
Pipeline including CS		

SPONSORS

# GENERAL INFORMATION



Promoter	Enagás S.A.
Operator	Enagás S.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2017 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+30,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Market integration (Spain and Portugal), Reverse Flows, Dive Integration, Enhancement of Internal Network; reduction of internal congestion,				, , ,	
Villafranca del Bierzo-Castropodame pipeline is part of the of the paralell core no	etwork in the	Spanish Syste	em to develop the 3rd Inte	rconnection project between	Spain and Portugal, which has been submitted as a PCI. From a European
perspective, this project contributes to integrate the European systems and, ther	efore, an inte	rnal gas mark	et development, fulfilling t	he objectives of the Europear	n Union policies and guidelines. This project linked and supplemented with
the full development of the IBERIAN-FRENCH CORRIDOR, ensure that no Membe Europe.	r State is isola	ated from the	e European network, as we	Il as, reinforce the security of	supply in any system, increasing the solidarity between countries in all of
The project has significant impact on cross-border because of the notable increa	•	•	• '	· ·	of the Iberian Gas Market (MIBGAS) which mainly aims to achieve a single
market in the Iberian Peninsula by developing cross border infrastructures to enh	ance transmis	ssion ilulaity t	between Portugal and Spai	II.	
COMMENTS ADOLLT THE DROUGT FINANCING					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-N-282 Za	mora-Barbolla-Adradas Non-FID
--------------	-------------------------------

### **SPONSORS**

### GENERAL INFORMATION



Promoter	Enagás S.A.
Operator	Enagás S.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2021 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+307,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Market integration (Spain and Portugal), Reverse Flows, Dive Integration, Enhancement of Internal Network; reduction of internal congestion,		-	·	, , ,	
Zamora-Barbolla-Adradas pipeline is part of the of the paralell core network in the	e Spanish Sys	tem to develo	op the 3rd Interconnect	on project between Spain and P	Portugal, which has been submitted as a PCI. From a European perspective,
this project contributes to integrate the European systems and, therefore, an in development of the IBERIAN-FRENCH CORRIDOR, ensure that no Member State is	-	•		•	• • • • • • • • • • • • • • • • • • • •
The project has significant impact on cross-border because of the notable increa market in the Iberian Peninsula by developing cross border infrastructures to enh	se of the cap	acity at the Po	ortugal-Spanish border	and is part of the development	, , , , , , , , , , , , , , , , , , , ,
market in the identification by developing cross border infrastructures to emi	ance transmis	ssion nature t	Jetween Fortugal and Sp	odiii.	
CONMACNITY A DOLLT THE DROUGHT FINANCING					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-F-186	Zarza de Tajo-Yela	FID

SPONSORS

### GENERAL INFORMATION



Promoter	Enagás S.A.
Operator	Enagás S.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME				
Considered TPA Regime	Regulated			
Considered Tariff Regime	Regulated			
Applied for Exemption ?	No			
Exemption granted ?	No			
% Exemption in entry direction	0%			
% Exemption in exit direction	0%			

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2013 Q4
Last completed Phase :	Permitting

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+106,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Market Integration, Enhancement of Internal Network; reduct	ion of interna	l congestion, f	N-1 compliance, Integration	of LNG plants, Integration of	UGS, Integration of new Gas fired power plants
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




UGS-N-127

# Underground Gas Storage in salt leached caverns in the Bages area, North-Eastern Spain

Non-FID


# **Storage Facility**

### **SPONSORS**



# GENERAL INFORMATION

Promoter	Ga	s Natural
Operator	Gas Natural Apr	rovisionamientos SDG
TEN-E Project ?	Project of 0	Common Interest
Interested by PCI ?		Yes
IGAs		None
Web Link		
TEN-E Requests	Date of Request 28/02/11	Year Funding Granted Not yet



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2014 Q3
FID	2014 Q3
Construction	2023 Q3
Commissioning	2023 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
Storage facility	Pinasses
Working volume (mcm)	+240,00
Injectability (mcm/d)	+3,00
Deliverability (mcm/d)	+14,00



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Pinasses	No	entry	33,00	Hub Spain	Storage Spain
	No	exit	154,00	Storage Spain	Hub France(PEG South)
Pinasses	No	exit	154,00	Storage Spain	Hub Spain
	No	entry	33,00	Hub France(PEG South)	Storage Spain

DESCRIPTION OF THE PROJECT				
Underground storage in underground caverns to be constructed by salt leaching to be carried out on the base salt of the potassium formation from Ecocene in the catalan sector of the Ebro river				
EXPECTED BENEFITS				
Security of Supply, Market integration (Spain and France), Reverse Flows, N-1 National, N-1 Regional, Back-up for renewables				
COMMENTS ABOUT THE PROJECT FINANCING				
Public financing	Private financing	Multilateral financing		
Expected to be received from TEN-E 2011				




LNG-N-162 Gran Canaria 2º LNG Tank Non-FID


**LNG Terminal** 

SPONSORS

# GENERAL INFORMATION



Promoter	Gascan
Operator	Gascan
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2018 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
Regasification facility	Tenerife LNG Terminal
Expected volume (bcm/y)	
Storage capacity (m3)	+150.000,00
Send-out (mcm/d)	
Ship size (m3)	
Reloading ability ?	No




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Market Integration, Enhancement of Internal Network; reduction of internal congestion, N-1 compliance, Integration of LNG plants, Integration of UGS, Integration of new Gas fired power plants					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




LNG-F-163	Gran Canaria LNG Terminal	FID

### SPONSORS





Promoter	Gascan
Operator	Gascan
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2015 Q4
Last completed Phase :	FID

TECHNICAL INFORMATION	
Regasification facility	Gran Canaria
Expected volume (bcm/y)	
Storage capacity (m3)	+150.000,00
Send-out (mcm/d)	+3,60
Ship size (m3)	140.000,00
Reloading ability ?	No




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Gran Canaria LNG	Yes	exit	41,80	LNG Terminals Spain(Canaria	Hub Spain(Canaria)
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Market Integration, Enhancement of Internal Network; reducti	ion of interna	I congestion,	N-1 compliance, Integration	n of LNG plants, Integration of U	GS, Integration of new Gas fired power plants
COMMENTS ADOLLT THE DEGLECT EMANCING					
COMMENTS ABOUT THE PROJECT FINANCING	Duit and a firm				Aubileas of formation
Public financing	Private fina	ncing			Multilateral financing




LNG-N-165	Gran Canaria send out increase	Non-FID

**SPONSORS** 

### GENERAL INFORMATION



Promoter	Gascan
Operator	Gascan
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME		SCHEDU
Considered TPA Regime	Regulated	End of p
Considered Tariff Regime	Regulated	FID
Applied for Exemption ?	No	Constru
Exemption granted ?	No	Commis
% Exemption in entry direction	0%	Last con
% Exemption in exit direction	0%	

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2018 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
Regasification facility	Tenerife LNG Terminal
Expected volume (bcm/y)	
Storage capacity (m3)	
Send-out (mcm/d)	+1,80
Ship size (m3)	
Reloading ability ?	No




PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Gran Canaria LNG	Yes	exit	20,90	LNG Terminals Spain(Canar	ia) Hub Spain(Canaria)
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Market Integration, Enhancement of Internal Network; reduct	ion of interna	I congestion,	N-1 compliance, Integratio	n of LNG plants, Integration of	UGS, Integration of new Gas fired power plants
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




LNG-N-185	Tenerife Send-Out increase	Non-FID

**SPONSORS** 

### GENERAL INFORMATION



Promoter	Gascan
Operator	Gascan
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME		S
Considered TPA Regime	Regulated	E
Considered Tariff Regime	Regulated	F
Applied for Exemption ?	No	C
Exemption granted ?	No	C
% Exemption in entry direction	0%	L
% Exemption in exit direction	0%	

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2017 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
Regasification facility	Tenerife LNG Terminal
Expected volume (bcm/y)	
Storage capacity (m3)	
Send-out (mcm/d)	+1,80
Ship size (m3)	
Reloading ability ?	No



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Tenerife LNG	Yes	exit	20,90	LNG Terminals Spain(Canari	a) Hub Spain(Canaria)
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Market Integration, Enhancement of Internal Network; reduction of internal congestion, N-1 compliance, Integration of LNG plants, Integration of UGS, Integration of new Gas fired power plants					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




LNG-N-184 Tenerife 2º LNG Storage Tank Non-FID


**LNG Terminal** 

SPONSORS

# GENERAL INFORMATION



Promoter	Gascan
Operator	Gascan
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME			
Considered TPA Regime	Regulated		
Considered Tariff Regime	Regulated		
Applied for Exemption ?	No		
Exemption granted ?	No		
% Exemption in entry direction	0%		
% Exemption in exit direction	0%		

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2017 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
Regasification facility	Tenerife LNG Terminal
Expected volume (bcm/y)	
Storage capacity (m3)	+150.000,00
Send-out (mcm/d)	
Ship size (m3)	
Reloading ability ?	No



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Market Integration, Enhancement of Internal Network; reduction of internal congestion, N-1 compliance, Integration of LNG plants, Integration of UGS, Integration of new Gas fired power plants					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




LNG-F-183	Tenerife LNG Terminal	FID


#### **LNG Terminal**

#### SPONSORS

#### GENERAL INFORMATION



Promoter	Gascan
Operator	Gascan
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME		SCHEDULE
Considered TPA Regime	Regulated	End of permitting pha
Considered Tariff Regime	Regulated	FID
Applied for Exemption ?	No	Construction
Exemption granted ?	No	Commissioning
% Exemption in entry direction	0%	Last completed Phase
% Exemption in exit direction	0%	

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2014 Q4
Last completed Phase :	Permitting

TECHNICAL INFORMATION	
Regasification facility	Tenerife LNG Terminal
Expected volume (bcm/y)	
Storage capacity (m3)	+150.000,00
Send-out (mcm/d)	+3,60
Ship size (m3)	140.000,00
Reloading ability ?	No



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Tenerife LNG	Yes	exit	41,80	LNG Terminals Spain(Canari	a) Hub Spain(Canaria)
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Market Integration, Enhancement of Internal Network; reduction	ion of interna	I congestion,	N-1 compliance, Integration	n of LNG plants, Integration of	UGS, Integration of new Gas fired power plants
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-F-155	Bilbao Terminal-Treto	FID


#### **Pipeline including CS**

**SPONSORS** 

#### GENERAL INFORMATION



Promoter	Naturgas
Operator	Enagás S.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME				
Considered TPA Regime	Regulated			
Considered Tariff Regime	Regulated			
Applied for Exemption ?	No			
Exemption granted ?	No			
% Exemption in entry direction	0%			
% Exemption in exit direction	0%			

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2013 Q4
Last completed Phase :	Construction

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+53,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
EXPECTED BENEFITS					
Security of Supply, Market Integration, Enhancement of Internal Network, reducti	on of internal	congestion, N	N-1 compliance, Integration	of LNG plants, Integration of	UGS, Integration of new Gas fired power plants
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




LNG-N-182	Sagunto Send-Out increase 1.200.000 Nm3/h	Non-FID


**LNG Terminal** 

**SPONSORS** 

#### GENERAL INFORMATION



Promoter	Saggas
Operator	Saggas
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME		SCHEDU
Considered TPA Regime	Regulated	End of
Considered Tariff Regime	Regulated	FID
Applied for Exemption ?	No	Constru
Exemption granted ?	No	Commis
% Exemption in entry direction	0%	Last cor
% Exemption in exit direction	0%	

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2014 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
Regasification facility Sagunto	
Expected volume (bcm/y)	
Storage capacity (m3)	
Send-out (mcm/d) +4,80	
Ship size (m3)	
Reloading ability ? No	



PROJECTED CAPACITY INCREASES						
Interconnection	Modelled	Direction	Capacity	(GWh/d)	From Zone	To Zone
Sagunto	Yes	exit		55,80	LNG Terminals Spain	Hub Spain
DESCRIPTION OF THE PROJECT						
EXPECTED BENEFITS						
Security of Supply, Market Integration, Enhancement of Internal Network; reduction of internal congestion, N-1 compliance, Integration of LNG plants, Integration of UGS, Integration of new Gas fired power plants						
COMMENTS ABOUT THE PROJECT FINANCING						
Public financing	Private fina	ncing				Multilateral financing










## LNG-N-032 Gothenburg LNG (preliminary) Non-FID


**LNG Terminal** 

SPONSORS

#### GENERAL INFORMATION



Promoter	Swedegas AB			
Operator	Swede	egas AB		
TEN-E Project ?	Project of Common Interest			
Interested by PCI ?	Not defined yet			
IGAs	None			
Web Link				
TEN-E Requests	Date of Request	Year Funding Granted		
	1/06/12	Not yet		



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%


SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2015
Last completed Phase :	

TECHNICAL INFORMATION	
Regasification facility	Gothenburg LNG (preliminary)
Expected volume (bcm/y)	+0,50
Storage capacity (m3)	+20.000,00
Send-out (mcm/d)	+2,00
Ship size (m3)	30.000,00
Reloading ability ?	Yes



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Gothenburg LNG	Yes	entry	24,00	LNG Terminals Sweden	Hub Sweden
DESCRIPTION OF THE PROJECT					
DESCRIPTION OF THE PROJECT					
A LNG terminal, including connection to the transmission grid, placed in the Gothe	enburg harbo	r.			
EXPECTED BENEFITS					
EXPECTED BENEFITS					
Security of Supply, Reverse Flows, Diversification of sources, Diversification of rou	tes, Facilitate	s supply to no	on grid customers, such as	industry replacing oil and futu	re bunkering of ships to comply with the coming SECA regulation.
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing

# Switzerland









TRA-N-230	Reverse Flow Transitgas Switzerland	Non-FID
Pipeline including CS		

GENERAL INFORMATION

.

SPONSORS





**FINANCING** 

THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	100%
% Exemption in exit direction	100%

FluxSwiss (100%)


SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2016 Q4
Last completed Phase :	Market test

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	
Total Pipeline Length (km)	
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Wallbach (Fluxys TENP/FluxSwiss)	Yes	exit	330,00	Hub Switzerland	Hub Germany(NCG)
Oltingue (FR) / Rodersdorf (CH)	Yes	exit	100,00	Hub Switzerland	Hub France(PEG North)
Griespass (CH) / Passo Gries (IT) (FluxSwiss)	Yes	entry	430,00	Hub Italia	Hub Switzerland
DESCRIPTION OF THE PROJECT					
Modification of a compressor station to allow the reversal of the border interconnection points at Gries Pass, Wallbach and Oltingue and a south-north use of the Transitgas pipeline.					
EXPECTED BENEFITS					
Security of Supply, Market integration, Reverse Flows, Diversification of sources, Diversification of routes					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing










### TRA-N-221 TANAP - Trans Anatolian Natural Gas Pipeline Project Non-FID


#### **Pipeline including CS**

#### SPONSORS



#### GENERAL INFORMATION

Promoter	Socar
Operator	Unknown
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	1
Web Link	www.tanap.com



THIRD-PARTY ACCESS REGIME			
Considered TPA Regime	Negotiated (e.g. Exemption)		
Considered Tariff Regime	Negotiated (e.g. Exemption)		
Applied for Exemption ?	No		
Exemption granted ?	No		
% Exemption in entry direction	0%		
% Exemption in exit direction	0%		


SCHEDULE	
End of permitting phase	
FID	2013 Q2
Construction	2017 Q3
Commissioning	2018 Q1
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+1.900,00
Total Compressor Power (MW)	+650,00
Maximum Capacity (GWh/d)	+16,00
Expected Load Factor	95,00%



		a	0 1 (014) (1)		
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Türkgözü	Yes	entry	536,00	Supplier Caspia interconnector trans-Anato	Interconnector Trans-Anatolian Pipeline
Esksisehir and Thracian region	No	exit	201,00	Riterconnector trans-Anato	TIAD TURKEY
Kipi	Yes	exit	335,00	Riterconnector trans-Anato	Hub Greece
Nabucco from Caspia (CA)	Yes	exit	335,00	Dinalina	Interconnector Nabucco
DESCRIPTION OF THE PROJECT					
TANAP intends for the transportation of the natural gas to be produced in Shah Do	eniz-2 field aı	nd other fields	s of Azerbaijan (and ot	ner possible countries) through Tu	rkey to Europe.
EXPECTED BENEFITS					
Security of Supply, Market integration, Diversification of sources, Diversification of routes					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing

# United Kingdom








UGS-F-091	Holford	FID


#### **Storage Facility**

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	E.ON UK
Operator	E.ON Gas Storage UK Ltd
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	www.eon-uk.com/generation/holford.aspx



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	Yes
Exemption granted ?	Yes
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	2005
Construction	
Commissioning	2013 Q1
Last completed Phase :	Construction

TECHNICAL INFORMATION	
Storage facility	
Working volume (mcm)	+196,00
Injectability (mcm/d)	+22,00
Deliverability (mcm/d)	+22,00



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Holford (frmr Byley)	Yes	entry	242,00	Hub United Kingdom	Storage United Kingdom
	Yes	exit	242,00	Storage United Kingdom	Hub United Kingdom
DESCRIPTION OF THE PROJECT					

#### **EXPECTED BENEFITS**

Security of Supply, Market Integration (Increase of competition) through marketing of capacity.

SoS - Provision of constant and secure gas supply into the UK gas market, which can be withdrawn to meet daily demand peaks

#### COMMENTS ABOUT THE PROJECT FINANCING

Public financing	Private financing	Multilateral financing




#### UGS-N-203 Preesall Gas Storage Non-FID


**Storage Facility** 

SPONSORS

#### GENERAL INFORMATION



Promoter	Halite Energy Group Ltd
Operator	Halite Energy Group Ltd
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	www.halite-energy.co.uk/



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2013
FID	2013
Construction	2018
Commissioning	2016
Last completed Phase :	Planned

TECHNICAL INFORMATION	
Storage facility	Preesall
Working volume (mcm)	+600,00
Injectability (mcm/d)	+30,00
Deliverability (mcm/d)	+30,00



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Preesall	Yes	exit	330,00	Storage United Kingdom	Hub United Kingdom
	Yes	entry	330,00	Hub United Kingdom	Storage United Kingdom

DESCRIPTION OF THE PROJECT				
A fast cycle salt cavern project with shallow depths allowing for rapid turnaround at low operating costs				
EXPECTED BENEFITS				
COMMENTS ABOUT THE PROJECT FINANCING				
Public financing	Private financing	Multilateral financing		




### UGS-N-087 King Street Energy Storage Project Non-FID


#### **Storage Facility**

#### SPONSORS

#### GENERAL INFORMATION



Promoter	King Street Enegy Ltd	
Operator	King Street Enegy Ltd	
TEN-E Project ?	Not part of TEN-E	
Interested by PCI ?	Not defined yet	
IGAs	1	
Web Link	www.kingstreetenergy.com	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	No
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2015 Q2
FID	2013 Q3
Construction	2014 Q1
Commissioning	2017 Q4
Last completed Phase :	Construction

TECHNICAL INFORMATION	
Storage facility	
Working volume (mcm)	+348,00
Injectability (mcm/d)	+32,00
Deliverability (mcm/d)	+32,00



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
King Street	Yes	entry	352,00	Hub United Kingdom	Storage United Kingdom
	Yes	exit	352,00	Storage United Kingdom	Hub United Kingdom


DESCRIPTION OF THE PROJECT		
Storage facility; Salt Cavern Storage Facility		
EXPECTED BENEFITS		
Market Integration (Increase of competition) Project increases available gas storage in the UK		
COMMENTS ABOUT THE PROJECT FINANCING		
Public financing	Private financing	Multilateral financing




	TRA-F-025	System Capacity Enhancements FID	FID
F	Pipeline including CS		

SPONSORS

#### **GENERAL INFORMATION**



Promoter	National Grid Gas plc
Operator	National Grid Gas plc
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	No
IGAs	None
Web Link	www.nationalgrid.com/



THIRD-PARTY ACCESS REGIME		SCHEDULE		TECHNICAL INFORMATION	
Considered TPA Regime	Regulated	End of permitting phase		# of Pipelines, nodes, CS	3
Considered Tariff Regime	Regulated	FID		Total Pipeline Length (km)	
Applied for Exemption ?	No	Construction		Total Compressor Power (MW)	+118,00
Exemption granted ?	Not relevant	Commissioning	2013	Maximum Capacity (GWh/d)	
% Exemption in entry direction	0%	Last completed Phase :	FID	Expected Load Factor	
% Exemption in exit direction	0%				



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
New electric drive unit to be installed as part of the Emissions Reduction Program	ıme.				
EXPECTED BENEFITS					
The compression fleet enhancements currently being completed by National Grid	d are installing	g alternative c	compression fuel capability	at selected sites; this will ena	able the bulk of compression at these sites to be electrically driven thereb
reducing station emission levels.					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




TRA-N-026	System Capacity Enhancements non-FID - National Grid	Non-FID
-----------	--	---------


**Pipeline including CS** 

**SPONSORS** 

#### GENERAL INFORMATION



Promoter	National Grid Gas plc
Operator	National Grid Gas plc
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	www.nationalgrid.com/



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	Not relevant
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	2018
Commissioning	2022*
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	2
Total Pipeline Length (km)	+93,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
DESCRIPTION OF THE PROJECT					
New pipelines to be constructed as part of the pre-FID System Capacity Enhancem	nents				
EXPECTED BENEFITS					
The system capacity enhancements proposed by National Grid will ensure that descenarios in order to meet both the predicted peak demand and lower levels of descenarios		certainty rega	ording the pattern of suppli	es – in terms of both volume	and location – sufficient gas can be transmitted under a variety of supply
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing



TRA-N-027


## Physical reverse flow from Northern Ireland to Great Britain and Republic of Ireland via Scotland to Northern Ireland pipeline

Non-FID


**Pipeline including CS** 

**SPONSORS** 

GENERAL INFORMATION



Promoter	Premier Transmission Ltd
Operator	Premier Transmission Ltd
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	Not relevant
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2014
FID	2013
Construction	2014
Commissioning	2016
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	
Total Compressor Power (MW)	+9,50
Maximum Capacity (GWh/d)	+132,00
Expected Load Factor	20,00%



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Scotland - Northern Ireland (SNIP)	No	exit	132,00		Hub United Kingdom
	No	exit	132,00		Hub Ireland
DESCRIPTION OF THE PROJECT					
Installation of bi-drectional compression on Scotland to Northern Ireland pipeline of the bidirectional transmission system.	e (SNIP); pipev	work modifica	ations at 2 AGI's to allow bio	directional metering and flow	control and moving gas odourisation point to a new point(s) downstream
EXPECTED BENEFITS					
Security of Supply, Market integration, Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (Ireland), Back-up for renewables, Extension of transport capacity of Russian gas to the West, Integration of Nord Stream off- and on-Shore in the European gas infrastructure					
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing




UGS-F-006	Stublach - Stage 1	FID


#### **Storage Facility**

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	Storengy
Operator	Storengy UK
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	www.storengy.co.uk/About-Storengy/Projects.php



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	Yes
Exemption granted ?	Yes
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2014 Q4
Last completed Phase :	Construction

TECHNICAL INFORMATION	
Storage facility	Stublach Gas Storage
Working volume (mcm)	+100,00
Injectability (mcm/d)	+16,00
Deliverability (mcm/d)	+16,00



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Stublach	Yes	entry	176,00	<b>Hub United Kingdom</b>	Storage United Kingdom
	Yes	exit	176,00	Storage United Kingdom	Hub United Kingdom
DESCRIPTION OF THE PROJECT					
Development of a new salt cavern storage facility in the UK.					
EXPECTED BENEFITS					
Security of Supply, Market integration, N-1 National (UK), N-1 Regional (UK, Irela	nd). Back-up f	or renewables			
o Market Integration (Increase of competition)					
The project will contribute to the increase of security of supply in the region and	will provide n	ore flexibility	to the market thus facilita	ting competition.	
COMMENTS ADOLLT THE PROJECT FINANCING					
COMMENTS ABOUT THE PROJECT FINANCING	D				54 bit - 16
Public financing	Private fina	ncing			Multilateral financing




UGS-N-266 Stublach - Stage 2 Non-FID


**Storage Facility** 

SPONSORS

#### GENERAL INFORMATION



Promoter	Storengy
Operator	Storengy UK
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	www.storengy.co.uk/About-Storengy/Projects.php



THIRD-PARTY ACCESS REGIME				
Considered TPA Regime	Negotiated (e.g. Exemption)			
Considered Tariff Regime	Negotiated (e.g. Exemption)			
Applied for Exemption ?	Yes			
Exemption granted ?	Yes			
% Exemption in entry direction	0%			
% Exemption in exit direction	0%			

SCHEDULE	
End of permitting phase	
FID	
Construction	
Commissioning	2020
Last completed Phase :	Construction
Commissioning	

TECHNICAL INFORMATION	
Storage facility	Stublach Gas Storage
Working volume (mcm)	+460,00
Injectability (mcm/d)	+16,00
Deliverability (mcm/d)	+16,00



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Stublach	Yes	entry	176,00	<b>Hub United Kingdom</b>	Storage United Kingdom
	Yes	exit	176,00	Storage United Kingdom	Hub United Kingdom
DESCRIPTION OF THE PROJECT					
Development of a new salt cavern storage facility in the UK.					
EXPECTED BENEFITS					
Security of Supply, Market integration, N-1 National (UK), N-1 Regional (UK, Irela	nd). Back-up f	or renewables			
o Market Integration (Increase of competition)					
The project will contribute to the increase of security of supply in the region and	will provide n	ore flexibility	to the market thus facilita	ting competition.	
COMMENTS ADOLLT THE PROJECT FINANCING					
COMMENTS ABOUT THE PROJECT FINANCING	D				54 bit - 16
Public financing	Private fina	ncing			Multilateral financing




UGS-N-033	Saltfleetby	Non-FID


#### **Storage Facility**

#### **SPONSORS**

#### GENERAL INFORMATION



Promoter	Wingas Storage UK Ltd
Operator	Wingas Storage UK Ltd
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	www.wingas-storage.com/



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Regulated
Applied for Exemption ?	Yes
Exemption granted ?	Yes
% Exemption in entry direction	100%
% Exemption in exit direction	100%

SCHEDULE	
End of permitting phase	
FID	2014 Q1
Construction	
Commissioning	2017 Q2
Last completed Phase :	Permitting


TECHNICAL INFORMATION	
Storage facility	Saltfleetby UGS
Working volume (mcm)	+775,00
Injectability (mcm/d)	+5,20
Deliverability (mcm/d)	+8,50



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Saltfleetby	Yes	exit	93,50	Storage United Kingdom	Hub United Kingdom
	Yes	entry	57,20	Hub United Kingdom	Storage United Kingdom

DESCRIPTION OF THE PROJECT		
Conversion of the Saltfleetby, Lincolnshire, gas field to a seasonal gas storage facility		
EXPECTED BENEFITS		
Security of Supply, The project will provide two clear benefits. First, it will increase the level of gas storage in the UK in a time of increasing concern about security of supply on a national level. Secondly it will provide storage capacity for the shareholders and third parties to enable them better to meet their commercial objectives		
COMMENTS ABOUT THE PROJECT FINANCING		
Public financing	Private financing	Multilateral financing

# Multi-Country Projects








#### TRA-N-149 Interconnector Greece Bulgaria - IGB Non-FID


#### **Pipeline including CS**

#### SPONSORS

#### GENERAL INFORMATION



Promoter	DEPA S.A.
Operator	DEPA S.A.
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	None
Web Link	



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	Not yet
Exemption granted ?	Not yet
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2013 Q2
FID	2013 Q1
Construction	2014 Q4
Commissioning	2015 Q1
Last completed Phase :	Permitting

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	2
Total Pipeline Length (km)	+182,00
Total Compressor Power (MW)	+20,00
Maximum Capacity (GWh/d)	+147,00
Expected Load Factor	90,00%



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Interconnector IGB (Greece - Bulgaria)	Yes	exit	110,00	Hub Greece	Hub Bulgaria
	Yes	entry	50,00	Hub Bulgaria	Hub Greece

# **DESCRIPTION OF THE PROJECT**

An onshore natural gas pipeline that will connect Komotini in Greece to Stara Zagora in Bulgaria

# **EXPECTED BENEFITS**

Security of Supply, Market integration (Greece, Bulgaria, Romania, Hungary, FYROM, Serbia), Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (Greece, Bulgaria), N-1 Regional (North South Interconnection in the South Eastern Europe), Back-up for renewables, Power-to-gas, The project will contribute significantly in the itegration of the market area, specifically the South Eastern Europe, and will allow to alleviate to a great extend the dependency of countries in the area to a single source/counterpart. Taking into account that the objective of the project is to bring additional import quantities of natural gas in Bulgaria and South Eastern Europe it significantly improves the resilience of the system in both short (the additional quantities will be able to cover daily peak demands) and long term.

Specifically for the long term, the diversification in route, supply source as well as counterparts will have a great positive impact on the resilience of the system and will be able to cater to any forecasted increase in demand over the coming years.

The impact of the project in the systems flexibility under disruption (n-1 rule) will be significant taking into account that it will create a new interconnections carrying gas from a new source allowing new counterparts to enter the market. A possible disruption in any of the other import sources (including the regional disruption of Russian gas) will NOT AFFECT this one having a great positive impact on the remaining flexibility of the system.


Public financing Private	financing	Multilateral financing



# TRA-N-187 South Stream Project (Onshore Section) Non-FID


# **Pipeline including CS**

# SPONSORS Rulearian section



Promoter	Gazprom
Operator	South Stream AG
TEN-E Project ?	Not part of TEN-E
Interested by PCI ?	Yes
IGAs	7
Web Link	





THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	No
Exemption granted ?	No
% Exemption in entry direction	100%
% Exemption in exit direction	100%

SCHEDULE	
End of permitting phase	2013 Q4
FID	2012 Q4
Construction	2015 Q4
Commissioning	2015 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	8
Total Pipeline Length (km)	+1.864,70
Total Compressor Power (MW)	+712,00
Maximum Capacity (GWh/d)	
Expected Load Factor	90,00%



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
South Stream (Bata, Nagykanizsa) (HU)	Yes	exit	224,00	Interconnector South Stream	Hub Hungary
South Stream into Slovenia (SI)	Yes	exit	104,00	Interconnector South Stream	Hub Slovenia
South Stream from Russia (RU)	Yes	entry	2.109,00	Supplier Russia(Mainland)	Interconnector South Stream
South Stream into Bulgaria (BG)	Yes	exit	563,00	Interconnector South Stream	Hub Bulgaria
South Stream into Serbia RS)	Yes	exit	251,00	Interconnector South Stream	Hub Serbia
South Stream into Bosnia (BH)	Yes	exit	18,00	Interconnector South Stream	Hub Bosnia Herzegovina
South Stream into Croatia (HR)	Yes	exit	90,00	Interconnector South Stream	Hub Croatia
South Stream into Austria (AT)	Yes	exit	670,00	Interconnector South Stream	Hub Austria

# **DESCRIPTION OF THE PROJECT**

Major infrastructure project (pipeline incl. compressor stations). Project operators are :

- South Stream Bulgaria AD
- South Stream d.o.o.
- South Stream Hungary Zrt.
- South Stream Slovenia LLC
- South Stream Austria GmbH
- South Stream Greece S.A.
- South Stream Croatia LLC to be incorporated

# **EXPECTED BENEFITS**

Security of Supply, Market integration, Diversification of routes, Power-to-gas, o Interruptible supplies during peak demands, Contribution to satisfaction of natural gas demand in Europe, Considerable number of EU Member States involved, Significant cross-border importance, Contribution to the economies of the countries involved

Public financing	Private financing	Multilateral financing




# TRA-N-010 Poseidon Pipeline Non-FID

# **Pipeline including CS**


# SPONSORS

# GENERAL INFORMATION



Promoter	IGI Po	seidon S.A.		
Operator	IGI Po	IGI Poseidon S.A.		
TEN-E Project ?	Project of E	Project of European Interest		
Interested by PCI ?		Yes		
IGAs		6		
Web Link	www.igi-poseidon.com			
TEN-E Requests	Date of Request	Year Funding Granted		

Date of Request	Year Funding Granted
6/07/09	2010
15/06/05	2006
23/04/03	2003



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	Yes
Exemption granted ?	Yes
% Exemption in entry direction	0%
% Exemption in exit direction	89%

SCHEDULE	
End of permitting phase	2013 Q1
FID	2013 Q3
Construction	2017 Q3
Commissioning	2017 Q4
Last completed Phase :	FEED

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+210,00
Total Compressor Power (MW)	+100,00
Maximum Capacity (GWh/d)	+329,40
Expected Load Factor	1,00



PROJECTED CAPACITY INCREASES					
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Komotini - GR / IGI Poseidon	Yes	entry	329,40	Hub Greece	Interconnector ITGI Poseidon
	Yes	exit	252,50	Interconnector ITGI Poseidon	Hub Greece
Otranto - IT / IGI Poseidon	Yes	exit	329,40	Interconnector ITGI Poseidon	Hub Italia
	Yes	entry	252,50	Hub Italia	Interconnector ITGI Poseidon

D	ES	CRI	PTI	ON	OF	THE	PRO.	JECT

# **EXPECTED BENEFITS**

Security of Supply, Market integration (Greece (SEE) and Italy), Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (Italy, Greece), N-1 Regional (NSI East Gas), Back-up for renewables, Power-to-gas, Biogas, Connecting diversified natural gas reserves not yet linked to Europe, providing diversification of gas supply sources, routes and supplier counterparts. The project promoters, being not gas producer, have strong interest in minimising the gas supply cost. In addition, being the project multi source, the promoters aim to foster competition among producers to supply competitive gas.

Moreover, the project, providing new diversified gas supplies from new counterparts, route and sources, will boost the liquidity of the Italian market contributing to the development of a hub with transparent price signals. This will also benefit Greece, that will be linked for the first time with an accessible gas trading hub.

The Project will support the creation of a more liquid market in Italy and create an excess of gas availability, also contributing to the security of supply of other regions such as the North South Interconnection in WE through the reverse flow of the Transit gas pipeline.

The possible use in Reverse Flow of Poseidon pipeline, not involving transit in non-eu countries, significantly contributes to security of supply of SEE. The project promoters, being not gas producer, have strong interest in minimising the gas supply cost. In addition, being the project multi source, the promoters aim to foster competition among gas producers to supply competitive gas.,


Public financing	Private financing	Multilateral financing



# TRA-N-077 Nabucco Gas Pipeline Project ("Nabucco Classic") Non-FID

# **Pipeline including CS**

# **SPONSORS**




# GENERAL INFORMATION

Promoter	NABUCCO Gas P	ipeline International		
Operator	NABUCCO Gas P	NABUCCO Gas Pipeline International		
TEN-E Project ?	Priori	Priority Project		
Interested by PCI ?		Yes		
IGAs		1		
Web Link	www.nabucco-pipeline.com			
TEN-E Requests	Date of Request 28/04/03	Year Funding Granted 2004		
	20/06/05	2007		

24/04/09

Not yet



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	Yes
Exemption granted ?	Yes
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2013 Q4
FID	2013 Q2
Construction	2013 Q4
Commissioning	2018 Q4
Last completed Phase :	Planned
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+3.184,00
Total Compressor Power (MW)	+1.560,00
Maximum Capacity (GWh/d)	+976,71
Expected Load Factor	90,00%



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Nabucco into Romania (RO)	No	exit	87,90	Interconnector Nabucco	Hub Romania
Nabucco into Austria (AT)	No	exit	654,40	Interconnector Nabucco	Hub Austria
Nabucco into Hungary (HU)	No	exit	107,44	Interconnector Nabucco	Hub Hungary
Nabucco from Caspia (CA)	No	entry	976,71	Supplier Caspia	Interconnector Nabucco
Nabucco into Turkey (TR)	No	exit	78,14	Interconnector Nabucco	Hub Turkey
Nabucco into Bulgaria (BG)	No	exit	48,84	Interconnector Nabucco	Hub Bulgaria

# **DESCRIPTION OF THE PROJECT**

The Nabucco Gas Pipeline is a new gas pipeline that will connect the Caspian region and the Middle East to the European gas demand markets. The pipeline will cross Turkey, Bulgaria, Romania and Hungary and run to Austria.

# **EXPECTED BENEFITS**

Security of Supply, Market integration (The Project will significantly increase the cross-border transmission capacity between Member States thereby contribute to integrating the European gas markets (see gas flow scenarios reflected in above table).) Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (Nabucco countries), N-1 Regional (Nabucco countries), Back-up for renewables, Power-to-gas, Biogas, Interconnectivity: No other project will connect European and Turkish Markets and the South East European national grids. Turkey, Bulgaria, Romania, Hungary, Austria and via the Central European Gas hub all other countries of Europe will receive Nabucco gas.

Third Party Access: No other project in the region offers 16 bcm/y transport capacity to third parties.

Stability by Treaty: No other project provides a predictable, long term concept over 50 years backed by an Intergovernmental Agreement (IGA) for gas transit via Turkey which is compatible with European Energy Law Supply Security: No other project will provide a gas transport volume of 31 bcm/y to gas producers from Central Asian and Middle East from alternative sources directly into the centre of the European markets.

Market Liquidity/Competition: No other project will reach such a high number of shippers, industrial users, wholesalers at competitive conditions in the European market

Market recovery: No other project promoter will spend [such an amount] to construct an infrastructure project with a transparent procurement regime.


Public financing	Private financing	Multilateral financing
The Nabucco project is eligible for 200 million Euro grant funds under the European Economic Programme for Recovery (EEPR). Sovereign guarantees shall be provided through export credit agencies (ECA) based on the procurement of material supplies from specific countries.		Mulilateral funds shall be provided by EBRD, EIB and IFC.



# TRA-N-078 Nabucco Gas Pipeline Project ("Nabucco West") Non-FID

# Pipeline including CS


# **SPONSORS**



# GENERAL INFORMATION

Promoter	NABUCCO Ga	s Pipeline International	
Operator	NABUCCO Ga	s Pipeline International	
TEN-E Project ?	Pri	Priority Project	
Interested by PCI ?		Yes	
IGAs		1	
Web Link	www.nabucco-pipeline.co	om	
TEN-E Requests	Date of Request	Year Funding Granted	

N-E Requests	Date of Request	Year Funding Granted
	24/04/09	Not yet
	28/04/03	2004
	20/06/05	2007



THIRD-PARTY ACCESS REGIME				
Considered TPA Regime	Regulated			
Considered Tariff Regime	Regulated			
Applied for Exemption ?	Yes			
Exemption granted ?	Yes			
% Exemption in entry direction	0%			
% Exemption in exit direction	0%			

SCHEDULE	
End of permitting phase	2015 Q2
FID	2013 Q2
Construction	2015 Q2
Commissioning	2018 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+1.318,00
Total Compressor Power (MW)	+345,00
Maximum Capacity (GWh/d)	+724,66
Expected Load Factor	90,00%



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Nabucco from Caspia (CA)	Yes	entry	724,66		Interconnector Nabucco
Nabucco into Hungary (HU)	Yes	exit	63,01	Interconnector Nabucco	Hub Hungary
Nabucco into Bulgaria (BG)	Yes	exit	63,01	Interconnector Nabucco	Hub Bulgaria
Nabucco into Austria (AT)	Yes	exit	535,62	Interconnector Nabucco	Hub Austria
Nabucco into Romania (RO)	Yes	exit	63,01	Interconnector Nabucco	Hub Romania

# **DESCRIPTION OF THE PROJECT**

"Nabucco West" is a modified concept of the Nabucco Gas Pipeline Project. It foresees the construction of a gas pipeline that will run from the Bulgarian/Turkish border via Bulgaria, Romania and Hungary to Austria.

# **EXPECTED BENEFITS**

Security of Supply, Market integration (The Project will significantly increase the cross-border transmission capacity between Member States thereby contribute to integrating the European gas markets (see gas flow scenarios reflected in above table).), Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (Nabucco countries), Back-up for renewables, Power-to-gas, Biogas

Public financing	Private financing	Multilateral financing
The Nabucco project is eligible for 200 million Euro grant funds under the European Economic Programme for Recovery (EEPR). Sovereign guarantees shall be provided through export credit agencies (ECA) based on the procurement of material supplies from specific countries.		Mulilateral funds shall be provided by EBRD, EIB and IFC.



# TRA-N-267 Nord Stream 3 Non-FID

# **Pipeline including CS**

# SPONSORS

Wintershall (16%)


Gasunie (9%)

GDF Suez (9%)

# E.ON Ruhrgas (15%) Gazprom (51%)

Promoter	Nord Stream AG	
Operator	Nord Stream AG	
TEN-E Project ?	Project of European Interest	
Interested by PCI ?	Not defined yet	
IGAs	None	
Web Link	www.nord-stream.com	





THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Not applicable
Considered Tariff Regime	Not applicable
Applied for Exemption ?	Not relevant
Exemption granted ?	Not relevant
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	
FID	2014 Q2
Construction	2016
Commissioning	2017 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+1.225,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Greifswald	Yes	exit	871,60	Interconnector Nord Stream	n Hub Germany
DESCRIPTION OF THE PROJECT					
DESCRIPTION OF THE PROJECT					
3rd natural gas pipelines from Russia to Germany through the Baltic Sea					
EXPECTED BENEFITS					
Security of Supply, Diversification of sources, Increasing reliability of supply by a in light of declining indigenous production; will as complementary low carbon en					rket; meeting the growing import gap, especially of Northwestern Europe
in light of decilining margenous production, will as complementary low carbon en	ergy source se	ive the EO to	Theet its energy and de-car	DOTTIZACION GOAIS	
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing



# TRA-N-069 Nord Stream 4 Non-FID


# **Pipeline including CS**

# SPONSORS

# GDF Suez (9%) Gasunie (9%) Wintershall (16%) E.ON Ruhrgas (16%)

Promoter	Nord Stream AG
Operator	Nord Stream AG
TEN-E Project ?	Project of European Interest
Interested by PCI ?	Not defined yet
IGAs	None
Web Link	www.nord-stream.com





THIRD-PARTY ACCESS REGIME				
Considered TPA Regime	Not applicable			
Considered Tariff Regime	Not applicable			
Applied for Exemption ?	Not relevant			
Exemption granted ?	Not relevant			
% Exemption in entry direction	0%			
% Exemption in exit direction	0%			

SCHEDULE	
End of permitting phase	
FID	2014 Q2
Construction	2017
Commissioning	2018 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+1.225,00
Total Compressor Power (MW)	
Maximum Capacity (GWh/d)	
Expected Load Factor	




Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Greifswald	Yes	exit	871,60	Interconnector Nord Stream	n Hub Germany
DESCRIPTION OF THE PROJECT					
4 natural gas pipelines from Russia to Germany through the Baltic Sea					
EXPECTED BENEFITS					
EN ESTED DENETHO					
Security of Supply, Diversification of sources, Increasing reliability of supply by a	modern direc	t nineline co	nnection: increasing the lig	uidity of the European gas ma	arket: meeting the growing import gap, especially of Northwestern Furone
in light of declining indigenous production; will as complementary low carbon ene					incet, meeting the growing import gap, especially of Northwestern Europe
COMMENTS ABOUT THE PROJECT FINANCING					
Public financing	Private fina	ncing			Multilateral financing



# TRA-N-035 Tauerngasleitung Gas Pipeline Project Non-FID


# **Pipeline including CS**

# SPONSORS



Promoter	Tauerngas	Tauerngasleitung GmbH		
Operator	Tauerngas	Tauerngasleitung GmbH		
TEN-E Project ?	Project of co	Project of common interest		
Interested by PCI ?		Yes		
IGAs	P	None		
Web Link	www.tauerngasleitung.at			
TEN-E Requests	Date of Request 26/04/06	Year Funding Granted 2007		
	28/04/10	2011		





THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Regulated
Considered Tariff Regime	Regulated
Applied for Exemption ?	Not yet
Exemption granted ?	No
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2014 Q4
FID	2014 Q2
Construction	2015 Q1
Commissioning	2018 Q4
Last completed Phase :	Planned

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	1
Total Pipeline Length (km)	+290,00
Total Compressor Power (MW)	+66,00
Maximum Capacity (GWh/d)	+125,27
Expected Load Factor	



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Haiming (bayernets) - DE / Burghausen (Transit) - TGL	Yes	exit	30,14	Interconnector Tauerngas Leitung	Hub Germany(NCG)
Haiming-Oberkappel (OGE) - DE / Burghausen (Transit) - TGL	Yes	exit	33,82	Interconnector Tauerngas Leitung	Hub Germany(NCG)
Haiming (bayernets) - DE / Burghausen (Transit) - TGL	Yes	entry	180,74	Hub Germany(NCG)	Interconnector Tauerngas Leitung
Haiming (bayernets) - DE / Burghausen-Auerbach (Austrian Storage) - TGL	Yes	exit	136,65	Storage Austria	Hub Germany(NCG)
Haiming (OGE) - DE / Burghausen-Auerbach (Austrian Storage) - TGL	Yes	entry	143,82	Hub Germany(NCG)	Storage Austria
Tarvisio - IT / Arnoldstein (Transit) - TGL	Yes	entry	65,40	Hub Italia	Interconnector Tauerngas Leitung
	Yes	exit	314,96	Interconnector Tauerngas Leitung	Hub Italia
Haiming (bayernets) - DE / Burghausen (Austrian Hub) - TGL	Yes	entry	148,61	Hub Germany(NCG)	Hub Austria

# **DESCRIPTION OF THE PROJECT**

Pipeline (incl. compressor stations) in North-South direction. TGL allows feed significant volumes from different sources from South-East regions towards Central Europe.

# **EXPECTED BENEFITS**

Security of Supply, Market integration, Reverse Flows, Diversification of sources, Diversification of routes, N-1 National, N-1 Regional, Back-up for renewables, Power-to-gas, Biogas

Sos: Investments will be necessary, especially in cross-border gas transmission capacity, with a view to diversifying sources of supply, and gas transmission systems in general, especially where capacities may be needed in an emergency to supply areas with capacity shortfalls. The TGL is in line with these objectives, which focus mainly on security of supplies.

Market Integration: By linking the Central European (Southern Germany) with the South-East European (mainly Italy) natural gas market, the TGL increases interoperability between gas markets in Europe which are still separate, develop new natural gas sources for these markets and therefore significantly improve competition within a European single market for natural gas.

Diversification of European natural gas supplies: By creating the infrastructure required for a functioning North-South/South-North system to develop the North African and Arab supply region, including liquefied natural gas (LNG) for the Mediterranean region, the TGL will reduce dependence on individual suppliers in the North and East.

Public financing	Private financing	Multilateral financing
	Own financing 30%. Loans 70% of which 70-80% from commercial banks and the rest from multilateral financing	20-30% of 70% of the overall external financing needs




# TRA-N-051 Trans Adriatic Pipeline Non-FID


# **Pipeline including CS**

# SPONSORS

# GENERAL INFORMATION



Promoter	Trans-Adr	Trans-Adriatic Pipeline AG		
Operator	Trans-Adr	Trans-Adriatic Pipeline AG		
TEN-E Project ?	Project of	Project of Common Interest		
Interested by PCI ?		Yes		
IGAs		4		
Web Link	www.trans-adriatic-pipelin	e.com		
TEN-E Requests	Date of Request 16/05/05	Year Funding Granted 2009		
	21/04/04	2008		



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	Yes
Exemption granted ?	No
% Exemption in entry direction	100%
% Exemption in exit direction	100%

SCHEDULE	
End of permitting phase	2013 Q2
FID	2013 Q2
Construction	2015 Q1
Commissioning	2018 Q4
Last completed Phase :	FEED

TECHNICAL INFORMATION	
# of Pipelines, nodes, CS	2
Total Pipeline Length (km)	+791,00
Total Compressor Power (MW)	+180,00
Maximum Capacity (GWh/d)	+337,00
Expected Load Factor	90,00%



Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone
Komotini (DESFA) - GR / TAP	Yes	exit	269,60	Interconnector Trans-Adriatic	Hub Greece
Melendugno - IT / TAP	Yes	exit	337,00	Hub Greece	Interconnector Trans-Adriatic Pipeline
Komotini (DESFA) - GR / TAP	Yes	entry	337,00	Dinalina	Hub Italia
Melendugno - IT / TAP	Yes	entry	269,60	Hub Italia	Interconnector Trans-Adriatic Pipeline

# **DESCRIPTION OF THE PROJECT**

The Trans Adriatic Pipeline will start in Greece near Komotini and continue onshore all the way to the Adriatic Sea coast, after crossing the entire territory of Albania from east to west. The offshore part of the pipeline begins near the Albanian city of Fier and crosses the Adriatic Sea to tie into Italy's gas transportation grid operated by Snam Rete Gas in the province of Lecce. In its upstream part, TAP will interconnect with the existing DESFA pipeline system in Greece, which is linked further to the east with systems in Turkey, to secure access to the Shah Deniz natural gas field in Azerbaijan.

# **EXPECTED BENEFITS**

Security of Supply, Market integration [Italy, Greece and potentially Albania, with the potential to further integrate the Western Balkans (Croatia) and broader South Eastern Europe area (Bulgaria, FYROM, Serbia, Hungary, Romania, Slovenia, Austria)], Reverse Flows, Diversification of sources, Diversification of routes, N-1 National (Italy, Greece, and potentially Albania), N-1 Regional [Italy, Greece and potentially Albania, Western Balkans (Croatia) and broader South Eastern Europe (Bulgaria, FYROM, Serbia, Hungary, Romania, Slovenia, Austria)], Back-up for renewables.

TAP represents the shortest and most economic way to secure gas from Shah Deniz 2 field within EU borders.

TAP will directly support the development of competition in the Italian and European gas markets. In addition to promoting diversification of routes and supply sources, TAP will also support diversification of counterparts (and shippers), as new players enter the markets together with completely new sources of gas. The entry of new counterparts in the Italian market will directly contribute to the development of the Italian gas hub and overall liquidity of the Italian market. By bringing new counterparts and increasing liquidity, TAP can make a crucial contribution to the increase of competition in European gas markets.

Public financing	Private financing	Multilateral financing
	Own financing 30%. Loans 70%, of which 70-80% from commercial banks and multilateral financing $$	30% of 70% of the overall external financing needs




TRA-N-053	White Stream	Non-FID

# **Pipeline including CS**

# **SPONSORS**

# **GENERAL INFORMATION**


# **FINANCING**



Promoter	White Stream
Operator	White Stream
TEN-E Project ?	Priority Project
Interested by PCI ?	Yes
IGAs	2
Web Link	

 TEN-E Requests
 Date of Request 31/08/07
 Year Funding Granted 2009

 30/06/08
 2011



THIRD-PARTY ACCESS REGIME	
Considered TPA Regime	Negotiated (e.g. Exemption)
Considered Tariff Regime	Negotiated (e.g. Exemption)
Applied for Exemption ?	Not yet
Exemption granted ?	Not yet
% Exemption in entry direction	0%
% Exemption in exit direction	0%

SCHEDULE	
End of permitting phase	2016 Q1
FID	2016 Q2
Construction	2019 Q2
Commissioning	2019 Q4
Last completed Phase :	Planned

FECHNICAL INFORMATION	
of Pipelines, nodes, CS	2
Total Pipeline Length (km)	+1.250,00
Total Compressor Power (MW)	+375,00
Maximum Capacity (GWh/d)	+487,00
Expected Load Factor	95,00%



PROJECTED CAPACITY INCREASES						
Interconnection	Modelled	Direction	Capacity (GWh/d)	From Zone	To Zone	
White Stream into Romania (RO)	Yes	exit	505,00	Supplier Caspia	Hub Romania	
DESCRIPTION OF THE PROJECT						
The WS pipeline will transport gas produced in the Caspian area from Georgia to the EU. It will branch off an existing pipeline from Azerbaijan to Georgia and will include an onshore pipeline to the Black Sea Georgian coast where a major compressor station will provide the high pressue required to transmit gas to Romania, across the Black Sea.						
EXPECTED BENEFITS						
Security of Supply, Diversification of sources, Diversification of routes, N-1 National,, N-1 Regional, Back-up for renewables, Extension of transport capacity of Russian gas to the West, Integration of Nord Stream off- and on-Shore in the European gas infrastructure						
COMMENTS ABOUT THE PROJECT FINANCING						
Public financing	Private fina	ncing			Multilateral financing	



ENTSOG AISBL
Avenue de Cortenbergh 100
B-1000 Brussels
T +32 (0)2 894 51 00
info@entsog.eu
www.entsog.eu

